

### **Attachment 1**

1. First map identifies outfall location
2. Second map more clearly shows receiving stream. Outfall location is immediately below cross section B. The cross sections designate approximate sampling locations for the dissolved oxygen monitoring required by the permit.






Figure 1  
SITE LOCATION MAP



TAKEN FROM USGS MAP  
ASHLAND QUADRANGLE,  
PHOTOREVISED 1985


**ALVARE** ENVIRONMENTAL INC



## **Attachment 2**

Four schematics are included:


1. Overall water flow schematic
2. Treatment facilities at the Doswell Wastewater Treatment Plant
3. Flow schematic for Bear Island
4. Treatment facilities at the Bear Island Wastewater Treatment Plant




FORM 2c II.A.i MILL WATER BALANCE		
BEAR ISLAND PAPER COMPANY, L.L.C. WASTEWATER TREATMENT PLANT		
SCALE NOT TO SCALE	APPROVED BY :	DRAWN BY: J.K.S.
DATE AUGUST 1999	DESIGNED BY :	REVISED OCT. 1999
PROJECT NUMBER N106-22	<b>AWARE</b> INC. <small>9305-J MONROE RD. CHARLOTTE, NC 28270</small>	
	DRAWING NO. <b>FIGURE</b>	

October 18, 1999 2:40:37 p.m.  
Drawing: N106-10617PC4.DWG

FIGURE 2



**HAZEN AND SAWYER**  
Environmental Engineers & Scientists



FORM 2c II.A.ii  
MILL WATER USAGE

BEAR ISLAND PAPER COMPANY, L.L.C.  
WASTEWATER TREATMENT PLANT

SCALE NOT TO SCALE

DATE AUGUST 1999

PROJECT NUMBER  
N106-22

APPROVED BY :


DESIGNED BY :

**AWARE** ENVIRONMENTAL INC.  
9305-J MONROE RD, CHARLOTTE, NC 28270

DRAWN BY: J.K.S.

REVISED

DRAWING NO.  
FIGURE



# LEGEND

- LIQUID LINE
- - - SLUDGE LINE
- . - . FILTRATE LINE

FORM 2c II.B.3.a	
PROCESS FLOW SCHEMATIC	
BEAR ISLAND PAPER COMPANY, L.L.C.	
WASTEWATER TREATMENT PLANT	
SCALE NOT TO SCALE	APPROVED BY: J.K.S.
DATE: AUGUST 1999	DESIGNED BY: J.K.S.
PROJECT NUMBER: N106-17	DRAWING NO: FIGURE
B-25-J MONROE RD. CHARLOTTE, NC 28205	



### **Attachment 3**

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	1/8/1979	S	.30	6.50	7.30		11.30
8-NAR005.42	3/22/1979	S	.30	12.00	7.00		10.50
8-NAR005.42	4/24/1979	S	.30	15.00	7.50		9.80
8-NAR005.42	6/14/1979	S	.30	21.00	7.00		7.20
8-NAR005.42	8/8/1979	S	.30	28.00	6.80		6.40
8-NAR005.42	9/20/1979	S	.30	18.00	7.00		8.40
8-NAR005.42	10/16/1979	S	.30	13.50	7.00		10.00
8-NAR005.42	11/14/1979	S	.30	9.50	7.00		10.50
8-NAR005.42	12/11/1979	S	.30	6.50	7.00		11.60
8-NAR005.42	1/29/1980	S	.30	4.00	7.10		11.80
8-NAR005.42	2/27/1980	S	.30	5.00	6.80		12.40
8-NAR005.42	3/17/1980	S	.30	8.50	6.70		11.20
8-NAR005.42	4/15/1980	S	.30	14.00	7.40		9.30
8-NAR005.42	5/12/1980	S	.30	18.00	7.50		9.00
8-NAR005.42	6/16/1980	S	.30	25.00	7.10		7.80
8-NAR005.42	7/10/1980	S	.30	27.00	6.80		6.80
8-NAR005.42	8/4/1980	S	.30	29.00	7.20		7.10
8-NAR005.42	9/8/1980	S	.30	25.00	6.90		7.20
8-NAR005.42	10/14/1980	S	.30	14.00	7.30		10.40
8-NAR005.42	11/24/1980	S	.30	5.50	6.90		11.40
8-NAR005.42	12/16/1980	S	.30	4.00	6.50		12.20
8-NAR005.42	1/20/1981	S	.30	.50	6.50		11.60
8-NAR005.42	2/17/1981	S	.30	5.50	7.00		12.00
8-NAR005.42	3/18/1981	S	.30	5.00	6.80		11.50
8-NAR005.42	4/16/1981	S	.30	13.00	7.50		11.00
8-NAR005.42	5/12/1981	S	.30	17.00	7.00		8.40
8-NAR005.42	6/15/1981	S	.30	28.50	7.40		8.10
8-NAR005.42	7/14/1981	S	.30	28.00	7.00		7.00
8-NAR005.42	8/12/1981	S	.30	24.70	7.00		6.40
8-NAR005.42	9/10/1981	S	.30	21.50	7.00		7.90
8-NAR005.42	11/19/1981	S	.30	9.00	7.00		5.00
8-NAR005.42	12/8/1981	S	.30	6.00	6.50		12.20
8-NAR005.42	2/9/1982	S	.30	6.00	6.70		9.40
8-NAR005.42	3/24/1982	S	.30	10.00	6.70		9.20
8-NAR005.42	4/28/1982	S	.30	15.00	6.80		
8-NAR005.42	6/29/1982	S	.30	27.00	6.80		5.90
8-NAR005.42	7/28/1982	S	.30	28.50	7.00		5.80
8-NAR005.42	8/18/1982	S	.30	24.50	6.80		6.20
8-NAR005.42	10/19/1982	S	.30	13.00	6.70		9.80
8-NAR005.42	11/17/1982	S	.30		6.70		11.40
8-NAR005.42	12/16/1982	S	.30	8.00	6.50		10.80
8-NAR005.42	1/27/1983	S	.30	3.50	6.70		12.10
8-NAR005.42	2/10/1983	S	.30	4.00	6.50		12.70
8-NAR005.42	3/15/1983	S	.30	12.00	6.70		10.00
8-NAR005.42	4/19/1983	S	.30	11.00	6.50		11.00
8-NAR005.42	5/19/1983	S	.30	17.00	6.80		9.50
8-NAR005.42	6/21/1983	S	.30	24.50	6.80		7.40
8-NAR005.42	7/12/1983	S	.30	26.00	7.00		7.20
8-NAR005.42	11/15/1983	S	.30	7.00	6.50		11.30
8-NAR005.42	12/8/1983	S	.30	8.00	6.00		12.00
8-NAR005.42	2/7/1984	S	.30	3.00	5.90		13.50

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	3/5/1984	S	.30	8.00	5.50		12.00
8-NAR005.42	4/26/1984	S	.30	9.00	5.90		9.90
8-NAR005.42	6/4/1984	S	.30	21.50	6.60		7.70
8-NAR005.42	7/2/1984	S	.30	25.00	6.92		7.70
8-NAR005.42	8/6/1984	S	.30	25.00	5.90		7.60
8-NAR005.42	9/5/1984	S	.30	21.00	6.69		12.40
8-NAR005.42	10/10/1984	S	.30	18.50	6.10		6.20
8-NAR005.42	1/7/1985	S	.30	8.00	6.06		11.10
8-NAR005.42	2/20/1985	S	.30	4.50	5.70		12.00
8-NAR005.42	3/6/1985	S	.30	6.50			12.20
8-NAR005.42	4/3/1985	S	.30	10.00	6.50		11.40
8-NAR005.42	5/7/1985	S	.30	20.00	6.50		9.90
8-NAR005.42	6/17/1985	S	.30	22.70	6.80		7.80
8-NAR005.42	7/9/1985	S	.30	24.00	6.20		8.10
8-NAR005.42	8/27/1985	S	.30	24.00	6.40		7.60
8-NAR005.42	9/24/1985	S	.30	20.90	6.70		8.60
8-NAR005.42	10/22/1985	S	.30	15.70	5.95		1.00
8-NAR005.42	12/2/1985	S	.30	11.00	6.50		11.10
8-NAR005.42	1/7/1986	S	.30	3.00	6.30		13.00
8-NAR005.42	2/4/1986	S	.30	6.00	6.60		11.80
8-NAR005.42	3/4/1986	S	.30	6.00	6.70		12.30
8-NAR005.42	4/1/1986	S	.30	16.00	6.90		10.40
8-NAR005.42	5/5/1986	S	.30	16.00	7.06		8.90
8-NAR005.42	6/12/1986	S	.30	27.00	7.51		7.50
8-NAR005.42	7/1/1986	S	.30	24.00	7.58		7.80
8-NAR005.42	8/12/1986	S	.30	24.00	7.47		7.40
8-NAR005.42	9/11/1986	S	.30	22.00	7.70		8.90
8-NAR005.42	10/15/1986	S	.30	16.50	7.50		8.00
8-NAR005.42	11/6/1986	S	.30	9.00	7.25		10.10
8-NAR005.42	12/8/1986	S	.30	5.00	7.60		11.80
8-NAR005.42	1/15/1987	S	.30	9.00	7.56		11.10
8-NAR005.42	2/10/1987	S	.30	3.70	7.24		12.40
8-NAR005.42	3/9/1987	S	.30	11.00	7.81		10.50
8-NAR005.42	4/27/1987	S	.30	14.50	7.35		10.00
8-NAR005.42	5/13/1987	S	.30	20.50	7.30		8.20
8-NAR005.42	6/10/1987	S	.30	22.80	7.10		6.00
8-NAR005.42	7/22/1987	S	.30	29.00	6.63		4.20
8-NAR005.42	7/22/1987	S	.30	29.00	6.63		4.20
8-NAR005.42	8/6/1987	S	.30	27.40	7.00		7.30
8-NAR005.42	8/6/1987	S	.30	27.40	7.00		7.30
8-NAR005.42	9/14/1987	S	.30	25.00	7.49		7.60
8-NAR005.42	10/13/1987	S	.30	11.50	7.86		10.00
8-NAR005.42	11/18/1987	S	.30	14.00	8.06		10.50
8-NAR005.42	12/22/1987	S	.30	9.00	8.54		11.20
8-NAR005.42	1/12/1988	S	.30	1.00	8.16		15.20
8-NAR005.42	3/28/1988	S	.30	12.10	7.64		10.20
8-NAR005.42	4/27/1988	S	.30	17.50	7.58		9.60
8-NAR005.42	5/10/1988	S	.30	19.00	7.29		8.70
8-NAR005.42	6/6/1988	S	.30	21.00	8.82		8.30
8-NAR005.42	7/6/1988	S	.30	24.50	7.10		8.20
8-NAR005.42	8/23/1988	S	.30	22.80	7.57		7.60

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	9/19/1988	S	.30	22.00	7.28		8.60
8-NAR005.42	10/6/1988	S	.30	14.00	7.25		9.60
8-NAR005.42	12/8/1988	S	.30				
8-NAR005.42	1/25/1989	S	.30	4.90	6.82		14.30
8-NAR005.42	2/16/1989	S	.30	10.20	7.31		11.50
8-NAR005.42	3/9/1989	S	.30				
8-NAR005.42	4/19/1989	S	.30	15.60	7.86		10.80
8-NAR005.42	5/16/1989	S	.30	14.50	7.30		9.60
8-NAR005.42	6/15/1989	S	.30	25.50	7.00		7.60
8-NAR005.42	7/25/1989	S	.30	28.20	7.00		7.20
8-NAR005.42	8/14/1989	S	.30	23.20	7.32		9.20
8-NAR005.42	9/14/1989	S	.30	24.70	6.74		7.00
8-NAR005.42	10/10/1989	S	.30	11.70	7.65		11.40
8-NAR005.42	11/15/1989	S	.30	17.30	7.33		10.20
8-NAR005.42	12/14/1989	S	.30	4.70	7.40		13.30
8-NAR005.42	1/10/1990	S	.30	6.50	7.05		12.60
8-NAR005.42	2/7/1990	S	.30	10.00	7.30		12.50
8-NAR005.42	3/7/1990	S	.30	8.20	7.90		12.70
8-NAR005.42	4/12/1990	S	.30	12.00	7.86		10.70
8-NAR005.42	5/15/1990	S	.30	18.90	6.46		8.70
8-NAR005.42	6/12/1990	S	.30	21.10	7.73		8.20
8-NAR005.42	7/17/1990	S	.30	25.70	7.34		7.20
8-NAR005.42	8/14/1990	S	.30			7.43	
8-NAR005.42	8/14/1990	B	1.00	25.78	6.97	7.43	
8-NAR005.42	9/17/1990	S	.30	20.10	7.36	7.95	8.00
8-NAR005.42	10/15/1990	S	.30	21.20	6.84	7.50	
8-NAR005.42	10/15/1990	B	1.00				
8-NAR005.42	11/28/1990	S	.30	12.60	7.04	10.16	10.20
8-NAR005.42	12/17/1990	S	.09	9.50	7.34	11.75	11.80
8-NAR005.42	1/15/1991	S	.30				
8-NAR005.42	2/5/1991	S	.30				
8-NAR005.42	3/13/1991	S	.09	7.69	7.39	11.53	11.50
8-NAR005.42	3/13/1991	B	304.50	7.70	7.39		11.50
8-NAR005.42	4/10/1991	S	.09	19.75	7.31	8.91	8.91
8-NAR005.42	4/10/1991	B	.30				
8-NAR005.42	5/8/1991	S	.09	19.30	6.95	8.27	8.30
8-NAR005.42	6/5/1991	S	.30	22.09	7.28		7.79
8-NAR005.42	7/1/1991	S	.30	27.49	6.92	7.06	
8-NAR005.42	8/5/1991	S	.30	25.62	6.40	7.11	
8-NAR005.42	9/4/1991	S	.30	21.50	6.83	8.77	
8-NAR005.42	9/30/1991	S	.30	18.17	7.43	8.87	
8-NAR005.42	9/30/1991	S	.30				
8-NAR005.42	12/3/1991	S	.30	11.57	6.67	9.60	
8-NAR005.42	1/6/1992	S	.30	7.03	6.37	11.79	
8-NAR005.42	2/18/1992	S	.30	6.80	6.45	11.88	
8-NAR005.42	3/4/1992	S	.30	10.50	6.60	11.06	
8-NAR005.42	4/13/1992	S	.30	15.90	6.39	10.05	
8-NAR005.42	5/11/1992	S	.30	16.36	6.01	8.87	
8-NAR005.42	6/10/1992	S	.30	22.86	6.66	7.49	
8-NAR005.42	7/7/1992	S	.30	23.37	6.27	6.78	
8-NAR005.42	8/17/1992	S	.30	21.12	6.02	7.89	

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	9/2/1992	S	.30	22.08	6.70	7.86	
8-NAR005.42	10/1/1992	S	.30	14.90	6.53	9.33	
8-NAR005.42	11/3/1992	S	.30	14.67	6.38	11.14	
8-NAR005.42	12/2/1992	S	.30	8.15	6.74	11.20	
8-NAR005.42	1/5/1993	S	.30	10.86	6.41	10.85	
8-NAR005.42	2/1/1993	S	.30	5.82	6.61	11.89	
8-NAR005.42	3/3/1993	S	.30	7.36	6.51	11.55	
8-NAR005.42	4/5/1993	S	.30	11.05	6.38	10.10	
8-NAR005.42	5/4/1993	S	.30	18.58	6.34	8.71	
8-NAR005.42	6/1/1993	S	.30	20.93	6.26	7.89	
8-NAR005.42	7/12/1993	S	.30	28.01	6.44	6.12	
8-NAR005.42	8/9/1993	S	.30	23.28	6.23	7.32	
8-NAR005.42	9/1/1993	S	.30	25.75	6.54	7.30	
8-NAR005.42	10/7/1993	S	.30	14.82	6.89	9.89	
8-NAR005.42	11/2/1993	S	.30	7.89	6.56	11.07	
8-NAR005.42	12/20/1993	S	.30	6.72	6.78	12.03	
8-NAR005.42	1/31/1994	S	.30	4.18	6.60	12.35	
8-NAR005.42	2/10/1994	S	.30	4.99	6.61	12.35	
8-NAR005.42	3/7/1994	S	.30	8.99	6.49	11.63	
8-NAR005.42	4/11/1994	S	.30	15.17	6.47	9.55	
8-NAR005.42	5/11/1994	S	.30	16.64	6.32	9.16	
8-NAR005.42	6/8/1994	S	.30	25.00	6.51	6.81	
8-NAR005.42	7/11/1994	S	.30	26.32	6.55	6.77	
8-NAR005.42	8/3/1994	S	.30	25.62	6.41	6.64	
8-NAR005.42	9/12/1994	S	.30	19.74	6.81	8.17	
8-NAR005.42	10/11/1994	S	.30	14.01	6.65	9.13	
8-NAR005.42	11/1/1994	S	.30	15.69	6.56	8.31	
8-NAR005.42	12/5/1994	S	.30	9.90	6.75	10.65	
8-NAR005.42	1/4/1995	S	.30	4.63	6.72	12.29	
8-NAR005.42	2/1/1995	S	.30	4.69	6.50	12.68	
8-NAR005.42	3/22/1995	S	.30	13.23	6.59	9.37	
8-NAR005.42	4/25/1995	S	.30	13.76	6.91	10.25	
8-NAR005.42	5/24/1995	S	.30	22.13	6.52	7.94	
8-NAR005.42	6/27/1995	S	.30	25.14	6.42	7.41	
8-NAR005.42	7/26/1995	S	.30	28.95	6.72	6.69	
8-NAR005.42	8/31/1995	S	.30	25.15	6.85	7.34	
8-NAR005.42	9/27/1995	S	.30	16.53	6.82	8.54	
8-NAR005.42	10/12/1995	S	.30	16.62	6.65	8.06	
8-NAR005.42	11/8/1995	S	.30	12.54	6.69	10.01	
8-NAR005.42	12/27/1995	S	.30	3.84	6.65	12.78	
8-NAR005.42	1/31/1996	S	.30	6.54	6.13	11.85	
8-NAR005.42	2/27/1996	S	.30	8.34	6.36	10.69	
8-NAR005.42	3/25/1996	S	.30	9.04	6.26	11.42	
8-NAR005.42	4/18/1996	S	.30	13.96	6.56	10.32	
8-NAR005.42	5/30/1996	S	.30	18.14	6.83	9.17	
8-NAR005.42	6/24/1996	S	.30	27.50	6.71	6.86	
8-NAR005.42	7/29/1996	S	.30	25.09	6.84	7.30	
8-NAR005.42	8/26/1996	S	.30	24.52	6.60	6.90	
8-NAR005.42	9/24/1996	S	.30	19.24	6.54	9.81	
8-NAR005.42	10/29/1996	S	.30	16.58	6.46	7.53	
8-NAR005.42	11/25/1996	S	.30	8.04	6.50	11.33	

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	12/19/1996	S	.30	9.39	6.57	10.90	
8-NAR005.42	1/27/1997	S	.30	6.27	6.77	12.22	
8-NAR005.42	2/13/1997	S	.30	6.07	6.80	12.83	
8-NAR005.42	3/17/1997	S	.30	8.57	6.74	11.01	
8-NAR005.42	4/9/1997	S	.30	13.30	6.63	9.76	
8-NAR005.42	5/5/1997	S	.30	16.03	6.67	9.14	
8-NAR005.42	6/2/1997	S	.30	20.21	6.35	7.94	
8-NAR005.42	7/2/1997	S	.30				
8-NAR005.42	8/4/1997	S	.30	25.85	6.72	7.19	
8-NAR005.42	9/25/1997	S	.30	17.86	6.96	9.00	
8-NAR005.42	10/22/1997	S	.30	12.70	7.10	10.45	
8-NAR005.42	11/10/1997	S	.60				
8-NAR005.42	11/12/1997	S	.30	13.64	6.77	9.46	
8-NAR005.42	12/8/1997	S	.30	5.86	6.65	12.08	
8-NAR005.42	1/12/1998	S	.30	8.65	6.61	11.46	
8-NAR005.42	2/12/1998	S	.30	8.69	6.78	11.11	
8-NAR005.42	3/12/1998	S	.30	8.62	6.30	11.57	
8-NAR005.42	4/13/1998	S	.30	14.38	6.64	10.30	
8-NAR005.42	5/5/1998	S	.30	16.69	6.49	8.81	
8-NAR005.42	6/1/1998	S	.30	25.76	6.75	7.24	
8-NAR005.42	7/6/1998	S	.30	26.01	6.66	7.11	
8-NAR005.42	8/19/1998	S	.30	25.25	6.56	7.41	
8-NAR005.42	9/15/1998	S	.30	23.23	6.71	6.84	
8-NAR005.42	10/6/1998	S	.30	17.31	6.68	8.46	
8-NAR005.42	11/3/1998	S	.30	11.68	6.50	9.57	
8-NAR005.42	12/14/1998	S	.30	6.98	6.35	11.08	
8-NAR005.42	1/12/1999	S	.30	1.88	6.12	13.52	
8-NAR005.42	2/9/1999	S	.30	5.68	6.46	11.97	
8-NAR005.42	3/16/1999	S	.30	9.10	6.17	11.60	
8-NAR005.42	4/19/1999	S	.30	12.70	6.70	9.88	
8-NAR005.42	5/19/1999	S	.30	20.28	6.48	8.08	
8-NAR005.42	6/22/1999	S	.30	20.95	6.83	8.35	
8-NAR005.42	7/1/1999	S	.30	24.89	6.84	6.64	
8-NAR005.42	8/3/1999	S	.30	25.75	6.83	6.76	
8-NAR005.42	9/1/1999	S	.30	20.21	6.93	8.66	
8-NAR005.42	10/18/1999	S	.30	15.88	6.54	9.01	
8-NAR005.42	11/2/1999	S	.30	14.58	6.28	8.75	
8-NAR005.42	12/28/1999	S	.30	3.71	6.71	13.17	
8-NAR005.42	1/5/2000	S	.30	9.81	6.79	10.38	
8-NAR005.42	2/3/2000	S	.30	3.11	6.54	14.70	
8-NAR005.42	3/1/2000	S	.30	10.80	7.07	10.95	
8-NAR005.42	4/12/2000	S	.30	15.66	6.84	8.90	
8-NAR005.42	5/3/2000	S	.30	17.86	6.93	8.93	
8-NAR005.42	6/7/2000	S	.30	19.10	6.56	7.85	
8-NAR005.42	7/6/2000	S	.30	26.18	6.70	6.66	
8-NAR005.42	8/8/2000	S	.30	26.80	6.58	6.17	
8-NAR005.42	9/12/2000	S	.30	22.74	6.75	6.58	
8-NAR005.42	10/16/2000	S	.30	13.89	6.81	9.33	
8-NAR005.42	11/13/2000	S	.30	9.64	6.79	9.77	
8-NAR005.42	12/27/2000	S	.30				
8-NAR005.42	1/16/2001	S	.30	4.13	6.70	12.53	

Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	1/31/2001	S	.30	7.65	6.89	11.76	
8-NAR005.42	3/12/2001	S	.30	9.04	6.79	11.15	
8-NAR005.42	4/25/2001	S	.30	18.40	6.84	7.57	
8-NAR005.42	6/11/2001	S	.30	23.25	6.51	7.85	
8-NAR005.42	8/8/2001	S	.30	29.30	7.20	7.92	
8-NAR005.42	10/4/2001	S	.30	18.52	7.00	9.11	
8-NAR005.42	12/27/2001	S	.30	.91	6.11	13.57	
8-NAR005.42	2/5/2002	S	.30	3.36	6.54	12.97	
8-NAR005.42	4/3/2002	S	.30	18.96	6.97	9.51	
8-NAR005.42	6/26/2002	S	.30	28.66	7.80		
8-NAR005.42	7/24/2002	S	.30	26.25	6.65	4.98	
8-NAR005.42	9/19/2002	S	.00				
8-NAR005.42	9/19/2002	S	.30				
8-NAR005.42	11/13/2002	S	.30	13.00	6.37	10.83	
8-NAR005.42	1/2/2003	S	.30	7.84	6.59	11.34	
8-NAR005.42	3/11/2003	S	.30	6.75	7.04	11.90	
8-NAR005.42	5/21/2003	S	.30	18.61	6.60	8.75	
8-NAR005.42	7/10/2003	S	.30	26.91	6.79	6.87	
8-NAR005.42	9/16/2003	S	.30	22.41	6.94	7.65	
8-NAR005.42	11/13/2003	S	.30	15.66	6.94	8.69	
8-NAR005.42	1/21/2004	S	.30	3.69	7.17	12.94	
8-NAR005.42	4/19/2004	S	.30	19.47	6.79	9.18	
8-NAR005.42	5/13/2004	S	.30	23.27	6.86	7.94	
8-NAR005.42	7/13/2004	S	.30	27.15	6.56	6.52	
8-NAR005.42	8/12/2004	S	.30	26.26	6.71	7.31	
8-NAR005.42	9/16/2004	S	.30	24.08	6.90	7.72	
8-NAR005.42	10/5/2004	S	.30	19.65	6.55	9.19	
8-NAR005.42	12/1/2004	S	.30	12.38	7.39	12.42	
8-NAR005.42	12/21/2004	S	.30	3.66	8.64	13.14	
8-NAR005.42	1/19/2005	S	.30	5.13	6.94	13.47	
8-NAR005.42	2/8/2005	S	.30	7.78	6.34	11.65	
8-NAR005.42	3/17/2005	S	.30	8.77	6.38	10.90	
8-NAR005.42	4/21/2005	S	.30	19.30	6.72	8.65	
8-NAR005.42	5/31/2005	S	.30	21.15	7.10	6.42	
8-NAR005.42	6/6/2005	S	.30	24.39	6.39	6.54	
8-NAR005.42	8/3/2005	S	.30	26.97	6.92	6.33	
8-NAR005.42	8/17/2005	S	.30	26.11	6.82	6.54	
8-NAR005.42	9/26/2005	S	.30	22.72	7.04	7.10	
8-NAR005.42	10/13/2005	S	.30	18.02	7.00	8.44	
8-NAR005.42	11/7/2005	S	.30	13.70	6.45	8.72	
8-NAR005.42	12/8/2005	S	.30	5.98	7.20		
8-NAR005.42	1/30/2006	S	.30	8.44	6.59	11.20	
8-NAR005.42	2/28/2006	S	.30	6.67	6.94	12.40	
8-NAR005.42	3/23/2006	S	.30	9.70	7.20	11.50	
8-NAR005.42	4/25/2006	S	.30	18.50	7.40	8.60	
8-NAR005.42	6/28/2006	S	.30	23.10	6.80	7.80	
8-NAR005.42	8/16/2006	S	.30	26.30	7.30	7.50	
8-NAR005.42	8/22/2006	S	.30				
8-NAR005.42	10/16/2006	S	.30	14.80	7.30	9.80	
8-NAR005.42	12/5/2006	S	.30	7.60	6.90	11.40	
8-NAR005.42	1/4/2007	S	.30	9.80	6.80	11.50	



Station ID	Collection Date	Depth Desc	Depth	Temp Celcius	Field Ph	Do Probe	Do Winkler
8-NAR005.42	3/8/2007	S	.30	7.30	6.20	11.20	
8-NAR005.42	3/20/2007	I	.00	10.30	6.40	10.30	
8-NAR005.42	4/11/2007	I	.00	10.40	6.70	10.60	
8-NAR005.42	4/16/2007	I	.00	11.90	6.60	10.20	
8-NAR005.42	5/8/2007	S	.30	15.60	6.80	8.80	
8-NAR005.42	5/16/2007	I	.00	21.30	6.90	7.90	
8-NAR005.42	5/30/2007	I	.00	23.00	6.80	7.20	
8-NAR005.42	6/28/2007	I	.00	28.40	7.00	7.00	
8-NAR005.42	7/9/2007	I	.00	27.10	6.90	7.40	
8-NAR005.42	7/12/2007	S	.30	30.30	5.50	4.80	
8-NAR005.42	8/6/2007	I	.00	26.40	7.10	6.50	
8-NAR005.42	9/5/2007	I	.00	22.50	7.00	7.90	
8-NAR005.42	9/11/2007	S	.30	26.20	7.20	7.40	
8-NAR005.42	10/9/2007	I	.00				
8-NAR005.42	10/9/2007	I	.00	23.40	7.40	10.00	
8-NAR005.42	10/25/2007	I	.00	16.80	6.60	7.70	
8-NAR005.42	10/29/2007	I	.00	12.10	6.80	9.70	
8-NAR005.42	11/5/2007	I	.00	10.90	6.90	10.50	
8-NAR005.42	11/5/2007	I	.00				
8-NAR005.42	11/7/2007	I	.00				
8-NAR005.42	11/26/2007	I	.00	8.00	6.90	10.60	
8-NAR005.42	11/27/2007	S	.30	12.10	6.70	10.60	
8-NAR005.42	1/7/2008	S	.30	7.10	6.30	12.00	
8-NAR005.42	1/10/2008	I	.00	7.20	7.10	11.80	
8-NAR005.42	1/29/2008	I	.00	2.60	7.10	13.20	
8-NAR005.42	1/29/2008	I	.00				
8-NAR005.42	2/3/2008	I	.00	4.20	7.00	11.90	
8-NAR005.42	2/26/2008	I	.00	7.10	7.20	12.60	
8-NAR005.42	3/4/2008	S	.30	12.50	6.50	11.80	
8-NAR005.42	3/6/2008	I	.00	11.20	6.90	11.20	
8-NAR005.42	3/9/2008	I	.00	7.90	6.90	11.20	
8-NAR005.42	3/12/2008	I	.00	8.40	6.80	12.00	
8-NAR005.42	3/27/2008	I	.00	13.60	7.00	10.50	
90th Percentile				26.2	7.4		
10th Percentile				5.5	6.4		



00900

HARDNESS, TOTAL  
(MG/L AS CaCO3)

Sta Id	Collection Date Time	Depth		Container	Comment	HARDNESS, TOTAL (MG/L AS CaCO3)	
		Desc	Depth			Value	Com Code
8-NAR005.42	01/25/1989 13:20	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	02/16/1989 13:10	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	03/09/1989 13:00	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	04/19/1989 13:30	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	05/16/1989 13:00	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	06/15/1989 13:50	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	08/14/1989 14:15	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	09/14/1989 14:00	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	10/10/1989 13:30	S	0.3	R	STORET DATA CONVERSION	24	
8-NAR005.42	11/15/1989 13:15	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	12/14/1989 13:35	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	01/10/1990 12:45	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	02/07/1990 13:20	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	03/07/1990 12:30	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	04/12/1990 13:20	S	0.3	R	STORET DATA CONVERSION	30	
8-NAR005.42	05/15/1990 12:15	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	06/12/1990 12:50	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	07/17/1990 12:55	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	09/17/1990 12:00	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	10/15/1990 12:10	S	0.3	R	STORET DATA CONVERSION		
8-NAR005.42	11/28/1990 11:30	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	12/17/1990 12:30	S	0.09	R	STORET DATA CONVERSION	22	
8-NAR005.42	01/15/1991 13:15	S	0.3	R	STORET DATA CONVERSION	24	
8-NAR005.42	02/05/1991 10:45	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	03/13/1991 11:46	B	304.5	R	STORET DATA CONVERSION	22	
8-NAR005.42		S	0.09	R	STORET DATA CONVERSION	22	
8-NAR005.42	04/10/1991 13:20	S	0.09	R	STORET DATA CONVERSION	40	
8-NAR005.42	05/08/1991 10:25	S	0.09	R	STORET DATA CONVERSION	46	
8-NAR005.42	06/05/1991 13:20	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	08/05/1991 10:52	S	0.3	R	STORET DATA CONVERSION	34	
8-NAR005.42	09/04/1991 11:40	S	0.3	R	STORET DATA CONVERSION	34	
8-NAR005.42	12/03/1991 11:31	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	01/06/1992 11:20	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	02/18/1992 10:00	S	0.3	R	STORET DATA CONVERSION	24	
8-NAR005.42	03/04/1992 11:10	S	0.3	R	STORET DATA CONVERSION	24	
8-NAR005.42	04/13/1992 12:30	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	05/11/1992 09:20	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	06/10/1992 10:25	S	0.3	R	STORET DATA CONVERSION	32	
8-NAR005.42	07/07/1992 10:49	S	0.3	R	STORET DATA CONVERSION	28	
8-NAR005.42	08/17/1992 10:34	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	09/02/1992 10:56	S	0.3	R	STORET DATA CONVERSION	2.6	
8-NAR005.42	10/01/1992 11:37	S	0.3	R	STORET DATA CONVERSION	43	
8-NAR005.42	11/03/1992 11:20	S	0.3	R	STORET DATA CONVERSION	34	
8-NAR005.42	12/02/1992 11:00	S	0.3	R	STORET DATA CONVERSION	19	
8-NAR005.42	01/05/1993 11:38	S	0.3	R	STORET DATA CONVERSION	21	
8-NAR005.42	02/01/1993 10:17	S	0.3	R	STORET DATA CONVERSION	28	
8-NAR005.42	03/03/1993 11:33	S	0.3	R	STORET DATA CONVERSION	24	
8-NAR005.42	04/05/1993 10:30	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	05/04/1993 09:30	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	06/01/1993 11:35	S	0.3	R	STORET DATA CONVERSION	21	
8-NAR005.42	07/12/1993 11:00	S	0.3	R	STORET DATA CONVERSION	24	
8-NAR005.42	08/09/1993 10:30	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	09/01/1993 11:10	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	10/07/1993 12:22	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	11/02/1993 10:15	S	0.3	R	STORET DATA CONVERSION	38	
8-NAR005.42	12/20/1993 12:41	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	01/31/1994 11:25	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	02/10/1994 10:55	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	03/07/1994 12:44	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	04/11/1994 12:34	S	0.3	R	STORET DATA CONVERSION	15	
8-NAR005.42	05/11/1994 11:00	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	06/08/1994 10:47	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	07/11/1994 11:00	S	0.3	R	STORET DATA CONVERSION	17	

00900

HARDNESS, TOTAL  
(MG/L AS CaCO3)

Sta Id	Collection Date Time	Depth		Container	Comment	HARDNESS, TOTAL (MG/L AS CaCO3)	
		Desc	Depth			Value	Com Code
8-NAR005.42	08/03/1994 12:11	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	09/12/1994 13:00	S	0.3	R	STORET DATA CONVERSION	26	
8-NAR005.42	10/11/1994 12:00	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	11/01/1994 11:00	S	0.3	R	STORET DATA CONVERSION	19	
8-NAR005.42	12/05/1994 10:00	S	0.3	R	STORET DATA CONVERSION	19	
8-NAR005.42	01/04/1995 12:22	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	02/01/1995 11:21	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	03/22/1995 09:14	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	04/25/1995 13:20	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	05/24/1995 12:30	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	06/27/1995 08:00	S	0.3	R	STORET DATA CONVERSION	15	
8-NAR005.42	07/26/1995 11:35	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	08/31/1995 11:40	S	0.3	R	STORET DATA CONVERSION	25	
8-NAR005.42	09/27/1995 11:00	S	0.3	R	STORET DATA CONVERSION	13	
8-NAR005.42	10/12/1995 10:45	S	0.3	R	STORET DATA CONVERSION	23	
8-NAR005.42	11/08/1995 10:00	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	12/27/1995 10:00	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	01/31/1996 12:05	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	02/27/1996 10:20	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	03/25/1996 09:45	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	04/18/1996 12:30	S	0.3	R	STORET DATA CONVERSION	13	
8-NAR005.42	05/30/1996 11:30	S	0.3	R	STORET DATA CONVERSION	30	
8-NAR005.42	06/24/1996 09:00	S	0.3	R	STORET DATA CONVERSION	16	
8-NAR005.42	07/29/1996 10:30	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	08/26/1996 08:45	S	0.3	R	STORET DATA CONVERSION	20	
8-NAR005.42	09/24/1996 07:37	S	0.3	R	STORET DATA CONVERSION	21	
8-NAR005.42	10/29/1996 12:50	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	11/25/1996 10:00	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	12/19/1996 11:11	S	0.3	R	STORET DATA CONVERSION	15	
8-NAR005.42	01/27/1997 13:22	S	0.3	R	STORET DATA CONVERSION	15.6	
8-NAR005.42	02/13/1997 09:54	S	0.3	R	STORET DATA CONVERSION	16.9	
8-NAR005.42	03/17/1997 07:55	S	0.3	R	STORET DATA CONVERSION	18.5	
8-NAR005.42	04/09/1997 11:11	S	0.3	R	STORET DATA CONVERSION	20.7	
8-NAR005.42	05/05/1997 11:44	S	0.3	R	STORET DATA CONVERSION	20.7	
8-NAR005.42	06/02/1997 10:31	S	0.3	R	STORET DATA CONVERSION	22	
8-NAR005.42	07/02/1997 11:55	S	0.3	R	STORET DATA CONVERSION	15.7	
8-NAR005.42	08/04/1997 11:44	S	0.3	R	STORET DATA CONVERSION	19.8	
8-NAR005.42	09/25/1997 15:23	S	0.3	R	STORET DATA CONVERSION	19.1	
8-NAR005.42	10/22/1997 11:30	S	0.3	R	STORET DATA CONVERSION	16.4	
8-NAR005.42	11/12/1997 12:55	S	0.3	R	STORET DATA CONVERSION	13.3	
8-NAR005.42	12/08/1997 12:33	S	0.3	R	STORET DATA CONVERSION	21	
8-NAR005.42	01/12/1998 14:15	S	0.3	R	STORET DATA CONVERSION	48	
8-NAR005.42	02/12/1998 11:01	S	0.3	R	STORET DATA CONVERSION	13.8	
8-NAR005.42	03/12/1998 13:00	S	0.3	R	STORET DATA CONVERSION	18	
8-NAR005.42	04/13/1998 12:40	S	0.3	R	STORET DATA CONVERSION	13.1	
8-NAR005.42	05/05/1998 11:50	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	06/01/1998 14:22	S	0.3	R	STORET DATA CONVERSION	19.6	
8-NAR005.42	07/06/1998 12:15	S	0.3	R	STORET DATA CONVERSION	13.8	
8-NAR005.42	08/19/1998 11:45	S	0.3	R	STORET DATA CONVERSION	13.7	
8-NAR005.42	09/15/1998 09:30	S	0.3	R	STORET DATA CONVERSION	11.8	
8-NAR005.42	10/06/1998 10:22	S	0.3	R	STORET DATA CONVERSION	10.7	
8-NAR005.42	11/03/1998 11:44	S	0.3	R	STORET DATA CONVERSION	14	
8-NAR005.42	12/14/1998 10:33	S	0.3	R	STORET DATA CONVERSION	19	
8-NAR005.42	01/12/1999 10:33	S	0.3	R		44	
8-NAR005.42	02/09/1999 11:11	S	0.3	R		26	
8-NAR005.42	03/16/1999 12:15	S	0.3	R		36	
8-NAR005.42	04/19/1999 10:55	S	0.3	R		18	
8-NAR005.42	05/19/1999 13:35	S	0.3	R		20	
8-NAR005.42	06/22/1999 14:00	S	0.3	R		13.3	
8-NAR005.42	07/01/1999 11:44	S	0.3	R		12.5	
8-NAR005.42	08/03/1999 10:31	S	0.3	R		14.3	
8-NAR005.42	09/01/1999 12:00	S	0.3	R		9.8	
8-NAR005.42	11/02/1999 12:30	S	0.3	R		18.3	

00900

HARDNESS, TOTAL  
(MG/L AS CaCO3)

Sta Id	Collection Date Time	Depth		Container	Comment	HARDNESS, TOTAL (MG/L AS CaCO3)	
		Desc	Depth			Value	Com Code
8-NAR005.42	12/28/1999 14:40	S	0.3	R		18.9	
8-NAR005.42	01/05/2000 15:20	S	0.3	R		25.5	
8-NAR005.42	02/03/2000 12:00	S	0.3	R		18.2	
8-NAR005.42	03/01/2000 13:00	S	0.3	R		13	
8-NAR005.42	04/12/2000 11:45	S	0.3	R		13	
8-NAR005.42	05/03/2000 12:30	S	0.3	R		15	
8-NAR005.42	06/07/2000 10:45	S	0.3	R		16	
8-NAR005.42	07/06/2000 10:40	S	0.3	R		16.3	
8-NAR005.42	08/08/2000 10:20	S	0.3	R	NORMAL FLOW	16.6	
8-NAR005.42	09/12/2000 10:30	S	0.3	R		17.5	
8-NAR005.42	10/16/2000 10:30	S	0.3	R	NORMAL FLOW	17.7	
8-NAR005.42	11/13/2000 10:30	S	0.3	R		16	
8-NAR005.42	01/16/2001 12:00	S	0.3	R		14.6	
8-NAR005.42	01/31/2001 13:00	S	0.3	R		17.2	
8-NAR005.42	03/12/2001 12:10	S	0.3	R		14.5	
8-NAR005.42	04/25/2001 12:05	S	0.3	R		5.7	
8-NAR005.42	06/11/2001 12:45	S	0.3	R		7.1	
8-NAR005.42	08/08/2001 16:00	S	0.3	R	LOW FLOW	16.3	
8-NAR005.42	10/04/2001 14:30	S	0.3	R	LOW FLOW	17.5	
8-NAR005.42	12/27/2001 11:00	S	0.3	R	BELOW NORMAL FLOW	7.2	
8-NAR005.42	02/05/2002 13:20	S	0.3	R	LOW FLOW	12.9	
8-NAR005.42	04/03/2002 13:00	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	06/26/2002 14:15	S	0.3	R	LOW FLOW	15	
8-NAR005.42	07/24/2002 11:40	S	0.3	R		44.5	
8-NAR005.42	11/13/2002 14:10	S	0.3	R		22.8	
8-NAR005.42	01/02/2003 14:10	S	0.3	R	ABOVE NORMAL FLOW	15.5	
8-NAR005.42	03/11/2003 10:45	S	0.3	R	NORMAL FLOW	20.3	
8-NAR005.42	07/10/2003 13:00	S	0.3	R	NORMAL FLOW	21.4	
8-NAR005.42	09/16/2003 13:20	S	0.3	R	NORMAL FLOW	17.7	
8-NAR005.42	11/13/2003 15:25	S	0.3	R	NORMAL FLOW.	16	
8-NAR005.42	01/21/2004 13:10	S	0.3	R	NORMAL FLOW; COMPLETELY FRI	19	
8-NAR005.42	04/19/2004 13:30	S	0.3	R		19.1	
8-NAR005.42	05/13/2004 12:15	S	0.3	R		16	
8-NAR005.42	07/13/2004 10:40	S	0.3	R	NORMAL FLOW.	18.5	
8-NAR005.42	08/12/2004 14:00	S	0.3	R	NORMAL FLOW; PH POST CALIBR/	17.5	
8-NAR005.42	09/16/2004 14:00	S	0.3	R	NORMAL FLOW.	14.7	
8-NAR005.42	10/05/2004 12:50	S	0.3	R		18.2	
8-NAR005.42	12/01/2004 10:40	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	12/21/2004 13:40	S	0.3	R		16	
8-NAR005.42	01/19/2005 10:40	S	0.3	R	ABOVE NORMAL FLOW.	15	
8-NAR005.42	02/08/2005 12:55	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	03/17/2005 11:00	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	04/21/2005 12:45	S	0.3	R		20.8	
8-NAR005.42	05/31/2005 11:20	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	06/06/2005 12:15	S	0.3	R	NORMAL FLOW	20	
8-NAR005.42	08/03/2005 11:10	S	0.3	R	LOW FLOW	20	
8-NAR005.42	08/17/2005 10:30	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	09/26/2005 12:20	S	0.3	R	LOW FLOW	18	
8-NAR005.42	10/13/2005 11:40	S	0.3	R	NORMAL FLOW	16	
8-NAR005.42	11/07/2005 11:05	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	12/08/2005 12:33	S	0.3	R	NORMAL FLOW	20	
8-NAR005.42	01/30/2006 11:00	S	0.3	R	NORMAL FLOW.	15	
8-NAR005.42	02/28/2006 12:54	S	0.3	R	BELOW NORMAL FLOW	15	
8-NAR005.42	03/23/2006 12:03	S	0.3	R	LOW FLOW	18	
8-NAR005.42	04/25/2006 12:10	S	0.3	R	NORMAL FLOW	15	
8-NAR005.42	06/28/2006 10:25	S	0.3	R	FLOOD STAGE	20	
8-NAR005.42	08/16/2006 12:30	S	0.3	R	VERY LOW FLOW	16	
8-NAR005.42	10/16/2006 14:00	S	0.3	R	NORMAL FLOW	18	
8-NAR005.42	12/05/2006 12:10	S	0.3	R	NORMAL FLOW	17	
8-NAR005.42	01/04/2007 14:30	S	0.3	R	ABOVE NORMAL FLOW.	15	
Mean						19.4	

#### **Attachment 4**

## MEMORANDUM

DEPARTMENT OF ENVIRONMENTAL QUALITY  
Piedmont Regional Office  
4949-A Cox Road Glen Allen, Virginia 23060

**SUBJECT:** Flow Frequency Determination / 303(d) Status  
Doswell WWTF - VA0029521

**TO:** Ray Jenkins

**FROM:** Jennifer V. Palmore, P.G. *JVP*

**DATE:** April 7, 2008

**COPIES:** File

The Hanover County Doswell Wastewater Treatment Facility discharges to the North Anna River at the confluence of the Little River downstream of Hart Corner, VA. The river mile for the discharge is 8-NAR003.55. Flow frequencies have been requested at this site for use in developing effluent limitations for the VPDES permit.

Previous flow frequencies were derived by using the flow frequencies for the gauge at the North Anna River at Hart Corner near Doswell, VA (#01671020), which is located at the Route 30 bridge approximately 2 miles upstream of the discharge, and then subtracting out the flow removed by several water withdrawals located between the gauge and the discharge. At the request of Hanover County, the USGS has installed a gauge on the North Anna directly upstream of the discharge (North Anna River at Little River, VA #01671025); the gauge has been in operation since July 2004. The flow measurements for the two gauges were correlated and were plotted on a logarithmic graph and a best fit power trend line was plotted through the data points.

Due to influence from the Lake Anna dam, only the period of record after 1979 was used to calculate the flow frequencies at the Route 30 gauge. The flow frequencies from the reference gage were plugged into the equation for the regression line to calculate the associated flow frequencies at the discharge point. The flow frequencies for the gauges are presented below. The regression analysis is attached.

**North Anna River at Hart Corner near Doswell, VA (#01671020):**

Drainage Area = 463 mi<sup>2</sup>  
Statistical period = 1979-2003  
High Flow Months = Jan - May

1Q30 = 35 cfs	High Flow 1Q10 = 49 cfs
1Q10 = 36 cfs	High Flow 7Q10 = 52 cfs
7Q10 = 39 cfs	High Flow 30Q10 = 75 cfs
30Q10 = 42 cfs	HM = 111 cfs
30Q5 = 44 cfs	

**North Anna River at Little River (#01671025):**


Drainage area = 467 mi<sup>2</sup>

1Q30 = 41 cfs (26 MGD)	High Flow 1Q10 = 56 cfs (36 MGD)
1Q10 = 42 cfs (27 MGD)	High Flow 7Q10 = 60 cfs (39 MGD)
7Q10 = 45 cfs (29 MGD)	High Flow 30Q10 = 86 cfs (56 MGD)
30Q10 = 49 cfs (32 MGD)	HM = 126 cfs (81 MGD)
30Q5 = 51 cfs (33 MGD)	

The North Anna River at the discharge point was assessed as a Category 1 water during the 2006 305(b)/303(d) cycle. The river was considered fully supporting of all of its designated uses – Aquatic Life Use, Recreation, Fish Consumption, and Wildlife Use.

If you have any questions concerning this analysis, please let me know.

North Anna at Little River #01671025  
vs North Anna River at Hart Corner near Doswell, VA #01671020



SUMMARY OUTPUT

Regression Statistics	
Multiple R	0.975703111
R Square	0.951996561
Adjusted R Square	0.951961213
Standard Error	92.6009299
Observations	1360

Flow Frequencies (cfs)	
@ Hart Corner	@ Little River
35	1Q30
36	1Q10
39	7Q10
42	30Q10
44	30Q5
49	HF 1Q10
52	HF 7Q10
75	HF 30Q10
111	HM
463	DA ( mi <sup>2</sup> )
HF Months: Jan-May	
Period: 1979-2003	

## **Attachment 5**



**VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY**

**Wastewater Facility Inspection Report**

Revised 08/2001

<b>Facility Name:</b>	<u>Doswell WWTP</u>	<b>Facility No.:</b>	<u>VA0029521</u>
<b>City/County:</b>	<u>Hanover</u>	<b>Inspection Agency:</b>	<u>DEQ - PRO</u>
<b>Inspection Date:</b>	<u>September 20, 2007</u>	<b>Date Form Completed:</b>	<u>September 21, 2007</u>
<b>Inspector:</b>	<u>Mike Dare</u> <i>9.21.07</i>	<b>Time Spent:</b>	<u>8 hrs. w/ travel &amp; report</u>
<b>Reviewed By:</b>	<i>[Signature]</i>	<b>Unannounced Insp.?</b>	<u>No</u>
		<b>FY-Scheduled Insp.?</b>	<u>Yes</u>
<b>Present at Inspection:</b> <u>Barbara Mitchell, Gary Proffit</u>			

**TYPE OF FACILITY:**

<u>Domestic</u>	<u>Industrial</u>
<input type="checkbox"/> Federal	<input checked="" type="checkbox"/> Major
<input checked="" type="checkbox"/> Non-Federal	<input type="checkbox"/> Minor
	<input type="checkbox"/> Primary
	<input type="checkbox"/> Secondary
Population Served: <u>approx.: Varies seasonally with the operation of Kings Dominion</u>	
Number of Connections: <u>approx.: 8 – the amusement park, Bear Island Paper Co. sanitary sewer &amp; local businesses</u>	

**TYPE OF INSPECTION:**

<input checked="" type="checkbox"/> Routine	Date of last inspection: <u>January 27 &amp; 31, 2005</u>
<input type="checkbox"/> Compliance	Agency: <u>DEQ/PRO</u>
<input type="checkbox"/> Reinspection	

**INFLUENT and EFFLUENT MONITORING:**

**Please refer to the DMR file for Data**

Last month average:	BOD: ____ mg/L	TSS: ____ mg/L	Flow: ____ MGD
<b>(Influent) Date:</b>			
Other: _____	mg/L		

Last month:	CBOD: ____ mg/L	TSS: ____ mg/L	Flow: ____ MGD
<b>(Effluent) Date:</b>			
Other:			

Quarter average:	CBOD: ____ mg/L	TSS: ____ mg/L	Flow: ____ MGD
<b>(Effluent) Date:</b>			
Other:			

**CHANGES AND/OR CONSTRUCTION**

DATA VERIFIED IN PREFACE	<input type="checkbox"/> Updated	<input checked="" type="checkbox"/> No changes
Has there been any new construction?	<input type="checkbox"/> Yes*	<input checked="" type="checkbox"/> No
If yes, were plans and specifications approved?	<input type="checkbox"/> Yes	<input type="checkbox"/> No* <input checked="" type="checkbox"/> N/A
DEQ approval date:	<u>N/A</u>	

**(A) PLANT OPERATION AND MAINTENANCE**

1. Class and number of licensed operators: Class I – 4; Class II – 1
2. Hours per day plant is staffed: 13.5 hours/day, 7 days/week
3. Describe adequacy of staffing: ☐ Good ☐ Average ☒ Poor\*
4. Does the plant have an established program for training personnel? ☒ Yes ☐ No
5. Describe the adequacy of the training program: ☒ Good ☐ Average ☐ Poor\*
6. Are preventive maintenance tasks scheduled? ☒ Yes ☐ No\*
7. Describe the adequacy of maintenance: ☐ Good ☒ Average ☐ Poor\*
8. Does the plant experience any organic/hydraulic overloading? ☐ Yes\* ☒ No

If yes, identify cause and impact on plant: Two 0.5 MG Equalization Basins limit impact of surges.

9. Any bypassing since last inspection? ☐ Yes\* ☒ No
10. Is the on-site electric generator operational? ☒ Yes ☐ No\* ☐ N/A
11. Is the STP alarm system operational? ☒ Yes ☐ No\* ☐ N/A
12. How often is the standby generator exercised? ☒ Weekly ☐ Monthly ☐ Other:
- Power Transfer Switch? ☒ Weekly ☐ Monthly ☐ Other:
- Alarm System? ☒ Weekly ☐ Monthly ☐ Other:
13. When were the cross connection control devices last tested on the potable water service? All four tested 10/3/06
14. Is sludge disposed in accordance with the approved sludge disposal plan? ☒ Yes ☐ No\* ☐ N/A
15. Is septage received by the facility? ☐ Yes ☒ No
- Is septage loading controlled? ☐ Yes ☐ No\* ☒ N/A
- Are records maintained? ☐ Yes ☐ No\* ☒ N/A
16. Overall appearance of facility: ☐ Good ☒ Average ☐ Poor\*

**Comments: #1, 2 & 3) In 2000 the plant hours of operation were reduced from 24 hrs/day to 13.5 hrs/day, and the staffing was reduced, however the workload and tasks required to operate the plant did not change. The County Maintenance crew is now being called in to perform routine maintenance tasks. #4 The training program includes unit by unit OJT with the "Doswell WWTP Training Guide", VA Rural Water Assoc. training, Licensing Prep classes at John Tyler and DEQ Lab Workshops. #14 The approved plan calls for landfill disposal.**

**(B) PLANT RECORDS**

1. Which of the following records does the plant maintain?
 

Operational Logs for each unit process	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Instrument maintenance and calibration	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Mechanical equipment maintenance	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Industrial waste contribution ( <b>Municipal Facilities</b> )	<input type="checkbox"/> Yes	<input type="checkbox"/> No*	<input checked="" type="checkbox"/> N/A
  
2. What does the operational log contain?
 

Visual Observations	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Flow Measurement	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Laboratory Results	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Process Adjustments	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Control Calculations	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Other:			
  
3. What do the mechanical equipment records contain:
 

As built plans and specs?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Spare parts inventory?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Manufacturers instructions?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Equipment/parts suppliers?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Lubrication schedules?	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Other:			
Comments:	<u>None</u>		
  
4. What do the industrial waste contribution records contain:
 

Waste characteristics?	<input type="checkbox"/> Yes	<input type="checkbox"/> No*	<input checked="" type="checkbox"/> N/A
Locations and discharge types?	<input type="checkbox"/> Yes	<input type="checkbox"/> No*	<input checked="" type="checkbox"/> N/A
Impact on plant?	<input type="checkbox"/> Yes	<input type="checkbox"/> No*	<input checked="" type="checkbox"/> N/A
Other:	<u>N/A</u>		
Comments:	<u>None</u>		

**(Applicable to municipal facilities only)**
  
5. Are the following records maintained at the plant:
 

Equipment maintenance records	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Operational Log	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Industrial contributor records	<input type="checkbox"/> Yes	<input type="checkbox"/> No*	<input checked="" type="checkbox"/> N/A
Instrumentation records	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Sampling and testing records	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
  
6. Are records maintained at a different location?
 

Where are the records maintained?	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No
-----------------------------------	------------------------------	--

**All are available on site, except some original P&S that are kept at the Courthouse**
  
7. Were the records reviewed during the inspection?
 

	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No
--	---	-----------------------------
  
8. Are the records adequate and the O & M Manual current?
 

O&M Manual date written: <u>February 1999, upgrade Submitted August 2003</u>	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*	<input type="checkbox"/> N/A
Date DEQ approved O&M <u>VDH approval 8/18/99;</u>			
  
9. Are the records maintained for required 3-year period?
 

	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No*
--	---	------------------------------

**Comments: #1. - A single operational log is kept for the entire plant. Log includes notes for various treatment units, observations, equipment adjustments and control tests. #2. - Lab records are separate from operational log.**

**(C) SAMPLING**

- |  |   |                              |                              |
|--|---|------------------------------|------------------------------|
| 1. Are sampling locations capable of providing representative samples? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 2. Do sample types correspond to those required by the permit?         | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 3. Do sampling frequencies correspond to those required by the permit? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 4. Are composite samples collected in proportion to flow?              | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 5. Are composite samples refrigerated during collection?               | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 6. Does plant maintain required records of sampling?                   | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 7. Does plant run operational control tests?                           | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |

**Comments:** Please see attached operational control data.

**(D) TESTING**

1. Who performs the testing? ☒ Plant/ Lab: BOD, TSS, pH, D.O.  
☐ Central Lab  
☒ Commercial Lab - Name: EnviroCompliance – Nutrients, Microbac – Fecals, Totopotomy WWTP Lab – Ortho/Total P

*If plant performs any testing, complete 2-4.*

2. What method is used for chlorine analysis? N/A – UV disinfection
- |   |   |                              |                              |
|---|---|------------------------------|------------------------------|
| 3. Is sufficient equipment available to perform required tests? | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |
| 4. Does testing equipment appear to be clean and/or operable?   | <input checked="" type="checkbox"/> Yes | <input type="checkbox"/> No* | <input type="checkbox"/> N/A |

**Comments:** Please see enclosed DEQ Laboratory Inspection Report.

**(E) FOR INDUSTRIAL FACILITIES W/ TECHNOLOGY BASED LIMITS N/A**

1. Is the production process as described in the permit application? (If no, describe changes in comments)  
☐ Yes ☐ No\* ☒ N/A
2. Do products and production rates correspond to the permit application? (If no, list differences in comments section)  
☐ Yes ☐ No\* ☒ N/A
3. Has the State been notified of the changes and their impact on plant effluent?  
☐ Yes ☐ No\* ☒ N/A

**Comments:** None

**FOLLOW UP TO COMPLIANCE RECOMMENDATIONS FROM THE January 27 & 31, 2005 DEQ INSPECTION:**

1. There were no Compliance Recommendations.

**FOLLOW UP TO GENERAL RECOMMENDATIONS FROM THE January 27 & 31, 2005 DEQ INSPECTION:**

1. The intensity sensor on the UV light system is malfunctioning; always indicating low intensity, even with new bulbs. The manufacturer has not been able to resolve the problem. Currently bulb cleaning is scheduled for every other week. Based on fecal coliform monitoring, this frequency of cleaning is adequate to maintain sufficient intensity for disinfection. Discussing this matter with your DEQ Permit Writer, Ray Jenkins, is recommended. **One bank of bulbs is cleaned each week, or sooner if fecal results spike. This procedure reportedly approved by Mr. Jenkins.**
2. Repair the aerator from the East EQ basin as soon as practical. The East basin was offline and currently not needed; generally only one of the 0.5 MG basins is required. **Aerator has been repaired.**
3. Pump station debris is being applied to drying beds. In addition to raw sewage, which carries pathogens and attracts rodents, the solids removed from the pumping stations often contain a lot of grease which may clog the drainage system. The County staff should look at other options for providing a suitable receiving station for the vac-trucks. **Most pump station debris now going to Totopotomoy WWTP for dewatering and disposal.**

**INSPECTION REPORT SUMMARY****Compliance Recommendations/Request for Corrective Action:**

1. There are no compliance recommendations.

**General Recommendations and Observations:**

There are no General Recommendations.

Items evaluated during this inspection include (check all that apply):

<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	Operational Units
<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	O & M Manual
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	Maintenance Records
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A Pathogen Reduction & Vector Attraction Reduction
<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A Sludge Disposal Plan
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A Groundwater Monitoring Plan
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A Storm Water Pollution Prevention Plan
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A Permit Special Conditions
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A Permit Water Quality Chemical Monitoring
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A Laboratory Records (see Lab Report)

## 10/01

1

**LABORATORY RECORDS SECTION**

LABORATORY RECORDS INCLUDE THE FOLLOWING:

<input checked="" type="checkbox"/>	SAMPLING DATE	<input checked="" type="checkbox"/>	ANALYSIS DATE	<input checked="" type="checkbox"/>	CONT MONITORING CHART
<input checked="" type="checkbox"/>	SAMPLING TIME	<input checked="" type="checkbox"/>	ANALYSIS TIME	<input checked="" type="checkbox"/>	INSTRUMENT CALIBRATION
<input checked="" type="checkbox"/>	SAMPLE LOCATION	<input checked="" type="checkbox"/>	TEST METHOD	<input checked="" type="checkbox"/>	INSTRUMENT MAINTENANCE
				<input checked="" type="checkbox"/>	CERTIFICATE OF ANALYSIS

WRITTEN INSTRUCTIONS INCLUDE THE FOLLOWING:

<input checked="" type="checkbox"/>	SAMPLING SCHEDULES	<input checked="" type="checkbox"/>	CALCULATIONS	<input checked="" type="checkbox"/>	ANALYSIS PROCEDURES
-------------------------------------	--------------------	-------------------------------------	--------------	-------------------------------------	---------------------

	YES	NO	N/A
DO ALL ANALYSTS INITIAL THEIR WORK?	X		
DO BENCH SHEETS INCLUDE ALL INFORMATION NECESSARY TO DETERMINE RESULTS?	X		
IS THE DMR COMPLETE AND CORRECT? MONTH(S) REVIEWED: <b>August 2007</b>	X		
ARE ALL MONITORING VALUES REQUIRED BY THE PERMIT REPORTED?	X		

**GENERAL SAMPLING AND ANALYSIS SECTION**

	YES	NO	N/A
ARE SAMPLE LOCATION(S) ACCORDING TO PERMIT REQUIREMENTS?	X		
ARE SAMPLE COLLECTION PROCEDURES APPROPRIATE?	X		
IS SAMPLE EQUIPMENT CONDITION ADEQUATE?	X		
IS FLOW MEASUREMENT ACCORDING TO PERMIT REQUIREMENTS?	X		
ARE COMPOSITE SAMPLES REPRESENTATIVE OF FLOW?	X		
ARE SAMPLE HOLDING TIMES AND PRESERVATION ADEQUATE?	X		
IF ANALYSIS IS PERFORMED AT ANOTHER LOCATION, ARE SHIPPING PROCEDURES ADEQUATE? LIST PARAMETERS AND NAME & ADDRESS OF LAB: <b>Ammonia, TKN, Nitrate, Nitrite - EnviroCompliance Laboratories, Inc, Glen Allen, VA; Fecals - Microbac, Richmond, VA; Ortho/Total P - Totopotomy WWTP Lab.</b>	X		

**LABORATORY EQUIPMENT SECTION**

	YES	NO	N/A
IS LABORATORY EQUIPMENT IN PROPER OPERATING RANGE?	X		
ARE ANNUAL THERMOMETER CALIBRATION(S) ADEQUATE?	X		
IS THE LABORATORY GRADE WATER SUPPLY ADEQUATE?			X
ARE ANALYTICAL BALANCE(S) ADEQUATE?	X		

# LABORATORY INSPECTION REPORT SUMMARY

<b>FACILITY NAME:</b> Doswell WWTP	<b>FACILITY NO:</b> VA0029521	<b>INSPECTION DATE:</b> September 20, 2007
<b>LABORATORY EVALUATION:</b>	(X) Deficiencies ( ) No Deficiencies	
<b>LABORATORY RECORDS</b>		
No Deficiencies – As allowed by the permit, Ms. Mitchell will begin including DMR data for any incomplete calendar week at months end in the following monthly reporting period.		
<b>GENERAL SAMPLING AND ANALYSIS</b>		
No Deficiencies		
<b>LABORATORY EQUIPMENT</b>		
No Deficiencies		
<b>INDIVIDUAL PARAMETERS</b>		
pH, Dissolved Oxygen, and Total Suspended Solids Analysis Procedures: No deficiencies <u>Biochemical Oxygen Demand Analysis Procedures:</u> 1. Two of five seed corrections for period 7/29/07 to 8/2/07 are >1.0 mg/L. Data not flagged. Flag on bench sheet and DMR.		



## **Attachment 6**

Subsections this Attachment are identified as 6A, 6B, and 6C

**Attachment 6A** presents the results of water quality criteria monitoring on Outfall 001

**Attachment 6B** presents Discharge Monitoring Report (DMR) data for Outfall 001

**Attachment 6C** presents DMR data for Outfalls 101 and 102

## **Attachment 6A**

Results of water quality criteria monitoring on Outfall 001

## Attachment 6A

Items in bold face are considered to be present in the discharge and require evaluation. See Attachment 7 of this fact sheet. Dioxin was not tested at the required QL and is also addressed in Attachment 7.

Parameter	Required QL (µg/L)	February 28, 2007	May 23, 2007	July 25, 2007
<b>METALS (µg/L)</b>				
Antimony, dissolved	18000	<100	<100	<100
Arsenic, dissolved	210	<60	<60	<60
Cadmium, dissolved	3.1	<0.50	<0.50	<0.50
Chromium, dissolved	---	<10	<10	<10
Chromium III, dissolved	570			<10
Chromium VI, dissolved	9.2			<5.0
<b>Copper, dissolved</b>	30	<b>6</b>	<b>&lt;5</b>	<b>&lt;5</b>
<b>Lead, dissolved <sup>(A)</sup></b>	44	<b>&lt;20</b>	<b>&lt;20</b>	<b>30</b>
Mercury, dissolved	1.0	<0.1	<0.1	<0.1
Nickel, dissolved	57	<10	<10	<10
Selenium, dissolved	10.0	<2	<2	<2
Silver, dissolved	11.0	<5	<5	<5
Thalium, dissolved	(B)	<40	<40	<40
<b>Zinc, dissolved <sup>(A)</sup></b>	180	<b>108</b>	<b>101</b>	<b>134</b>
<b>PESTICIDES / PCBs (µg/L)</b>				
Aldrin	0.05			<0.05
Chlordane	0.2			<0.20
Chlorpyrifos	(B)			<0.10
DDD	0.1			<0.05
DDE	0.1			<0.05
DDT	0.1			<0.05
Demeton	(B)			<0.10
Dieldrin	0.1			<0.05
Alpha-Endosulfan	0.1			<0.05
Beta-Endosulfan	0.1			<0.05
Endosulfan sulfate	0.1			<0.05
Endrin	0.1			<0.05
Endrin Aldehyde	(B)			<0.05
Guthion	(B)			<0.10
Heptachlor	0.05			<0.05
Heptachlor Epoxide	(B)			<0.05
Alpha-BHC	(B)			<0.05
Beta-BHC	(B)			<0.05
Gamma-BHC or Lindane	0.05			<0.05
Kepone	(B)			<0.40
Malathion	(B)			<0.10
Methoxychlor	(B)			<0.05
Mirex	(B)			<0.05
Parathion	(B)			<0.10
PCB 1260	1.0			<1
PCB 1254	1.0			<1
PBC 1248	1.0			<1
PCB 1242	1.0			<1
PCB 1232	1.0			<1
PCB 1221	1.0			<1
PCB 1016	1.0			<1
PCB Total	7.0			<7
Toxaphene	5.0			<5.0
<b>BASE NEUTRALS (µg/L)</b>				
Acenaphthene	10.0	<10.0	<10.0	<10.0
Anthracene	10.0	<10.0	<10.0	<10.0
Benzidine	(B)	<10.0	<10.0	<10.0
Benzo (a) anthracene	10.0	<10.0	<10.0	<10.0
Benzo (b) fluoranthene	10.0	<10.0	<10.0	<10.0
Benzo (k) fluoranthene	10.0	<10.0	<10.0	<10.0
Benzo (a) pyrene	10.0	<10.0	<10.0	<10.0
Bis 2-Chloroethyl Ether	(B)	<10.0	<10.0	<10.0
Bis 2-Chloroisopropyl Ether	(B)	<10.0	<10.0	<10.0
Butyl benzyl phthalate	10.0	<10.0	<10.0	<10.0
2-Chloronaphthalene	(B)	<10.0	<10.0	<10.0
Chrysene	10.0	<10.0	<10.0	<10.0

	Required QL (µg/L)	February 28, 2007	May 23, 2007	July 25, 2007
Parameter				
Dibenz(a,h)anthracene	20.0	<10.0	<10.0	<10.0
Dibutyl phthalate	10.0	<10.0	<10.0	<10.0
1,2- Dichlorobenzene	10.0	<10.0		
1,3- Dichlorobenzene	10.0	<10.0		
1,4- Dichlorobenzene	10.0	<10.0		
3,3-Dichlorobenzidine	(B)	<10.0	<10.0	<10.0
Diethyl phthalate	10.0	<10.0	<10.0	<10.0
Di-2-Ethylhexyl Phthalate	10.0	<10.0	<10.0	<10.0
Dimethyl phthalate	(B)	<10.0	<10.0	<10.0
2,4-Dinitrotoluene	10.0	<10.0	<10.0	<10.0
1,2-Diphenylhydrazine	(B)	<10.0	<10.0	<10.0
Fluoranthene	10.0	<10.0	<10.0	<10.0
Fluorene	10.0	<10.0	<10.0	<10.0
Hexachlorobenzene	(B)	<10.0	<10.0	<10.0
Hexachlorobutadiene	(B)	<10.0	<10.0	<10.0
Hexachlorocyclopentadiene	(B)	<10.0	<10.0	<10.0
Hexachloroethane	(B)	<10.0	<10.0	<10.0
Indeno (1,2,3-cd) pyrene	20.0	<10.0	<10.0	<10.0
Isophorone	10.0	<10.0	<10.0	<10.0
Nitrobenzene	10.0	<10.0	<10.0	<10.0
N-Nitrosodimethylamine	(B)	<10.0	<10.0	<10.0
N-Nitrosodi-n-propylamine	(B)	<10.0	<10.0	<10.0
N-Nitrosodiphenylamine	(B)	<10.0	<10.0	<10.0
Pyrene	10.0	<10.0	<10.0	<10.0
1,2,4-Trichlorobenzene	10.0	<10.0	<10.0	<10.0
VOLATILES (µg/L)				
Acrolein	(B)	<10.0	<10.0	<10.0
Acrylonitrile	(B)	<10.0	<10.0	<10.0
Benzene	10.0	<10.0	<10.0	<10.0
Bromoform	10.0	<10.0	<10.0	<10.0
Carbon Tetrachloride	10.0	<10.0	<10.0	<10.0
Chlorobenzene	(B)	<10.0	<10.0	<10.0
Chlorodibromomethane	10.0	<10.0	<10.0	<10.0
Chloroform	10.0	<10.0	<10.0	<10.0
Dichloromethane	20.0	<10.0	<10.0	<10.0
Dichlorobromomethane	20.0	<10.0	<10.0	<10.0
1,2-Dichloroethane	10.0	<10.0	<10.0	<10.0
1,1-Dichloroethylene	10.0	<10.0	<10.0	<10.0
1,2-trans-dichloroethylene	(B)	<10.0	<10.0	<10.0
1,2-Dichloropropane	(B)	<10.0	<10.0	<10.0
1,3-Dichloropropene	(B)	<20.0	<20.0	<20.0
Ethylbenzene	10.0	<10.0	<10.0	<10.0
Methyl bromide	(B)	<10.0	<10.0	<10.0
1,1,2,2-Tetrachloroethane	(B)	<10.0	<10.0	<10.0
Tetrachloroethylene	10.0	<10.0	<10.0	<10.0
Toluene	10.0	<10.0	<10.0	<10.0
1,1,2-Trichloroethane	(B)	<10.0	<10.0	<10.0
Trichloroethylene	10.0	<10.0	<10.0	<10.0
Vinyl chloride	10.0	<10.0	<10.0	<10.0
RADIONUCLIDES				
Strontium 90 (pCi/L)	(B)	Sampling for radionuclides will be required by special condition in the permit to be reissued.		
Tritium (pCi/L)	(B)			
Beta Particle & Photon Activity (mrem/yr)	(B)			
Gross Alpha Particle Activity (pCi/L)	(B)			
ACIDS (µg/L)				
2-Chlorophenol	10.0	<10.0	<10.0	<10.0
2,4 Dichlorophenol	10.0	<10.0	<10.0	<10.0
2,4- Dimethylphenol	10.0	<10.0	<10.0	<10.0
2,4-Dinitrophenol	(B)	<20.0	<20.0	<10.0
2-Methyl-4,6-Dinitrophenol	(B)	<10.0	<20.0	<10.0
Pentachlorophenol	50.0	<10.0	<20.0	<10.0
Phenol	10.0	<10.0	<10.0	<10.0
2,4,6-Trichlorophenol	10.0	<10.0	<10.0	<10.0
MISCELLANEOUS (µg/L unless otherwise noted)				
Chlorides, mg/L	(B)			29

	Required QL (µg/L)	February 28, 2007	May 23, 2007	July 25, 2007
Parameter				
Total Residual Chlorine	100	See footnote (C) below		
Cyanide, Total <sup>(D)</sup>	10.0	11	10	<10
Dioxin	0.00001			<0.0000101
Hardness, mg/L	(B)	586	581	521
Hydrogen sulfide	(B)			<300 sulfide
Tributyltin	(B)			<0.030
Xylenes total	6.0			<6.00

(A) Additional Data:	Dissolved Lead	Dissolved Zinc
October 11, 2007	<20	218
October 12, 2007	<20	173
October 17, 2007	<20	98
October 18, 2007	<20	113
October 24, 2007	<20	110
October 25, 2007	<20	104
October 31, 2007	<20	109
December 19, 2007	---	204

(B) Any approved method in 40 CFR Part 136 if the parameter is addressed in 40 CFR Part 136.

(C) In March 2007, TRC concentrations of 0.19 mg/L, 0.41 mg/L, and 0.48 mg/L were determined in conjunction with WET testing on Outfall 001. These data are not considered representative of Outfall 001 as neither the Doswell treatment plant nor Bear Island use chlorine compounds. These results are thought to be due to test interferences.

(D) Additional Data from cyanide study. These data were used to modify the permit in October 2006 to remove cyanide limitations that were added to the permit at reissuance in May 2003.

March 1, 2004	7.64
March 8, 2004	10.1
March 15, 2004	10.1
March 22, 2004	15.3
March 31, 2004	9.52
April 5, 2004	13.2
April 12, 2004	14.8
April 19, 2004	8.20
April 26, 2004	8.20
May 3, 2004	11.1
May 10, 2004	10.4
May 17, 2004	8.2
May 24, 2004	16.9
January 3, 2005	<6
April 4, 2005	18.8
July 11, 2005	9.77
October 10, 2005	11.2

**Attachment 6B**

Discharge Monitoring Report (DMR) data for Outfall 001

Attachment 6B														
Outfall 001 Effluent Data														
Outfall 001 Effluent Data from Discharge Monitoring Reports														
Sample frequency is once per day unless otherwise noted.														
Date	BOD <sub>5</sub> , mg/L		TSS, mg/L (3W)		D.O., mg/L		TKN, mg/L (3W)		Temperature, °F		pH, Standard Units		Ammonia, mg/L (1/M)	
	Reported	Limitation	Reported	Limitation	Minimum		Weekly Average	Minimum	Average	Maximum	Minimum	Maximum	Monthly Average	
Monthly Averages														
2005														
July	8.3	40.9	17.6	47.0	6.7		7.50	80.6	86.3	93.2	7.3	7.8	3.30	
August	15.8	43.7	23.3	46.5	6.5		10.48	82.4	87.3	91.4	7.4	7.8	0.40	
September	6.7	43.5	17.0	47.8	6.6		4.92	73.4	84.6	89.6	7.5	7.9	0.60	
October	5.0	48.2	14.5	48.2	7.4		4.24	68.0	77.9	87.8	7.3	7.7	0.30	
November	6.0	49.2	16.8	49.2	7.8		4.79	64.4	72.0	80.6	7.2	7.8	0.60	
December	10.5	49.5	19.1	49.4	8.1		2.74	60.8	66.8	78.8	7.1	7.6	<0.20	
2006														
January	5.5	49.1	15.0	49.1	7.7		3.62	59.0	67.6	80.6	7.0	7.7	1.36	
February	9.2	49.2	15.1	49.2	8.2		2.98	60.8	70.2	77.0	7.1	7.6	<0.20	
March	7.0	49.3	15.4	49.4	7.4		5.72	66.2	71.6	80.6	7.2	7.9	<0.20	
April	7.9	48.9	15.6	48.9	6.8		7.90	60.8	75.0	84.2	7.1	7.8	1.10	
May	4.2	48.9	6.2	48.9	6.9		3.14	64.4	80.7	87.8	7.2	7.8	0.29	
June	10.1	48.6	15.4	48.6	6.5		4.53	78.8	87.1	95.0	7.1	7.8	<0.20	
July	11.8	47.7	13.4	47.8	6.5		4.05	84.6	89.8	93.2	7.1	7.7	0.20	
August	12.4	47.8	16.8	47.8	6.5		4.34	84.2	91.9	96.8	7.3	7.6	0.50	
September	10.6	48.5	16.9	48.6	6.6		3.74	75.2	84.8	95.0	7.0	7.9	<0.20	
October	7.2	48.9	13.4	49.0	6.5		4.52	68.0	77.3	84.2	7.3	7.9	2.00	
November	8.9	48.9	20.9	48.9	6.5		4.42	60.8	70.9	80.6	7.1	7.9	1.50	
December	8.7	49.5	17.3	49.5	6.6		3.14	66.2	74.5	82.4	7.2	7.8	0.40	
2007														
January	3.8	49.3	12.1	49.4	6.5		2.39	55.4	68.8	80.6	7.0	7.7	0.30	
February	10.5	49.5	26.0	49.5	7.9		2.29	53.6	69.0	75.2	7.3	7.8	<0.20	
March	7.1	49.2	18.2	49.3	7.7		3.76	57.2	70.3	82.4	7.3	7.9	<0.20	
April	2.2	49.0	8.7	49.0	7.0		3.30	60.8	76.2	84.2	7.2	7.9	<0.20	
May	5.9	49.0	8.0	49.1	6.9		2.59	78.8	83.8	91.4	7.4	7.8	0.40	
June	12.4	48.3	15.5	48.5	6.9		3.55	80.6	86.2	91.4	7.1	7.8	0.20	
July	4.4	47.7	15.3	47.7	7.1		2.56	78.8	85.7	89.6	7.3	7.8	0.40	
August	3.8	47.8	12.9	47.9	6.7		4.21	80.6	86.9	89.6	7.6	7.9	<0.20	
September	9.3	48.8	13.6	48.8	6.9		3.61	80.6	85.6	89.6	7.4	7.7	<0.20	
October	3.3	48.5	10.3	48.6	6.8		5.37	71.6	78.2	84.2	7.4	7.8	1.40	

Date	Reported	BOD <sub>5</sub> , mg/L	TSS, mg/L (3W)	D.O., mg/L	TKN, mg/L (3W)	Temperature, °F		pH, Standard Units		Ammonia, mg/L (1/M)
	Limitation	Limitation	Reported	Limitation	Weekly Average	Minimum	Average	Maximum	Minimum	Monthly Average
Monthly Averages										
November	3.9	49.4	11.3	49.3	2.88	64.4	74.5	82.4	7.2	<0.20
December	10.2	49.5	26.1	49.5	5.09	68.0	72.4	78.8	7.5	0.70
2008										
January	12.9	49.4	23.2	49.4	6.33	60.8	70.5	80.6	7.1	0.50
February	9.7	49.4	24.8	49.5	4.36	66.2	71.9	78.8	7.2	<0.20
March	8.6	49.3	19.5	49.3	4.12	68.0	74.1	82.4	7.2	<0.20
April	8.1	49.1	23.3	49.1	3.63	69.8	77.4	84.2	7.3	<0.20
May	7.7	48.9	28.5	48.9	7.42	68.0	78.4	87.8	7.2	1.50
June	6.8	48.2	12.6	48.2	3.35	80.6	86.5	91.4	6.9	0.50
Average	8.0	48.4	16.7	48.7	4.38	69.5	78.1	85.7	7.2	0.84
Maximum	15.8	49.5	28.5	49.5	10.48	84.6	91.9	96.8	7.6	3.30
Minimum	2.2	40.9	6.2	46.5	2.29	53.6	66.8	75.2	6.9	0.20
					90th percentile	80.6	87.0	93.2	7.4	7.9
					10th percentile	59.9	69.6	78.8	7.1	7.7
(See below for temperatures in °C)										
Effluent Limitation:	48.4		48.7	6.5	13.0		NL	NL	6.00	9.00
Ratio (in %) of actual value to limitation (using average values above):										
	16.5		34.3	100	33.7				N/A	N/A
Baseline	1 / Day	1 / Day	1 / Day	1 / Day	1 / Day				1 / Day	1 / Day
Allowable reduction in monitoring frequency:										
	1 / Week		3 / Week	No reduction	3 / Week				Not applicable	
Temperature, °C										
						Minimum	Average	Maximum		
					Average	20.8	25.6	29.8		
					Maximum	29.2	33.3	36		
					Minimum	12	19.3	24		
					90th percentile	27	30.6	34		
					10th percentile	15.5	20.9	26		



**Attachment 6C**

DMR data for Outfalls 101 and 102

Attachment 6C				
Date	Outfall 101		Outfall 201	
	BOD <sub>5</sub> , mg/L (5/W)	TSS, mg/L (3/W)	BOD <sub>5</sub> , mg/L (5/W)	TSS, mg/L (3/W)
Monthly Averages				
2005				
July	4.5	9.2	8.6	18.2
August	3.6	10.3	11.1	22.4
September	2.8	14.0	7.7	16.2
October	0.5	8.2	5.6	15.6
November	2.3	6.5	7.0	19.0
December	2.3	17.1	9.1	23.0
2006				
January	1.5	17.8	6.1	15.9
February	0.8	14.3	9.6	14.1
March	4.3	13.1	5.3	14.1
April	7.4	11.6	7.5	15.4
May	6.0	9.9	3.3	6.6
June	4.4	11.3	8.7	16.2
July	5.1	12.6	11.5	14.4
August	6.4	17.7	12.4	15.6
September	2.6	12.4	10.6	16.6
October	1.6	10.4	6.9	15.1
November	4.3	12.3	9.4	21.3
December	1.0	13.9	8.7	18.5
2007				
January	1.1	16.8	3.5	12.1
February	1.9	12.2	9.2	21.1
March	0.2	10.1	7.2	16.5
April	6.4	10.0	1.7	8.1
May	4.4	8.1	4.8	7.1
June	4.3	13.0	12.7	17.9
July	7.5	16.8	3.5	11.5
August	0.6	6.6	4.3	15.6
September	3.0	11.4	9.8	15.2
October	1.1	9.1	2.9	10.5
November	5.2	23.1	2.6	9.5
December	4.7	22.3	8.2	27.7
2008				
January	4.8	20.5	7.5	20.5
February	1.9	12.0	9.6	25.8
March	3.8	12.6	9.1	20.5
April	3.5	12.4	8.5	19.9
May	3.7	9.8	8.0	25.4
June	4.6	10.1	7.1	14.2
Average	3.4	12.8	7.5	16.6
Maximum	7.5	23.1	12.7	27.7
Minimum	0.2	6.5	1.7	6.6
Limitation	30	30	50	50
% of actual average versus limitation	11.3	42.7	15.0	33.2

Baseline monitoring	1 / Day	1 / Day	1 / Day	1 / Day
Allowable reduction in monitoring frequency:				
	1 / Week	3 / Week	1 / Week	3 / Week

## **Attachment 7**

Effluent Limitation Development

## Attachment 7

The data summarized in the following table were provided in the permit renewal application. The data are summarized in Attachment 6A.

If data were reported at less than a quantification level (QL) equal to or less than the required QL, the parameter was considered absent for the purpose of this evaluation. All uncensored values (that is, not a “less than” value) were evaluated in regard to the need for a water quality based effluent limitation. The parameters requiring evaluation, which are indicated in bold type in the following table are ammonia (see Attachment 6B for effluent ammonia data), copper, lead, zinc, chloride, chlorine, and cyanide.

Included in this attachment are:

- a. “Mixing Zone Predictions...”. This analysis uses statistical flows and basic information about the receiving stream to predict mixing patterns in-stream.

These pages (and others) are identified in the first line as either “existing” or “expansion”. The “existing” condition uses an effluent flow of 5.8 MGD. The “expansion” condition uses an effluent flow of 6.34 MGD.

- b. Spreadsheets titled “Water Quality Standards and Wasteload Allocations” (also known as MSTRANTI). These spreadsheets calculate the water quality standards and wasteload allocations given inputs for effluent and stream flow, pH, temperature, and hardness, and other stream characteristics. See Attachment 3 for stream data.
- c. Calculation sheets (“STATS”) that present a reasonable potential analysis of the listed data to determine if a water quality based effluent limitation is needed. The wasteload allocations from MSTRANTI are used in these analyses.
- d. The following table shows a comparison of reported data to applicable human health wasteload allocations. No limitations are required to protect human health.

Parameter	Outfall 001	
	Expected Value*	WLA <sub>hh</sub> **
Cyanide (µg/L)	10.5	1,300,000
Dissolved Zinc (µg/L)	133.9	430,000
Dioxin*** (ppq)	10.1	49

\* See STATS printouts in this attachment.

\*\* Taken from the MSTRANTI spreadsheet for the expansion flow (see Attachment 14), which is conservative for the existing condition.

\*\*\* The required QL for the dioxin testing was 10 ppq. Dioxin was reported as < 10.1 ppq. Dioxin is associated with the production of Kraft paper using chlorine. Bear Island is not a Kraft mill and no Kraft paper is presently used at the mill (although Special Condition 12 acknowledges that up to 10% purchased Kraft could be imported). The reported result of < 10.1 ppq is therefore, a reasonable indication that dioxin can be considered absent in this effluent. As presented in the table above however, if dioxin was present at a concentration of 10.1 ppq, a limitation would not be needed. Note that the dioxin standard applies at the mean annual stream flow. The annual mean for Water Years 1980 through 2007 is 387 cfs (250 MGD). The above  $WLA_{HH}$  was obtained using the MSTRANTI spreadsheet with an effluent flow of 6.34 MGD and stream flow of 250 MGD.

## Mixing Zone Predictions for

Doswell WWTP existing

Effluent Flow = 5.8 MGD  
Stream 7Q10 = 29 MGD  
Stream 30Q10 = 32 MGD  
Stream 1Q10 = 27 MGD  
Stream slope = 0.00038 ft/ft  
Stream width = 75 ft  
Bottom scale = 2  
Channel scale = 1

---

### Mixing Zone Predictions @ 7Q10

Depth = 1.5301 ft  
Length = 5044.68 ft  
Velocity = .4694 ft/sec  
Residence Time = .1244 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 7Q10 may be used.

---

### Mixing Zone Predictions @ 30Q10

Depth = 1.6092 ft  
Length = 4830.64 ft  
Velocity = .4848 ft/sec  
Residence Time = .1153 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 30Q10 may be used.

---

### Mixing Zone Predictions @ 1Q10

Depth = 1.4758 ft  
Length = 5203.82 ft  
Velocity = .4587 ft/sec  
Residence Time = 3.1514 hours

#### Recommendation:

A complete mix assumption is appropriate for this situation providing no more than 31.73% of the 1Q10 is used.

---

# FRESHWATER WATER QUALITY CRITERIA / WASTELOAD ALLOCATION ANALYSIS

Facility Name: Doswell WWTP existing  
Receiving Stream: North Anna River

Permit No.: VA0029521

Version: OWP Guidance Memo 00-2011 (8/24/00)

Stream Information			Stream Flows			Mixing Information			Effluent Information		
Mean Hardness (as CaCO <sub>3</sub> ) =	19.4 mg/L		1Q10 (Annual) =	27 MGD		Annual - 1Q10 Mix =	31.73 %		Mean Hardness (as CaCO <sub>3</sub> ) =	562 mg/L	
90% Temperature (Annual) =	26.2 deg C		7Q10 (Annual) =	29 MGD		- 7Q10 Mix =	100 %		90% Temp (Annual) =	30.6 deg C	
90% Temperature (Wet season) =	deg C		30Q10 (Annual) =	32 MGD		- 30Q10 Mix =	100 %		90% Temp (Wet season) =	deg C	
90% Maximum pH =	7.4 SU		1Q10 (Wet season) =	0 MGD		Wet Season - 1Q10 Mix =	%		90% Maximum pH =	7.9 SU	
10% Maximum pH =	6.4 SU		30Q10 (Wet season) =	0 MGD		- 30Q10 Mix =	%		10% Maximum pH =	7.7 SU	
Tier Designation (1 or 2) =	1		30Q5 =	33 MGD					Discharge Flow =	5.8 MGD	
Public Water Supply (PWS) Y/N? =	n		Harmonic Mean =	81 MGD							
Trout Present Y/N? =	n		Annual Average =	MGD							
Early Life Stages Present Y/N? =	y										

Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Acenaphthene	0	--	--	na	2.7E+03	--	--	na	1.8E+04	--	--	--	na	--	--	1.8E+04
Acrolein	0	--	--	na	7.8E+02	--	--	na	5.2E+03	--	--	--	na	--	--	5.2E+03
Acrylonitrile <sup>c</sup>	0	--	--	na	6.6E+00	--	--	na	9.9E+01	--	--	--	na	--	--	9.9E+01
Aldrin <sup>c</sup>	0	3.0E+00	--	na	1.4E+03	7.4E+00	--	na	2.1E+02	--	--	--	na	7.4E+00	--	2.1E+02
Ammonia-N (mg/l)	0	1.87E+01	2.06E+00	na	--	4.6E+01	1.3E+01	na	--	--	--	--	na	4.6E+01	1.3E+01	--
Ammonia-N (mg/l) (High Flow)	0	1.01E+01	2.80E+00	na	--	1.0E+01	2.8E+00	na	--	--	--	--	na	1.0E+01	2.8E+00	--
Anthracene	0	--	--	na	1.1E+05	--	--	na	7.4E+05	--	--	--	na	--	--	7.4E+05
Antimony	0	--	--	na	4.3E+03	--	--	na	2.9E+04	--	--	--	na	--	--	2.9E+04
Arsenic	0	3.4E+02	1.5E+02	na	--	8.4E+02	9.0E+02	na	--	--	--	--	na	8.4E+02	9.0E+02	--
Barium	0	--	--	na	--	--	--	na	--	--	--	--	na	--	--	--
Benzene <sup>c</sup>	0	--	--	na	7.1E+02	--	--	na	1.1E+04	--	--	--	na	--	--	1.1E+04
Benzidine <sup>c</sup>	0	--	--	na	5.4E+03	--	--	na	8.1E+02	--	--	--	na	--	--	8.1E+02
Benzo (a) anthracene <sup>c</sup>	0	--	--	na	4.9E+01	--	--	na	7.3E+00	--	--	--	na	--	--	7.3E+00
Benzo (b) fluoranthene <sup>c</sup>	0	--	--	na	4.9E+01	--	--	na	7.3E+00	--	--	--	na	--	--	7.3E+00
Benzo (k) fluoranthene <sup>c</sup>	0	--	--	na	4.9E+01	--	--	na	7.3E+00	--	--	--	na	--	--	7.3E+00
Bis(2-Chloroethyl) Ether	0	--	--	na	1.4E+01	--	--	na	9.4E+01	--	--	--	na	--	--	9.4E+01
Bis(2-Chloroisopropyl) Ether	0	--	--	na	1.7E+05	--	--	na	1.1E+06	--	--	--	na	--	--	1.1E+06
Bromofom <sup>c</sup>	0	--	--	na	3.6E+03	--	--	na	5.4E+04	--	--	--	na	--	--	5.4E+04
Butylbenzylphthalate	0	--	--	na	5.2E+03	--	--	na	3.5E+04	--	--	--	na	--	--	3.5E+04
Cadmium	0	1.0E+01	1.2E+00	na	--	2.6E+01	7.3E+00	na	--	--	--	--	na	2.6E+01	7.3E+00	--
Carbon Tetrachloride <sup>c</sup>	0	--	--	na	4.4E+01	--	--	na	6.8E+02	--	--	--	na	--	--	6.8E+02
Chlordane <sup>c</sup>	0	2.4E+00	4.3E+03	na	2.2E+02	5.9E+00	2.6E+02	na	3.3E+01	--	--	--	na	5.9E+00	2.6E+02	3.3E+01
Chloride	0	8.6E+05	2.3E+05	na	--	2.1E+06	1.4E+06	na	--	--	--	--	na	2.1E+06	1.4E+06	--
TCR	0	1.9E+01	1.1E+01	na	--	4.7E+01	6.6E+01	na	--	--	--	--	na	4.7E+01	6.6E+01	--
Chlorobenzene	0	--	--	na	2.1E+04	--	--	na	1.4E+05	--	--	--	na	--	--	1.4E+05



Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Chlorobromomethane <sup>c</sup>	0	--	--	na	3.4E+02	--	--	na	5.1E+03	--	--	--	--	--	--	na
Chloroform <sup>c</sup>	0	--	--	na	2.9E+04	--	--	na	4.3E+05	--	--	--	--	--	--	na
2-Chloronaphthalene	0	--	--	na	4.3E+03	--	--	na	2.9E+04	--	--	--	--	--	--	na
2-Chlorophenol	0	--	--	na	4.9E+02	--	--	na	2.7E+03	--	--	--	--	--	--	na
Chlorpyrifos	0	8.3E-02	4.1E-02	na	--	2.1E-01	2.5E-01	na	--	--	--	--	--	2.1E-01	2.5E-01	na
Chromium III	0	1.2E+03	8.0E+01	na	--	2.9E+03	4.8E+02	na	--	--	--	--	--	2.9E+03	4.8E+02	na
Chromium VI	0	1.6E+01	1.1E+01	na	--	4.0E+01	6.6E+01	na	--	--	--	--	--	4.0E+01	6.6E+01	na
Chromium, Total	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Chrysene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	na
Copper	0	3.0E+01	9.7E+00	na	--	7.5E+01	5.8E+01	na	--	--	--	--	--	7.5E+01	5.8E+01	na
Cyanide	0	2.2E+01	5.2E+00	na	2.2E+05	5.4E+01	3.1E+01	na	1.4E+06	--	--	--	--	5.4E+01	3.1E+01	na
DOD <sup>c</sup>	0	--	--	na	8.4E-03	--	--	na	1.9E-01	--	--	--	--	--	--	na
DDE <sup>c</sup>	0	--	--	na	5.9E-03	--	--	na	8.8E-02	--	--	--	--	--	--	na
DDT <sup>c</sup>	0	1.1E+00	1.0E-03	na	5.9E-03	2.7E+00	6.0E-03	na	8.8E-02	--	--	--	--	2.7E+00	6.0E-03	na
Demeton	0	--	1.0E-01	na	--	--	6.0E-01	na	--	--	--	--	--	--	6.0E-01	na
Dibenz(a,h)anthracene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	na
Diethyl phthalate	0	--	--	na	1.2E+04	--	--	na	8.0E+04	--	--	--	--	--	--	na
Dichloromethane	0	--	--	na	1.6E+04	--	--	na	2.4E+05	--	--	--	--	--	--	na
(Methylene Chloride) <sup>c</sup>	0	--	--	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
1,2-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.7E+04	--	--	--	--	--	--	na
1,3-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.7E+04	--	--	--	--	--	--	na
1,4-Dichlorobenzene	0	--	--	na	7.7E-01	--	--	na	1.2E+01	--	--	--	--	--	--	na
3,3-Dichlorobenzidine <sup>c</sup>	0	--	--	na	4.6E+02	--	--	na	6.9E+03	--	--	--	--	--	--	na
Dichlorobromomethane <sup>c</sup>	0	--	--	na	9.9E+02	--	--	na	1.5E+04	--	--	--	--	--	--	na
1,2-Dichloroethane <sup>c</sup>	0	--	--	na	1.4E+05	--	--	na	9.4E+05	--	--	--	--	--	--	na
1,1-Dichloroethylene	0	--	--	na	7.9E+02	--	--	na	5.9E+03	--	--	--	--	--	--	na
1,2-trans-dichloroethylene	0	--	--	na	3.9E+02	--	--	na	5.8E+03	--	--	--	--	--	--	na
2,4-Dichlorophenol	0	--	--	na	1.7E+03	--	--	na	1.1E+04	--	--	--	--	--	--	na
2,4-Dichlorophenoxy acetic acid (2,4-D)	0	--	--	na	1.4E-03	5.9E-01	3.4E-01	na	2.1E-02	--	--	--	--	5.9E-01	3.4E-01	na
1,3-Dichloropropene	0	2.4E-01	5.6E-02	na	1.2E+05	--	--	na	8.0E+05	--	--	--	--	--	--	na
Dieldrin <sup>c</sup>	0	--	--	na	1.2E+05	--	--	na	8.0E+05	--	--	--	--	--	--	na
Diethyl Phthalate	0	--	--	na	5.9E+01	--	--	na	8.8E+02	--	--	--	--	--	--	na
Di-2-Ethylhexyl Phthalate <sup>c</sup>	0	--	--	na	2.3E+03	--	--	na	1.5E+04	--	--	--	--	--	--	na
2,4-Dimethylphenol	0	--	--	na	2.9E+06	--	--	na	1.9E+07	--	--	--	--	--	--	na
Dimethyl Phthalate	0	--	--	na	1.2E+04	--	--	na	8.0E+04	--	--	--	--	--	--	na
Di-n-Butyl Phthalate	0	--	--	na	1.4E+04	--	--	na	9.4E+04	--	--	--	--	--	--	na
2,4-Dinitrophenol	0	--	--	na	7.6E+02	--	--	na	5.1E+03	--	--	--	--	--	--	na
2-Methyl-4,6-Dinitrophenol	0	--	--	na	9.1E-01	--	--	na	1.4E+03	--	--	--	--	--	--	na
2,4-Dinitrotoluene <sup>c</sup>	0	--	--	na	1.2E-06	--	--	na	8.1E+01	--	--	--	--	--	--	na
Dioxin (2,3,7,8- tetrachlorodibenzo-p-dioxin) (pg/g)	0	--	--	na	5.4E+00	--	--	na	8.1E+01	--	--	--	--	--	--	na
1,2-Diphenylhydrazine <sup>c</sup>	0	2.2E-01	5.6E-02	na	2.4E+02	5.4E-01	3.4E-01	na	1.6E+03	--	--	--	--	5.4E-01	3.4E-01	na
Alpha-Endosulfan	0	2.2E-01	5.6E-02	na	2.4E+02	5.4E-01	3.4E-01	na	1.6E+03	--	--	--	--	5.4E-01	3.4E-01	na
Beta-Endosulfan	0	--	--	na	2.4E+02	--	--	na	1.6E+03	--	--	--	--	--	--	na
Endosulfan Sulfate	0	8.9E-02	3.6E-02	na	9.1E-01	2.1E-01	2.2E-01	na	5.4E+00	--	--	--	--	2.1E-01	2.2E-01	na
Endrin	0	--	--	na	8.1E+01	--	--	na	5.4E+00	--	--	--	--	--	--	na
Endrin Aldehyde	0	--	--	na	8.1E+01	--	--	na	5.4E+00	--	--	--	--	--	--	na

Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Ethylbenzene	0	--	--	na	2.9E+04	--	--	na	1.9E+05	--	--	--	--	--	--	na
Fluoranthene	0	--	--	na	3.7E+02	--	--	na	2.5E+03	--	--	--	--	--	--	na
Fluorene	0	--	--	na	1.4E+04	--	--	na	9.4E+04	--	--	--	--	--	--	na
Foaming Agents	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Guthion	0	--	1.0E-02	na	--	--	6.0E-02	na	--	--	--	--	--	--	6.0E-02	na
Heptachlor <sup>C</sup>	0	5.2E-01	3.9E-03	na	2.1E-03	1.3E+00	2.3E-02	na	3.1E-02	--	--	--	--	1.3E+00	2.3E-02	na
Heptachlor Epoxide <sup>C</sup>	0	5.2E-01	3.9E-03	na	1.1E-03	1.3E+00	2.3E-02	na	1.9E-02	--	--	--	--	1.3E+00	2.3E-02	na
Hexachlorobenzene <sup>C</sup>	0	--	--	na	7.7E-03	--	--	na	1.2E-01	--	--	--	--	--	--	na
Hexachlorobutadiene <sup>C</sup>	0	--	--	na	5.0E+02	--	--	na	7.5E+03	--	--	--	--	--	--	na
Hexachlorocyclohexane	0	--	--	na	1.3E-01	--	--	na	1.9E+00	--	--	--	--	--	--	na
Alpha-BHC <sup>C</sup>	0	--	--	na	4.6E-01	--	--	na	6.9E+00	--	--	--	--	--	--	na
Beta-BHC <sup>C</sup>	0	--	--	na	6.3E-01	2.4E+00	--	na	9.4E+00	--	--	--	--	2.4E+00	--	na
Gamma-BHC <sup>C</sup> (Lindane)	0	9.5E-01	na	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
Hexachlorocyclopentadiene	0	--	--	na	8.9E+01	--	--	na	1.3E+03	--	--	--	--	--	--	na
Hexachloroethane <sup>C</sup>	0	--	2.0E+00	na	--	--	1.2E+01	na	--	--	--	--	--	--	1.2E+01	na
Hydrogen Sulfide	0	--	--	na	4.9E-01	--	--	na	7.3E+00	--	--	--	--	--	--	na
Indeno (1,2,3-cd) pyrene <sup>C</sup>	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Iron	0	--	--	na	2.6E+04	--	--	na	3.9E+05	--	--	--	--	--	--	na
Isophorone <sup>C</sup>	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Kepona	0	3.6E+02	1.9E+01	na	--	8.9E-02	9.1E+01	na	--	--	--	--	--	8.9E-02	9.1E+01	na
Lead	0	--	1.0E-01	na	--	--	6.0E-01	na	--	--	--	--	--	--	6.0E-01	na
Malathion	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Manganese	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Mercury	0	1.4E+00	7.7E-01	na	5.1E-02	3.5E+00	4.6E+00	na	3.4E-01	--	--	--	--	3.5E+00	4.6E+00	na
Methyl Bromide	0	--	--	na	4.0E+03	--	--	na	2.7E+04	--	--	--	--	--	--	na
Methoxychlor	0	--	3.0E-02	na	--	--	1.8E-01	na	--	--	--	--	--	--	1.8E-01	na
Mirex	0	--	0.0E+00	na	--	--	0.9E+00	na	--	--	--	--	--	--	0.0E+00	na
Monochlorobenzene	0	3.8E-02	2.2E+01	na	4.6E+03	9.4E+02	1.3E+02	na	1.4E+05	--	--	--	--	9.4E+02	1.3E+02	na
Nickel	0	--	--	na	2.1E+04	--	--	na	--	--	--	--	--	--	--	na
Nitrate (as N)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Nitrobenzene	0	--	--	na	1.9E+03	--	--	na	1.3E+04	--	--	--	--	--	--	na
N-Nitrosodimethylamine <sup>C</sup>	0	--	--	na	8.1E+01	--	--	na	1.2E+03	--	--	--	--	--	--	na
N-Nitrosodiphenylamine <sup>C</sup>	0	--	--	na	1.6E+02	--	--	na	2.4E+03	--	--	--	--	--	--	na
N-Nitrosodi-n-propylamine <sup>C</sup>	0	--	--	na	1.4E+01	--	--	na	2.1E+02	--	--	--	--	--	--	na
Parathion	0	6.5E-02	1.3E-02	na	--	1.6E-01	7.9E-02	na	--	--	--	--	--	1.6E-01	7.9E-02	na
PCB-1016	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1221	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1232	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1242	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1248	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1254	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB-1260	0	--	1.4E-02	na	--	--	8.4E-02	na	--	--	--	--	--	--	8.4E-02	na
PCB Total <sup>C</sup>	0	--	--	na	1.7E-03	--	--	na	2.5E-02	--	--	--	--	--	--	na

Parameter (ug/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Pentachlorophenol <sup>c</sup>	0	5.9E+00	3.9E+00	na	8.2E+01	1.5E+01	2.4E+01	na	1.2E+03	--	--	--	--	1.5E+01	2.4E+01	na
Phenol	0	--	--	na	4.5E+06	--	--	na	3.1E+07	--	--	--	--	--	--	na
Pyrene	0	--	--	na	1.1E+04	--	--	na	7.4E+04	--	--	--	--	--	--	na
Radionuclides (pCi/l except Beta/Photon)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Gross Alpha Activity (mrem/yr)	0	--	--	na	1.5E+01	--	--	na	1.0E+02	--	--	--	--	--	--	na
Beta and Photon Activity	0	--	--	na	4.0E+00	--	--	na	2.7E+01	--	--	--	--	--	--	na
Strontium-90	0	--	--	na	8.0E+00	--	--	na	5.4E+01	--	--	--	--	--	--	na
Tridium	0	--	--	na	2.0E+04	--	--	na	1.3E+05	--	--	--	--	--	--	na
Selenium	0	2.0E+01	5.0E+00	na	1.1E+04	5.0E+01	3.0E+01	na	7.4E+04	--	--	--	--	5.0E+01	3.0E+01	na
Silver	0	1.5E+01	--	na	--	3.8E+01	--	na	--	--	--	--	--	3.8E+01	--	na
Sulfate	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
1,1,2,2-Tetrachloroethane <sup>c</sup>	0	--	--	na	1.1E+02	--	--	na	1.6E+03	--	--	--	--	--	--	na
Tetrachloroethylene <sup>c</sup>	0	--	--	na	8.9E+01	--	--	na	1.3E+03	--	--	--	--	--	--	na
Thallium	0	--	--	na	6.3E+00	--	--	na	4.2E+01	--	--	--	--	--	--	na
Toluene	0	--	--	na	2.0E+05	--	--	na	1.3E+06	--	--	--	--	--	--	na
Total dissolved solids	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Toxaphene <sup>c</sup>	0	7.3E-01	2.0E-04	na	7.5E-03	1.8E+00	1.2E-03	na	1.1E-01	--	--	--	--	1.8E+00	1.2E-03	na
Tributyltin	0	4.6E-01	6.3E-02	na	--	1.1E+00	3.8E-01	na	--	--	--	--	--	1.1E+00	3.8E-01	na
1,2,4-Trichlorobenzene	0	--	--	na	9.4E+02	--	--	na	6.3E+03	--	--	--	--	--	--	na
1,1,2-Trichloroethane <sup>c</sup>	0	--	--	na	4.2E+02	--	--	na	6.3E+03	--	--	--	--	--	--	na
Trichloroethylene <sup>c</sup>	0	--	--	na	8.1E+02	--	--	na	1.2E+04	--	--	--	--	--	--	na
2,4,6-Trichlorophenol <sup>c</sup>	0	--	--	na	6.5E+01	--	--	na	9.7E+02	--	--	--	--	--	--	na
2-(2,4,5-Trichlorophenoxy) propionic acid (Silver)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Vinyl Chloride <sup>c</sup>	0	2.4E+02	1.3E+02	na	6.1E+01	--	--	na	9.1E+02	--	--	--	--	6.1E+02	7.7E+02	na
Zinc	0	--	--	na	6.9E+04	6.1E+02	7.7E+02	na	4.6E+05	--	--	--	--	--	--	na

Notes:

- All concentrations expressed as micrograms/liter (ug/l), unless noted otherwise
- Discharge flow is highest monthly average or Form 2C maximum for Industries and design flow for Municipals
- Metals measured as Dissolved, unless specified otherwise
- "C" indicates a carcinogenic parameter
- Regular WLAs are mass balances (minus background concentration) using the % of stream flow entered above under Mixing Information. Antidegradation WLAs are based upon a complete mix.
- Antideg. Baseline = (0.25(WQC - background conc.) + background conc.) for acute and chronic  
= (0.1(WQC - background conc.) + background conc.) for human health
- WLAs established at the following stream flows: 1Q10 for Acute, 30Q10 for Chronic Ammonia, 7Q10 for Other Chronic, 30Q5 for Non-carcinogens, Harmonic Mean for Carcinogens, and Annual Average for Dioxin. Mixing ratios may be substituted for stream flows where appropriate.

Metal	Target Value (SSTV)
Antimony	2.9E+04
Arsenic	3.4E+02
Barium	na
Cadmium	4.4E+00
Chromium III	2.9E+02
Chromium VI	1.6E+01
Copper	3.0E+01
Iron	na
Lead	5.5E+01
Manganese	na
Mercury	3.4E-01
Nickel	7.9E+01
Selenium	1.8E+01
Silver	1.5E+01
Zinc	2.4E+02

Note: do not use QL's lower than the minimum QL's provided in agency guidance

Facility = Doswell WWTP existing  
Chemical = Ammonia  
Chronic averaging period = 30  
WLAa = 46  
WLAc = 13  
Q.L. = .2  
# samples/mo. = 12  
# samples/wk. = 3

Summary of Statistics:

# observations = 1  
Expected Value = 7.8  
Variance = 21.9024  
C.V. = 0.6  
97th percentile daily values = 18.9806  
97th percentile 4 day average = 12.9775  
97th percentile 30 day average = 9.40721  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

7.8

Guidance Memorandum No. 00-2011 directs that an ammonia effluent concentration of 9 mg/L be used to evaluate the need for an ammonia limitation for a municipal discharge. Although this discharge consists predominantly of industrial wastewater, it is reasonable to check to see if the cited guidance would result in a limitation. In this case, the permit already limits TKN to 13 mg/L. Ammonia typically makes up 40% to 60% of the TKN in a municipal effluent. Ammonia makes up 46% of the TKN in the Bear Island wastewater (see "Outfall 001 – Supplement to Table I"). Using 60% as a worse case scenario, the ammonia concentration could be as high 7.8 mg/L, which is the concentration used in the above analysis ( $13 \times 0.6 = 7.8$ ). The above result that "no limit is required" establishes that the TKN limitation is also protective of the ammonia water quality standard. (See Attachment 6B for ammonia data on Outfall 001.)

Facility = Doswell WWTP existing  
Chemical = Chloride  
Chronic averaging period = 4  
WLAa = 2100000  
WLAc = 1400000  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 29000  
Variance = 3027600  
C.V. = 0.6  
97th percentile daily values = 70569.1  
97th percentile 4 day average = 48249.9  
97th percentile 30 day average = 34975.5  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

29000

Facility = Doswell WWTP existing  
Chemical = Total Residual Chlorine  
Chronic averaging period = 4  
WLAa = 47  
WLAc = 66  
Q.L. = 0.1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 3  
Expected Value = 360  
Variance = 46656  
C.V. = 0.6  
97th percentile daily values = 876.030  
97th percentile 4 day average = 598.964  
97th percentile 30 day average = 434.179  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**A limit is needed based on Acute Toxicity**

Maximum Daily Limit = 47  
Average Weekly Limit = 47  
Average Monthly Limit = 47

The data are:

190  
410  
480

Chlorine is not used for disinfection at the Doswell treatment plant and chlorine is not used in the Bear Island process. The above concentrations were determined in conjunction with the failed *Ceriodaphnia dubia* chronic bioassay test in March 2007 (see Attachment 8). These TRC concentrations are believed to be false positives due to possible interference by manganese or alkalinity. Because chlorine is not used at either site, limitations are not included in the draft permit. (It is not appropriate to "force" chlorine limitations with an input of value of 20,000 µg/L per Guidance Memorandum No. 00-2011 because chlorine is not added to the system at any point.)

Facility = Doswell WWTP existing  
Chemical = Dissolved Copper  
Chronic averaging period = 4  
WLAa = 75  
WLAc = 58  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 6  
Variance = 12.96  
C.V. = 0.6  
97th percentile daily values = 14.6005  
97th percentile 4 day average = 9.98274  
97th percentile 30 day average = 7.23631  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

6

The dissolved copper data reported with the permit renewal application were 6 µg/L, <5 µg/L, and <5 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the copper data.

Facility = Doswell WWTP  
Chemical = Cyanide  
Chronic averaging period = 4  
WLAa = 54  
WLAc = 31  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 2  
Expected Value = 10.5  
Variance = 39.69  
C.V. = 0.6  
97th percentile daily values = 25.5508  
97th percentile 4 day average = 17.4697  
97th percentile 30 day average = 12.6635  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

11  
10

The cyanide data reported with the permit renewal application were 11 µg/L, 10 µg/L, and <10 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the cyanide data. Note in Attachment 6A that a cyanide study was conducted starting in March 2004 and ending in October 2005. The above data are consistent with the data collected during that study period. Although the data from the cyanide study are more than three years old, they are still representative and could have been included in the above analysis. The above analysis using only two data points is a more extreme analysis however, which indicates that limitations are not needed.



Facility = Doswell WWTP existing  
Chemical = Dissolved Lead  
Chronic averaging period = 4  
WLAa = 890  
WLAc = 91  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 30  
Variance = 324  
C.V. = 0.6  
97th percentile daily values = 73.0025  
97th percentile 4 day average = 49.9137  
97th percentile 30 day average = 36.1815  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

30

The dissolved lead data reported with the permit renewal application were (all in µg/L): <20, <20, 30, <20, <20, <20, <20, <20, <20, and <20 (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the lead data.

Facility = Doswell WWTP existing  
Chemical = Dissolved Zinc  
Chronic averaging period = 4  
WLAa = 610  
WLAc = 770  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 11  
Expected Value = 133.937  
Variance = 1605.77  
C.V. = 0.299185  
97th percentile daily values = 222.573  
97th percentile 4 day average = 175.236  
97th percentile 30 day average = 147.698  
# < Q.L. = 0  
Model used = lognormal

**No Limit is required for this material**

The data are:

108  
101  
134  
218  
173  
98  
113  
110  
104  
109  
204

**Attachment 8**

WET Evaluation

## Attachment 8

VPDES Permit VA00029521 – Doswell Wastewater Treatment Plant

Results of acute toxicity tests during term of current permit:

Permit endpoints:  $LC_{50} \geq 100\%$   
 $NOEC \geq 21\%$  at 5.8 MGD

TEST DATE	<i>Ceriodaphnia dubia</i>		<i>Pimephales promelas</i>		Laboratory
	LC <sub>50</sub>	PERCENT SURVIVAL IN 100% EFFLUENT	LC <sub>50</sub>	PERCENT SURVIVAL IN 100% EFFLUENT	
February 2004	>100	100	>100	95	Coastal Bioanalysts
April 2005	>100	100	>100	100	J. R. Reed
April 2006	>100	100	>100	100	J. R. Reed
March 2007	>100	100	>100	100	J. R. Reed
February 2008	>100	100	>100	100	J. R. Reed

Results of chronic toxicity tests during term of current permit:

TEST DATE**	<i>Ceriodaphnia dubia</i>		<i>Pimephales promelas</i>		Laboratory
	Survival	Reproduction	Survival	Reproduction	
February 2004	100	61	100	100	Coastal Bioanalysts
April 2005	100	50	100	100	J. R. Reed
April 2006	invalid		100	100	J. R. Reed
May 2006 <sup>(1)</sup>	100	50			J. R. Reed
March 2007	100	<6.25 <sup>(2)</sup>			J. R. Reed
April 2007 <sup>(1)</sup>	100	100			J. R. Reed
April 2007 <sup>(1)</sup>	100	100			Coastal Bioanalysts
February 2008	100	<4 <sup>(3)</sup>	100	100	J. R. Reed
April 2008 <sup>(1)</sup>	100	100 <sup>(4)</sup>			J. R. Reed
April 2008 <sup>(1)</sup>	100	100			Coastal Bioanalysts

- (1) Retest
- (2) Total residual chlorine concentrations were detected in the samples received at the laboratory. Those concentrations were determined to be false positives; chlorine is not used for disinfection of final effluent. Also, subsequent screening tests at Bear Island did not indicate toxicity.
- (3) Laboratory noted presence of large brown cotton shaped solids that surrounded the *C. dubia* during the test period.
- (4) Laboratory noted presence of brown cotton shaped solids in one of the three samples collected for the test. Also, total residual chlorine concentrations were detected in the samples received at the laboratory. Those concentrations are considered to be false positives.

Discussion

Acute toxicity is not indicated.

Chronic toxicity (reproduction effect) may be indicated. The retests however, did not confirm the toxic effects.

The proposed permit requires the continuation of annual acute and chronic WET testing with *Ceriodaphnia dubia* and *Pimephales promelas*. The results of those tests will be evaluated for reasonable potential at the conclusion of the permit term, or sooner if toxicity is noted, and appropriate effluent limitations established.

# Spreadsheet for determination of WET test endpoints or WET limits

Excel 97  
Revision Date: 01/10/05  
File: WETLIM10.xls  
(MIX.EXE required also)

Acute Endpoint/Permit Limit

Use as LC<sub>50</sub> in Special Condition, as TUa on DMR

ACUTE 100% = NOAEC LC<sub>50</sub> = NA % Use as NA TUa

ACUTE WLAa 9.743125862 Note: Inform the permittee that if the mean of the data exceeds this TUa, a limit may result using WLA EXE

Chronic Endpoint/Permit Limit

Use as NOEC in Special Condition, as TUc on DMR

CHRONIC 7.431258803 TUc NOEC = 14 % Use as 7.14 TUc

BOTH\* 7.431258803 TUc NOEC = 14 % Use as 7.14 TUc

AML 7.431258803 TUc NOEC = 14 % Use as 7.14 TUc

ACUTE WLAa,c 7.43125882 Note: Inform the permittee that if the mean of the data exceeds this TUc, a limit may result using WLA EXE

CHRONIC WLAa,c 6

% Flow to be used from MIX EXE

Diffuser modeling study?

Enter Y/N

Acute 1:1

Chronic 1:1

Go to Page 2

Go to Page 3

NOTE: If the IWCA is >33%, specify the

NOAEC = 100% test/endpoint for use

Minimum of 10 data points, same species, needed)

(NOEC-LC50, do not use greater/less than data)

Plant flow/plant flow + 1Q10

Plant flow/plant flow + 7Q10

100/WCA

100/WCC

Instream criterion (0.3 TUa) X's Dilution, acute

Instream criterion (1.0 TUc) X's Dilution, chronic

ACR X's WLAa - converts acute WLA to chronic units

LC50/NOEC (Default is 10 - if data are available, use tables Page 3)

Default of 0.6 - if data are available, use tables Page 2)

Default = 0.41

Default = 0.60

Default = 2.43

Default = 2.43 (1 samp)

No. of sample

\*\*The Maximum Daily Limit is calculated from the lowest LTA, X's eC. The LTAa,c and MDL using it are driven by the ACR.

WLAa,c X's eA

WLAa,c X's eB

NOEC = 13.456670

NOEC = 11.395429

NOEC = 13.456670

Lowest LTA X's eD

Convert MDL from TUa to TUc

LC50 = 134.566704 %

LC50 = 113.954295 %

Use NOAEC=100%

Use NOAEC=100%

Use NOAEC=100%

Use NOAEC=100%

Use NOAEC=100%

Use NOAEC=100%

Use NOAEC=100%

Use NOAEC=100%

Use NOAEC=100%

Page 2 - Follow the directions to develop a site specific CV (coefficient of variation)									
IF YOU HAVE AT LEAST 10 DATA POINTS THAT ARE QUANTIFIABLE (NOT "<" OR ">") FOR A SPECIES, ENTER THE DATA IN EITHER COLUMN "G" (VERTEBRATE) OR COLUMN "J" (INVERTEBRATE). THE "CV" WILL BE PICKED UP FOR THE CALCULATIONS BELOW. THE DEFAULT VALUES FOR eA, eB, AND eC WILL CHANGE IF THE "CV" IS ANYTHING OTHER THAN 0.6.									
<div> <div> <div>Vertebrate</div> <div>IC<sub>50</sub> Data</div> <div>or</div> <div>LC<sub>50</sub> Data</div> <div>*****</div> </div> <div> <div>LN of data</div> <div>1</div> <div>2</div> <div>3</div> <div>4</div> <div>5</div> <div>6</div> <div>7</div> <div>8</div> <div>9</div> <div>10</div> <div>11</div> <div>12</div> <div>13</div> <div>14</div> <div>15</div> <div>16</div> <div>17</div> <div>18</div> <div>19</div> <div>20</div> </div> </div>									
<div> <div> <div>Vertebrate</div> <div>IC<sub>50</sub> Data</div> <div>or</div> <div>LC<sub>50</sub> Data</div> <div>*****</div> </div> <div> <div>LN of data</div> <div>1</div> <div>2</div> <div>3</div> <div>4</div> <div>5</div> <div>6</div> <div>7</div> <div>8</div> <div>9</div> <div>10</div> <div>11</div> <div>12</div> <div>13</div> <div>14</div> <div>15</div> <div>16</div> <div>17</div> <div>18</div> <div>19</div> <div>20</div> </div> </div>									
Coefficient of Variation for effluent tests									
CV = 0.6 (Default 0.6)									
$\sigma^2 = 0.3074847$ $\sigma = 0.554513029$									
Using the log variance to develop eA (P. 100, step 2a of TSD)									
Z = 1.881 (97% probability stat from table)									
A = -0.88929666									
eA = 0.410644686									
Using the log variance to develop eB (P. 100, step 2b of TSD)									
$\sigma_r^2 = 0.088177696$ $\sigma_r = 0.293560379$ $B = -0.50909823$ $eB = 0.601037335$									
Using the log variance to develop eC (P. 100, step 4a of TSD)									
$\sigma^2 = 0.3074847$ $\sigma = 0.554513029$ $C = 0.889296658$ $eC = 2.433411525$									
Using the log variance to develop eD (P. 100, step 4b of TSD)									
$\sigma = 1$ $\sigma_r^2 = 0.3074847$ $\sigma_r = 0.554513029$ $D = 0.889296658$ $eD = 2.433411525$									
This number will most likely stay as "1" for 1 sample/month.									

**Page 3 - Follow directions to develop a site specific ACR (Acute to Chronic Ratio)**

To determine Acute/Chronic Ratio (ACR), insert usable data below. Usable data is defined as valid paired test results, acute and chronic, tested at the same temperature, same species. The chronic NOEC must be less than the acute LC<sub>50</sub>, since the ACR divides the LC<sub>50</sub> by the NOEC. LC<sub>50</sub>'s > 100% should not be used.

**Table 1. ACR using Vertebrate data**

Set #	LC <sub>50</sub>	NOEC	Test ACR	Logarithm	Geomean	Antilog	ACR to Use
1	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
2	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
3	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
4	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
5	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
6	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
7	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
8	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
9	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
10	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
ACR for vertebrate data							
0							

**Table 1. Result**

**Table 2. Result**

**Table 2. ACR using Invertebrate data**

Set #	LC <sub>50</sub>	NOEC	Test ACR	Logarithm	Geomean	Antilog	ACR to Use
1	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
2	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
3	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
4	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
5	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
6	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
7	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
8	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
9	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
10	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
ACR for invertebrate data							
0							

**Table 4.**

**DILUTION SERIES TO RECOMMEND**

Dilution series based on data mean	Monitoring % Effluent	TUC	Limit	TUC
Dilution series to use for limit	32.7	3.0538362	14	7.1428571
Dilution factor to recommend:	0.5722386		0.3741657	
Dilution series to recommend:	100.0	1.00	100.0	1.00
	57.2	1.75	37.4	2.67
	32.7	3.05	14.0	7.14
	18.7	5.34	5.2	19.09
	10.72	9.33	2.0	51.02
Extra dilutions if needed	6.14	16.30	0.7	136.36
	3.51	28.48	0.3	364.43

**Table 3. Convert LC<sub>50</sub>'s and NOEC's to Chronic TU's for use in WLA EXE**

Table 3.	Enter LC <sub>50</sub>	Enter NOEC	TUC
1	NO DATA	NO DATA	NO DATA
2	NO DATA	NO DATA	NO DATA
3	NO DATA	NO DATA	NO DATA
4	NO DATA	NO DATA	NO DATA
5	NO DATA	NO DATA	NO DATA
6	NO DATA	NO DATA	NO DATA
7	NO DATA	NO DATA	NO DATA
8	NO DATA	NO DATA	NO DATA
9	NO DATA	NO DATA	NO DATA
10	NO DATA	NO DATA	NO DATA
11	NO DATA	NO DATA	NO DATA
12	NO DATA	NO DATA	NO DATA
13	NO DATA	NO DATA	NO DATA
14	NO DATA	NO DATA	NO DATA
15	NO DATA	NO DATA	NO DATA
16	NO DATA	NO DATA	NO DATA
17	NO DATA	NO DATA	NO DATA
18	NO DATA	NO DATA	NO DATA
19	NO DATA	NO DATA	NO DATA
20	NO DATA	NO DATA	NO DATA

If WLA EXE determines that an acute limit is needed, you need to convert the TUC answer you get to TUA and then an LC50, enter it here.

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA



Cell: I9

Comment:

This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: K18

Comment: This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: J22

Comment: Remember to change the "N" to "Y" if you have ratios entered, otherwise, they won't be used in the calculations.

Cell: C40

Comment:

If you have entered data to calculate an ACR on page 3, and this is still defaulted to "10", make sure you have selected "Y" in cell E21

Cell: C41

Comment: If you have entered data to calculate an effluent specific CV on page 2, and this is still defaulted to "0.6", make sure you have selected "Y" in cell E20

Cell: L48

Comment:

See Row 151 for the appropriate dilution series to use for these NOEC's

Cell: G62

Comment:

Vertebrates are:  
Pimephales promelas  
Oncorhynchus mykiss  
Cyprinodon variegatus

Cell: J62

Comment:

Invertebrates are:  
Ceriodaphnia dubia  
Mysidopsis bahia

Cell: C117

Comment:

Vertebrates are:  
Pimephales promelas  
Cyprinodon variegatus

Cell: M119

Comment: The ACR has been picked up from cell C34 on Page 1. If you have paired data to calculate an ACR, enter it in the tables to the left, and make sure you have a "Y" in cell E21 on Page 1. Otherwise, the default of 10 will be used to convert your acute data.

Cell: M121

Comment: If you are only concerned with acute data, you can enter it in the NOEC column for conversion and the number calculated will be equivalent to the T<sub>01a</sub>. The calculation is the same: 100/NOEC = T<sub>01c</sub> or 100/LC50 = T<sub>01a</sub>.

Cell: C138

Comment:

Invertebrates are:  
Ceriodaphnia dubia  
Mysidopsis bahia

# Spreadsheet for determination of WET test endpoints or WET limits

Excel 97  
Revision Date: 01/10/05  
File: WETLIM10.xls  
(MIX EXE required also)

Acute Endpoint/Permit Limit

Use as LC<sub>50</sub> in Special Condition, as TUa on DMR

ACUTE 100% =

NOAEC

LC<sub>50</sub> = NA

% Use as

NA

TUa

ACUTE WLAa 0.71151577 Note: Inform the permittee that if the mean of the data exceeds this TUa: 1.0 a limit may result using WLA EXE

Chronic Endpoint/Permit Limit

Use as NOEC in Special Condition, as TUc on DMR

CHRONIC 7.115157903 TUc

NOEC =

15 % Use as

6.66 TUc

6.66 TUc

6.66 TUc

Enter data in the cells with blue type:

Entry Date: 08/13/08

Facility Name: Dorwell WWTP

VPOES Number: VA0029521

Outfall Number: 1

Plant Flow: 6.34 MGD

Acute 1Q10: 27 MGD

Chronic 7Q10: 29 MGD

Are data available to calculate CV? (Y/N)

Are data available to calculate ACR? (Y/N)

IWC<sub>a</sub> 42.16350662 % Plant flowplant flow + 1Q10

IWC<sub>c</sub> 17.94001132 % Plant flowplant flow + 7Q10

Dilution, acute 2.371719243 100/WCa

Dilution, chronic 5.574132492 100/WCc

WLA<sub>a</sub> 0.711515773 Instream criterion (0.3 TUa) X's Dilution, acute

WLA<sub>c</sub> 5.574132492 Instream criterion (1.0 TUc) X's Dilution, chronic

WLA<sub>a,c</sub> 7.115157729 ACR X's WLA<sub>a</sub> - converts acute WLA to chronic units

ACR - acute/chronic ratio 10 LC50/NOEC (Default is 10 - if data are available, use tables Page 3)

CV - Coefficient of variation 0.6 Default of 0.6 - if data are available, use tables Page 2)

Constants eA 0.4109447 Default = 0.41

eB 0.6010373 Default = 0.60

eC 2.4334175 Default = 2.43

eD 2.4334175 Default = 2.43 (1 samp) No. of sample

LTA<sub>a,c</sub> 2.9239936358 WLAa c X's eA

LTA<sub>c</sub> 3.350261543 WLa c X's eB

MDL\*\* with LTA<sub>a,c</sub> 7.115157903 TUc NOEC =

MDL\*\* with LTA<sub>c</sub> 8.152585068 TUc NOEC =

AML with lowest LTA 7.115157903 TUc NOEC =

IF ONLY ACUTE ENDPOINT/LIMIT IS NEEDED, CONVERT MDL FROM TU<sub>a</sub> to TU<sub>c</sub>

MDL with LTA<sub>a,c</sub> 0.71151579 TUa LC50 =

MDL with LTA<sub>c</sub> 0.815258507 TUc LC50 =

Use NOAEC=100%

Use NOAEC=100%

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

LC50 = NA

Page 2 - Follow the directions to develop a site specific CV (coefficient of variation)									
IF YOU HAVE AT LEAST 10 DATA POINTS THAT ARE QUANTIFIABLE (NOT "<" OR ">") FOR A SPECIES, ENTER THE DATA IN EITHER COLUMN "G" (VERTEBRATE) OR COLUMN "J" (INVERTEBRATE). THE "CV" WILL BE PICKED UP FOR THE CALCULATIONS BELOW. THE DEFAULT VALUES FOR eA, eB, AND eC WILL CHANGE IF THE "CV" IS ANYTHING OTHER THAN 0.6.									
<div> <div>Vertebrate</div> <div>IC<sub>95</sub> Data</div> <div>or</div> <div>LC<sub>50</sub> Data</div> <div>LN of data</div> <div>LN of data</div> </div>									
<div> <div>1</div> <div>2</div> <div>3</div> <div>4</div> <div>5</div> <div>6</div> <div>7</div> <div>8</div> <div>9</div> <div>10</div> <div>11</div> <div>12</div> <div>13</div> <div>14</div> <div>15</div> <div>16</div> <div>17</div> <div>18</div> <div>19</div> <div>20</div> </div>									
Coefficient of Variation for effluent tests									
CV = 0.6 (Default 0.6)									
<div> <div><math>\sigma^2</math> = 0.3074847</div> <div><math>\sigma</math> = 0.554513029</div> </div>									
Using the log variance to develop eA (P. 100, step 2a of TSD)									
Z = 1.881 (97% probability stat from table)									
A = -0.89929658									
eA = 0.410944696									
Using the log variance to develop eB (P. 100, step 2b of TSD)									
<div> <div><math>\sigma^2</math> = 0.086177696</div> <div><math>\sigma</math> = 0.293560379</div> </div>									
B = -0.5909823									
eB = 0.601037335									
Using the log variance to develop eC (P. 100, step 4a of TSD)									
<div> <div><math>\sigma^2</math> = 0.3074847</div> <div><math>\sigma</math> = 0.554513029</div> </div>									
C = 0.88929658									
eC = 2.433417525									
Using the log variance to develop eD (P. 100, step 4b of TSD)									
<div> <div>n = 1</div> <div>This number will most likely stay as "1" for 1 sample/month</div> </div>									
<div> <div><math>\sigma^2</math> = 0.3074847</div> <div><math>\sigma</math> = 0.554513029</div> </div>									
D = 0.88929658									
eD = 2.433417525									

**Page 3 - Follow directions to develop a site specific ACR (Acute to Chronic Ratio)**

To determine Acute/Chronic Ratio (ACR), insert usable data below. Usable data is defined as valid paired test results, acute and chronic, tested at the same temperature, same species. The chronic NOEC must be less than the acute LC<sub>50</sub>, since the ACR divides the LC<sub>50</sub> by the NOEC. LC<sub>50</sub>'s >100% should not be used.

**Table 1. ACR using Vertebrate data**

Set #	LC <sub>50</sub>	NOEC	Test ACR	Logarithm	Geomean	Antilog	ACR to Use
1	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
2	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
3	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
4	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
5	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
6	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
7	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
8	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
9	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
10	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
ACR for vertebrate data:							
0							

**Table 1. Result**  
**Table 2. Result**

Vertebrate ACR  
Invertebrate ACR  
Lowest ACR

**Table 2. ACR using Invertebrate data**

Set #	LC <sub>50</sub>	NOEC	Test ACR	Logarithm	Geomean	Antilog	ACR to Use
1	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
2	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
3	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
4	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
5	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
6	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
7	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
8	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
9	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
10	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	#/N/A	NO DATA
ACR for invertebrate data:							
0							

**DILUTION SERIES TO RECOMMEND**

Table 4.	Dilution series based on data mean	Dilution series to use for limit	Dilution factor to recommend:	Dilution series to recommend:	Extra dilutions if needed
	34.2	2.9239362	0.5843117	100.0	6.84
				58.5	14.62
				34.2	25.00
				20.0	
				11.70	
				6.84	
				4.00	

**Table 3. Convert LC<sub>50</sub>'s and NOEC's to Chronic TU's for use in WLA EXE**

Table 3.	Enter LC <sub>50</sub>	Enter NOEC	TUc
1	NO DATA	NO DATA	NO DATA
2	NO DATA	NO DATA	NO DATA
3	NO DATA	NO DATA	NO DATA
4	NO DATA	NO DATA	NO DATA
5	NO DATA	NO DATA	NO DATA
6	NO DATA	NO DATA	NO DATA
7	NO DATA	NO DATA	NO DATA
8	NO DATA	NO DATA	NO DATA
9	NO DATA	NO DATA	NO DATA
10	NO DATA	NO DATA	NO DATA
11	NO DATA	NO DATA	NO DATA
12	NO DATA	NO DATA	NO DATA
13	NO DATA	NO DATA	NO DATA
14	NO DATA	NO DATA	NO DATA
15	NO DATA	NO DATA	NO DATA
16	NO DATA	NO DATA	NO DATA
17	NO DATA	NO DATA	NO DATA
18	NO DATA	NO DATA	NO DATA
19	NO DATA	NO DATA	NO DATA
20	NO DATA	NO DATA	NO DATA

If WLA EXE determines that an acute limit is needed, you need to convert the TUC answer you get to TUA and then an LC<sub>50</sub>.

enter it here

%LC<sub>50</sub>

TUA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

NO DATA

Cell: J9

Comment:

This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: K18

Comment:

This is assuming that the data are Type 2 data (none of the data in the data set are censored - "<" or ">").

Cell: J22

Comment:

Remember to change the "N" to "Y" if you have ratios entered, otherwise, they won't be used in the calculations.

Cell: C40

Comment:

If you have entered data to calculate an ACR on page 3, and this is still defaulted to "10", make sure you have selected "Y" in cell E21

Cell: C41

Comment:

If you have entered data to calculate an effluent specific CV on page 2, and this is still defaulted to "0.6", make sure you have selected "Y" in cell E20

Cell: L48

Comment:

See Row 151 for the appropriate dilution series to use for these NOEC's

Cell: G62

Comment:

Vertebrates are:

Pinephales promelas

Oncorhynchus mykiss

Cyprinodon variegatus

Cell: J62

Comment:

Invertebrates are:

Coriophila dubia

Mysidopsis bahia

Cell: C117

Comment:

Vertebrates are:

Pinephales promelas

Cyprinodon variegatus

Cell: M119

Comment:

The ACR has been picked up from cell C34 on Page 1. If you have paired data to calculate an ACR, enter it in the tables to the left, and make sure you have a "Y" in cell E21 on Page 1. Otherwise, the default of 10 will be used to convert your acute data.

Cell: M121

Comment:

If you are only concerned with acute data, you can enter it in the NOEC column for conversion and the number calculated will be equivalent to the T<sub>Ua</sub>. The calculation is the same. 100/NOEC = T<sub>Uc</sub> or 100/LC50 = T<sub>Ua</sub>.

Cell: C138

Comment:

Invertebrates are:

Coriophila dubia

Mysidopsis bahia

**Attachment 9**

## Revision of Control Equation

- Refer to page 2, item #3 of July 12, 1978 (copy attached).

NOD concentration for 6.0 mg/l TKN equals  $6 \times 4.5 \times 0.25 = 6.75$  (instead of 15.75).

$$\text{Therefore, } LW_u = 1.5625 LW_5 + 6.75 \quad (\text{ref. eqn (1), p2})$$

substituting and solving as before,

$$LW_5 = 3.4 \frac{Q_s}{Q_w} + 0.3 \quad (\text{ref. eqn (3), p3})$$

For simplicity, omit 0.3 which makes insignificant contribution.

Therefore, new control equation is

$$LW_5 = 3.4 \frac{Q_s}{Q_w}$$

- The control equation must now be adjusted to reflect the Doswell water treatment plant and BIPCO raw water intakes on the North Anna above the discharge point. The intake capacities are 3.0 MGD for Doswell and 4.0 MGD for BIPCO. (See attached letter dated May 6, 1985 from Mr. John Jackson, County Administrator.)

$$7 \text{ MGD} \times 1.55 = 10.85 \text{ cfs}$$

Therefore, control equation becomes

$$LW_5 = 3.4 \frac{Q_s - 10.85}{Q_w}$$

- using new control equation, the 7 day/10 year allocation is:

$Q_w = 5.0 \text{ MGD} : 1 \text{ MGD Doswell} ; 4 \text{ MGD BIPCO}$ . BIPCO is in the early stages of planning for a mill expansion to double production. Wastewater flow projected at 4 MGD.

$$LW_5 = \frac{3.4 (43.68 - 10.85)}{5 \text{ MGD}(1.55)}$$

$$= 14.4 \text{ mg/l}$$

$$14.4 \text{ mg/L} \times 5 \text{ MGD} \times 8.34 = 600 \text{ lbs/day}$$

- The current permit establishes a maximum discharge of 1500 #/d BOD<sub>5</sub> and TSS. This value is based on 1 MGD from Doswell at 30 mg/l and 3 MGD from BIPCO at 50 mg/l. (The 3 MGD represented a doubling of the facility based on the initial design flow of 1.5 MGD.) The attached graph titled "BIPCO Effluent Storage Analysis" was prepared by BIPCO's consultant Mr. John Combs for a meeting on May 2, 1985. At a BIPCO effluent flow of 4 MGD, this graph indicates that the current maximum of 1500 #/d (which corresponds to approx. 100 cfs stream flow) does not allow emptying of the storage basin in a reasonable period of time. The company has therefore, requested that a new maximum be established based on a stream flow of 300 cfs. As the control equation establishes an allowable discharge given any stream



flow, an increase in the maximum limitation is acceptable. Using the control equation, the maximum limitation based on 300 cfs is:

$$LW_5 = 3.4 \frac{(300 - 10.85)}{5(1.55)}$$

$$= 127 \text{ mg/l}$$

$$127 \text{ mg/l} \times 5140 \times 8.34 = 5296 \text{ \#/d}$$

say 5300 \#/d

RRJ  
5-21-85

# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

SUBJECT: Amendment of Doswell NPDES Permit, VA0029521. Supplement to Memorandum dated June 19, 1978

TO: File (42-0525)

FROM: Ray R. Jenkins, Jr. *Ray Jenkins*

DATE: July 12, 1978

COPIES: L. G. Lawson, J. J. Cibulka, W. D. Jones, Dale F. Jones

On June 28, 1978, Wes Jones, John Combs, and the writer traveled to Philadelphia, Pennsylvania to discuss the proposed Doswell tiered permit with personnel of the EPA's Region III Office. The attached list of people were in attendance.

All aspects of the proposed permit and some of the reasons for proposing a tiered permit were discussed. One of the most significant results of the meeting was the realization that the modeling recalculations detailed in the June 19, 1978, memorandum were not entirely appropriate. Charlie App pointed out that not only did the York River Basin 303(e) plan allocate wasteloads, but it also established a stream modeling methodology that took into account NOD (nitrogenous oxygen demand) and a 20% reserve assimilative capacity (p.53, 67-69 and Appendix F from the plan are attached). In our original work, it had been decided that we would strictly follow the methodology (no NOD or reserve) used in the 1973 Doswell modeling. (It should be noted that the 303(e) Plan indicates that NOD and a 20 % reserve were taken into account in establishing the 200 #d/ CBOD<sub>5</sub> allocation. These values however, were derived (back-calculated) from the 200 #d CBOD<sub>5</sub> allocation as this allocation was already in the Doswell NPDES permit when the Plan was prepared.) Charlie App advised that if changes in the allocation and therefore, the 303(e) Plan were to be proposed, the changes should incorporate the modeling methodology outlined in the Plan. These changes essentially involved reassigning rate coefficients to be consistent with other modeling in the Basin Plan, and incorporating the methodology of Appendix F.

The attached memorandum titled "Proposed Discharge to North Anna River, Hanover County" dated June 30, 1978 details the inputs to the modeling as described above. The UCBOD to CBOD<sub>5</sub> ratio was 1.25 (ref. Appendix F). The particular modeling effort detailed in the June 30 memorandum was intended to define the 7 day/10 year low flow allocation. It also served as a check on the accuracy of the CBOD<sub>5</sub> control equation which was generated by letting  $L_0$  (now UOD of the discharge-river mix) be the input variable to the modeling equation (refer to June 19 memorandum for methodology).

Following the procedure detailed in the June 19, 1978, memorandum, the allowable  $L_0$  using the revised rate coefficients was determined to be 7.2 mg/l. The critical dissolved oxygen deficit of 0.96 mg/l occurred just prior to the confluence of the North and South Anna Rivers. The river was observed to recover with the entry of the South Anna River.

The revised control equation was generated through the following approach, which is in accordance with the Plan methodology. The NOD was subtracted from the discharge concentration in ultimate demand terms. The resultant was converted to 5-day demand and the 20% reserve was subtracted. The resulting expression was rewritten in order that the UOD of the wastewater could be substituted into the mass balance equation of the wastewater-river mix, which was set equal to 7.2 mg/l. The wastewater TKN concentration was calculated to be 14 mg/l using 1.0 MGD of Doswell wastewater at 20 mg/l TKN and 1.5 MGD of BATO wastewater at 10 mg/l TKN. This wastewater mix can be considered to be a worst case condition in that any increase in BATO flow above 1.5 MGD would lower the TKN concentration of the combined discharge. Assuming such a "worst case" TKN concentration was considered preferable to adding another variable (TKN) to the control equation.

The following computations delineate the derivation of the revised control equation:

1. Ultimate oxygen demand (UOD) = ultimate CBOD + nitrogenous oxygen demand (NOD).
2.  $\text{UOD \#/d} = \text{LW}_u \times \text{Q}_w \times 8.34$ , where  $\text{LW}_u$  = ultimate oxygen demand of waste; and  $\text{Q}_w$  = wastewater flow rate (MGD)
3.  $\text{NOD} = 15.75 \times \text{Q}_w \times 8.34$   

$$15.75 = 0.25^* \times 4.5 \times \frac{20(1) + 10(1.5)}{1 + 1.5}$$

\* see p. 53 from York 303 (e), attached
4.  $\text{UCBOD} \times 0.8 = \text{CBOD}_5$  ( $\text{UCBOD}/\text{CBOD}_5 = 1.25$ )
5. 20% reserve =  $\text{CBOD}_5 \times 0.8$

Therefore  $\text{BOD}_5$  discharge in #/d =

$$0.8 \times 0.8 \times [(\text{LW}_u \times \text{Q}_w \times 8.34) - (15.75 \times \text{Q}_w \times 8.34)]$$

$$\text{BOD}_5 (\#/d) \div (8.34 \times \text{Q}_w) = \text{discharge CBOD}_5 \text{ concentration} = \text{LW}_5$$

Therefore,

$$\text{LW}_5 = \frac{0.8 \times 0.8 \times [(\text{LW}_u \times \text{Q}_w \times 8.34) - (15.75 \times \text{Q}_w \times 8.34)]}{8.34 \times \text{Q}_w}$$

solving for  $\text{LW}_u$ :

$$\text{LW}_u = 1.5625 \text{ LW}_5 + 15.75 \quad \text{Equation (1)}$$

Remembering now that  $\text{L}_0$  must equal 7.2 mg/l, the following mass balance equation can be written:

$$(\text{LW}_u \times \text{Q}_w) + (1.875^{**} \times \text{Q}_s) = 7.2 \quad \text{Equation (2)}$$

$$\text{Q}_w + \text{Q}_s$$

\*\* stream background UCBOD

Substituting equation (1) into (2) yields,

$$\left[ \frac{(1.5625 LW_5 + 15.75) \times Q_w}{Q_w + Q_s} \right] + (1.875 \times Q_s) = 7.2$$

Solving for  $LW_5$  and simplifying,

$$LW_5 = 3.4 Q_s - 5.5. \quad \text{Equation (3)}$$

This expression will be the permit controlling equation for allowable  $CBOD_5$  discharge based upon the water quality standards. (This expression replaces equation (1) in the June 19 memorandum.)

At a 7 day/10 year low flow of 43.68 cfs (North Anna and Little Rivers) and a wastewater flow of 2.5 MGD, the allowable  $CBOD_5$  discharge from equation (3) is 684 #/d. This compares well with the value computed from the 7 day/10 year modeling detailed in the June 30, 1978, memorandum, which is as follows:

1407 #/d	UOD
- 330 #/d	NOD ***
<u>1077 #/d</u>	UCBOD
$\div 1.25$	ratio of UCBOD to $CBOD_5$
<u>861.6</u>	
-20%	reserve
<u>690 #/d</u>	allowable $CBOD_5$ discharge

*** Doswell:	20 mg/l TKN x .25 x 4.5 x 1.0 x 8.34 = 188 #/d
BATO :	10 mg/l TKN x .25 x 4.5 x 1.5 x 8.34 = 140 #/d
	<u>328 #/d</u>

The 6 #/d difference is the result of not including  $Q_w$  in the wastewater-river mass balance when establishing the 7.2 mg/l mix concentration.

Another item discussed with the EPA personnel was the location of stream flow measurement. The State Water Control Board (previously the USGS) maintains a gaging station on the North Anna River at the Route 1 bridge (approximately 8 miles above the discharge point.) At the suggestion of EPA, it was agreed that this gage would provide the most reliable stream measurement. It should be noted that by measuring stream flow at this point, some additional conservatism is added to the control equation (i.e.; use of this measurement excludes a segment flow of 0.45 cfs between the gage and the discharge point, and the Little River at 1.77 cfs, both flows being 7 day/10 year low flows; the conservatism is a result of the fact that these flows were included in the derivation of Equation (3)).

One final item discussed with the EPA was statement number 4 on page 5 of the June 19, 1978, memorandum. There is some difference of opinion concerning the direction of change of  $K_2$  once the model enters the Pamunkey River. In any event, the present modeling used a  $K_2$  computed in accordance with Appendix F.

In accordance with the revised low flow allocation generated in accordance with the 303(e) Plan methodology as described above, it is proposed to modify the York River Basin 303(e) Plan to show a 7 day/10 year low flow allocation of 690 #/d  $BOD_5$ . This figure accounts for a 20% reserve assimilative capacity and an NOD of 330 #/d. The ultimate oxygen demand would be 1407 #/d.

ntp

Attendees - 6/28/78 Meeting on Hanover Co.

Phil Sengdorn

Charles App

My Hodgkiss

Stuart Kerzner

Michael Zickler

Paul E Ambrose

Wesley D. Jones

Ray E. Jenkins, Jr.

John L. Combs

#

Stan Siskowski

EPA III - Ent 597-8211

EPA III - Water Planning 597-8323

EPA III - Enforcement 597-2945

EPA III - Water Planning 597-3847

" ENFORCEMENT 597-2726

EPA III ENFORCEMENT 597-2459

VSNCR 804-897-0056

Dr. J. L. B. - PEO 804-257-121

Roy F. Weston 804-277-405

Recent evidence reported in the literature indicates that<sup>1</sup> nitrogenous BOD demand occurs in all parts of a river system. The ultimate nitrogenous BOD was calculated stoichiometrically, and each segment of the basin was assigned a percentage of ultimate nitrogenous BOD as follows, to reflect the detention time available for the BOD to take effect:

- Headwaters - 25%
- Tidal/Non-Tidal Interface 50%
- Tidal - 100%

Maximum daily loads for any stream segment depend on its flow and on the location and magnitude of point discharges. Lake Anna will change the low-flow conditions in the downstream portion of the North Anna River and in the Pamunkey River. Then the assimilative capacity of the rivers will be much greater because supplemental water discharged from the lake can maintain a higher level of stream flow, and, therefore, the rivers can accommodate higher maximum daily loads. The maximum daily loads for all segments are presented in Table IV-2.

#### C. Identification and Location of Water Quality Violations

##### 1. Dissolved Oxygen (DO) Problems

Water quality violations were identified by applying BPCTCA (1977) levels of treatment (obtained from EPA effluent guidelines) and the Virginia water quality standards (Appendix D) to point source discharges. The Virginia standard for DO is a minimum of 5.0 mg/L, and State policy on non-degradation limits the DO decrease to 0.2 mg/L. Water quality conditions were modeled to determine assimilative capacities of major streams in the York System. A summary of assumptions made for this modeling effort is presented in Appendix F. The results of the selected alternatives are depicted in Figures IV-3 through IV-7.

##### a. South Anna River

Figure IV-3 presents the dissolved oxygen profile for the South Anna River under 1977 loading conditions. The treatment plants in the headwaters (Gordonsville and Louisa-Mineral) are required to provide 92 and 93 percent carbonaceous BOD removal. The high degree of removal is necessitated by the relatively low stream flow and the correspondingly low assimilative capacity of the headwaters.

<sup>1</sup>"Zones of Nitrification", T. J. Tuffely, J. W. Hunter and V. A. Matulewic, AWRA, Volume 10, No. 2, June 1974

All fecal coliform contamination in the lower York River Basin cannot be attributed to traditional sources. Chesapeake Corporation may be discharging organisms that have been identified as fecal coliform. It is possible that this may be due to organism misidentification, and Chesapeake Corporation has contracted with VIMS to determine this possibility. The results of this study could have significant impact on condemned shellfish areas.

Although no loading reduction has been established for Contrary Creek, an abatement program is being implemented to reduce the Creek's acid mine drainage. This program includes the following:

- Restore and regrade surrounding areas to minimize erosion and remove tailing piles.
- Mix soil with limestone, appropriate fertilizer, and digested sludge.
- Seed the entire area to establish a vegetative cover.
- Dredge Contrary Creek.
- Develop a monitoring program, involving:
  - Continuous flow at selected locations.
  - Grab samples at selected locations (including Lake Anna) for analysis of heavy metals.

The influence of salt marsh discharges is clearly illustrated in the D0 profile for the Pamunkey River (Figure IV-6). This water quality segment was modeled under 1977 loading conditions with zero discharge from all point sources. The conclusions were that this segment is water quality limited by natural causes and that the discharges of Chesapeake Corporation and of the proposed Hanover County regional treatment plant will have little effect on water quality in this segment.

#### G. Allocation of Reduction Responsibilities

No specific loading reductions are required for any segment in the York River Basin.

#### H. Assignment of Effluent Limitations

During the course of this study, the rivers, streams, and creeks were analyzed to determine waste load assimilative capacities. Recommendations for 1977 waste loads are based on the magnitude of waste load at each significant point

source required to maintain high quality water. Twenty percent of that load has been set aside as a reserve wherever possible.

Table IV-5 shows the recommended effluent limitations in terms of BOD<sub>5</sub> and Ultimate BOD. The first column is the waste load allocation for 1977; these waste discharges were used to establish the existing water quality, which was defined as that resulting after the 1977 effluent limitations were applied.

The maximum daily load allocations were determined by calculating the magnitude of the daily load beyond the 1977 baseline load that could be added without decreasing the DO at the sag point more than 0.2 mg/L (the state policy on non-degradation). The recommended allocation is 80% of the maximum (wherever possible), which reserves 20% as a safety factor. Required removal efficiency to meet the maximum daily load by 1995 is also provided.



TABLE IV-5  
WASTE LOAD ALLOCATIONS (IN LBS PER DAY)

POINT SOURCE	1977 WASTE LOAD <sup>2</sup>		MAXIMUM DAILY LOAD		RECOMMENDED ALLOCATION			RAW WASTE LOAD AT 1995		REQUIRED % REMOVAL EFFICIENCY 1995	
	CBOD <sub>5</sub>	UBOD <sup>1</sup>	CBOD <sub>5</sub>	UBOD	CBOD <sub>5</sub>	UBOD	PERCENT RESERVE	CBOD <sub>5</sub>	UBOD	CBOD <sub>5</sub>	UBOD
Gordonsville	145	398	150	412	150	412	0	1950	2730	92	85
Louisa-Mineral	50	108	55	118	55	118	0	850	1150	93	90
Doswell	52	110	250	417	200	334	20	1080	1444	85 (4)	71
Thornburg	63	150	68	162	68	162	0	1240	1690	94	90
Bowling Green	27	64	29	68	29	68	0	680	926	96	93
Ashland	160	303	235	559	183	447	20	2250	3825	92	88
Hanover (Regional STP)	170	437	280	820	280	820	0	5730	7930	96	90
Chesapeake Corp.	6400	8000	6170 <sup>5</sup>	7710 <sup>5</sup>	6170 <sup>5</sup>	7710 <sup>5</sup>	N/A	51700	64630	90	90
West Point	105	380	281 <sup>3</sup>	1020	225	814	20	1000	1600	85 <sup>4</sup>	66
York & James City SD #1	213	641	2630 <sup>3</sup>	7843	2100	6270	20	4480	6780	85 <sup>4</sup>	72
American Oil	406	1360	73 <sup>5</sup>	245	73	245	N/A	4620	6630	96	98
York Regional STP	2280	9230	10000 <sup>3</sup>	40900	8010	32700	20	26900	44900	85 <sup>4</sup>	67

<sup>1</sup>UBOD is Ultimate Biochemical Oxygen Demand. Its concentration is derived by the following:  $800\% / 0.80 + 4.5$  (TKN) = (UBOD)  
NOTE: The amount of TKN utilized depends on the location in the basin.

<sup>2</sup>Projected for 1977 based on population projections.  
<sup>3</sup>Recommended allocation based on BPTCA effluent guidelines applied to raw waste loads at 2020.

<sup>4</sup>Minimum removal efficiency.  
<sup>5</sup>Allocation based on BATEA Guidelines at 2020.

<sup>6</sup>Based on assumed influent characteristics.

APPENDIX F: CALCULATION OF ASSIMILATIVE CAPACITY AND WASTELoad ALLOCATIONS  
FOR OXYGEN-DEMANDING MATERIALS IN NON-TIDAL AND TIDAL STREAMS

I. Non-Tidal

In the modeling of all non-tidal streams, a modified Streeter-Phelps oxygen-sag model was used for both carbonaceous and nitrogenous oxygen-demanding materials. The basic equation utilized in the simulation may be written as:

$$D = \frac{E_1 L_a}{K_2 - K_1} (e^{-K_1 t} - e^{-K_2 t}) + D_a e^{-K_2 t}$$

where D = oxygen deficit at time t (mg/l)

D<sub>a</sub> = oxygen deficit at origin, where t = 0 (mg/l)

L<sub>a</sub> = ultimate oxygen demand in stream at origin (mg/L)

K<sub>1</sub> = log base e deoxygenation coefficient

K<sub>2</sub> = log base e reaeration coefficient

t = time of travel from origin

K<sub>2</sub> values for all streams were calculated using critical low-flow stream depths and velocities, and K<sub>1</sub> was chosen to conform to a typical sanitary waste and to provide the most reasonable fit to existing stream dissolved oxygen data. It must be emphasized that, in all cases, existing stream data were minimal with respect to water quality, and the modeling parameters used must be regarded as best available estimates which may be considered adequate only for purposes of interim planning. Further explanation of the model components is presented in the following paragraphs.

a. Ultimate Biochemical (Carbonaceous) Oxygen Demand (UBCOD)

The amount of ultimate CBOD discharge is calculated by multiplying reported BOD<sub>5</sub> loadings by 1.25 or by the following equation:

$$\text{UCBOD (lbs/day)} = \frac{\text{Effluent BOD}_5 \text{ concentrations (mg/l)} \times \text{flow(mgd)} \times 8.34}{0.8}$$

b. Ultimate Nitrogenous Oxygen Demand

Ultimate nitrogenous oxygen demands (UNOD) are calculated stoichiometrically as follows:

$$\text{UNOD (lbs/day)} = \text{effluent TKN concentration (mg/l)} \\ \times \text{flow (mgd} \times 4.5 \times 8.34)$$

Wherever the effluent concentration of TKN is not available, 20 mg/L is used as the effluent concentration unless otherwise indicated.

c. Ultimate Oxygen Demand

The ultimate oxygen demand at the point of discharge is equal to the sum of ultimate carbonaceous biochemical oxygen demand and nitrogenous oxygen demand.

d. Non-Point Source Contribution

In general, non-point sources of oxygen demanding material are not adequately defined and must at present be considered as a background dissolved oxygen deficit. In the absence of actual stream water quality data, values between 1.0 and 2.0 mg/L were used.

e. Waste Load Distribution

In the process of evaluating stream assimilative capacity, it is necessary to determine the decay of waste loads from all points of discharge as materials flow downstream. For any given segment this may be expressed as follows:

$$L = L_o \exp (-K_1 t)$$

where  $L_o$  = ultimate oxygen demand at the upstream end of the segment

$K_1$  = coefficient of deoxygenation at the ambient stream temperature

$t$  = average time of travel to the point of application in the segment at the 7-day, 10-year average low-flow conditions

f. Critical Low Flow

The 7-day average low flow with a 10-year return period was used for analysis. Annual low-flow series for Virginia were obtained from USGS gaging station records. For segments lacking a gaging station, the critical flow was obtained based on known drainage basin areas and geologic considerations.

g. Velocity and Depth

Stream hydraulic characteristics were estimated from maps and field data, since stream sampling and geometry data were not available.

h. Temperature

In this study, the temperature used in modeling the non-tidal stream segments is 25°C. Statistical analysis showed 25° to be the critical temperature.

i. DO Saturation

Dissolved oxygen concentrations at saturation used in these computations are taken from the table of saturation values found in "Standard Methods for the Examination of Water and Wastewater", 13th edition.

j. Deoxygenation and Reaeration Rate

The deoxygenation rate,  $K_1$  is estimated by the discharged waste characteristics. Further refinement in  $K_1$  is not justified on the basis of existing data. The above rate is considered to be an appropriate average for both carbonaceous and nitrogenous materials within the context of this study.

The reaeration rate  $K_2$  is estimated from the O'Connor-Dobbins formula. It is based on estimated hydraulic depths and velocities. Generally,  $K_2$  values have a higher level of confidence than  $K_1$  values in this study.

Both  $K_1$  and  $K_2$  are corrected for ambient stream temperatures according to the relationships:

$$K_1 = K_{1_{20^{\circ}}} (1.047)^{T-20}$$
$$\text{and } K_2 = K_{2_{20^{\circ}}} (1.024)^{T-20}$$

where  $K_1, K_2$  = corrected rate constants ( $\text{day}^{-1}$ )

$K_{1_{20^{\circ}}}, K_{2_{20^{\circ}}}$  = estimated rate constants at  $T = 20^{\circ}\text{C}$  ( $\text{day}^{-1}$ )

$T$  = Ambient Stream Temperature ( $^{\circ}\text{C}$ )

## k. Stream Assimilative Capacity

A discussion of stream assimilative capacity is given in Chapter IV. Calculation of the assimilative capacity of each reach is based on the definition of the maximum upstream loading required to allow the stream to meet the specified dissolved oxygen criteria at each critical point (minimum points on the dissolved oxygen versus river mile curve). Since downstream conditions depend on the distribution and magnitude of all upstream discharge points, the calculated assimilative capacity (CAC) was first calculated for the upstream reaches and proceeded downstream. The magnitude and location of all point sources were accounted for in these calculations.

### 1. Waste Load Allocations

Using the calculated assimilative capacity (CAC), the recommended waste load allocation was calculated according to the expression:

$$\text{Waste load allocation (BOD)} = 0.8 (\text{CAC})$$

If the projected 1977 BOD<sub>5</sub> load to the segment is less than the target load, allocation is required. Allocations are normally made in terms of BOD<sub>5</sub>. However, an option for negotiation between the discharger and regulatory agencies for increasing BOD<sub>5</sub> discharge allocation in return for reducing ultimate biochemical oxygen demand may be considered.

### 2. Tidal Model

The dissolved oxygen in the tidal estuaries of the York River Basin was simulated with the use of a one-dimensional, non-steady state model developed by VIMS. This model is based on the finite element method of volume integration. It has been developed for the Virginia State Water Control Board for the specific purpose of serving as a planning and management tool in the analysis of river systems.

The model covers the physical area of the tidal portions of the Pamunkey and the Mattaponi, as well as the York estuary itself. The input data necessary for the tidal model is extensive. The main program requires the total drainage area, tidal cycles, time increments, weighting factor for advection of sea salt, Manning's roughness factor for each section, etc. In addition, sub-routines require extensive data. Fortunately, through cooperation with VIMS staff, the input requirements for this study were reduced to changes in the loadings typified by various alternatives.

One limitation of the VIMS model is its average DO predictions in the area below the Yorktown Bridge. In this area, the assumption of one-dimensionality is invalid. Significant density stratification, as well as vertical and horizontal variations, mandate a three-dimensional model. Such an effort is presently underway at VIMS. However, for the present study, the resulting dissolved oxygen values obtained in this area from the VIMS model were used to determine relative impacts. The absolute levels of dissolved oxygen in this area were obtained from a model recently completed as part of a 201 Facilities Plan for the Hampton Roads Sanitation Commission. Both models predicted little impact on water quality from point source discharges in the area below the Yorktown bridge.

# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

SUBJECT: Proposed Discharge to North Anna River, Hanover County

TO: W. D. Jones

FROM: K. C. Das *KC Das*

DATE: June 30, 1978

COPIES: D. F. Jones, J. J. Cibulka, D. B. Richwine, J. K. Bailey, R. R. Jenkins,  
C. T. Bathala

In accordance with your suggestion, I am summarizing here below the results of the analysis relative to the proposed discharge into North Anna River. The methodology used herein is in keeping with the procedures as outlined in the York River Basin 303(e) Plan (Appendix F).

The 7-day, 10-year low flow was computed in the manner indicated below:

The drainage area at the dam site is 343 sq.miles. (Ref: App. C-York Plan)  
The drainage area between the dam site and the outfall is 127 sq.miles. This dam will release a minimum drought flow of 40 cfs. The contribution due to an additional 127 sq.miles is 1.9 cfs based on a drought flow rate of 0.015 cfs/sq.mile. The Little River contributes 1.77 cfs at the discharge point which is based on a drainage area of 118 sq. miles. (See attached letter)

The reaeration rate was computed using O'Connor-Dobbins equation (see Appendix F of the 303(e) Plan). Using an average velocity of 0.5 fps and an average depth of 3 ft., a reaeration rate of  $1.76 \text{ day}^{-1}$  (base e,  $20^{\circ}\text{C}$ ) was obtained. An average depth of 3 ft. was assumed to reflect summer low flow conditions in the North Anna River. We have used the deoxygenation rate of  $0.23 \text{ day}^{-1}$  (base e,  $20^{\circ}\text{C}$ ). The same  $K_1$  rate was used for discharge into South Anna River by Roy Weston. A temperature of  $29^{\circ}\text{C}$  was used for the analysis which reflects the highest temperature recorded at the Rt. 30 Bridge on August 17, 1977 (see attached memo). The DO of the effluent is assumed to be 6.5 mg/l which is in agreement with the present NPDES permit limits. The results are summarized in Table 1.

If you have any questions concerning this matter, please let me know.

sw

Attachments

TABLE 1

<u>Parameters</u>	<u>Proposed Discharge to North Anna River</u>	<u>Source of Information</u>
<u>Stream Characteristics</u>		
Receiving Stream	North Anna River	North Anna River
7/10 Low Flow Upstream of Outfall (cfs)*	43.68	
Stream Velocity (fps)	0.5	**
Background DO (mg/l)	6.82	
Critical Water Temperature (°C)	29	PRO
Background BOD (ultimate) (mg/l)	1.88	**
<u>Reaction Rate Constants</u>		
K <sub>1</sub> Deoxygenation (Base e, 20°C)	0.23	**
K <sub>2</sub> Reaeration (Base e, 20°C)	1.76	**
<u>Allowable Effluent Limits</u>		
Effluent Discharge (mgd)	2.5	
DO <sub>eff</sub> (mg/l)	6.5	
BOD (ultimate) (mg/l)	67.5	
BOD (ultimate) (lbs/day)	1407.0	

---

BOD (ultimate) = CBOD (ultimate) + NBOD (ultimate)

\* 7-Day, 10-Year Low Flow = 41.91 (North Anna) + 1.77 (Little Creek) = 43.68 cfs

\*\* Information gathered via telephone conversation with Kevin Phillips of Roy Weston by PRO staff. This information was used for Pamunkey and South Anna Rivers.



# Associated Engineers

ENGINEERS • SURVEYORS • PLANNERS

STATE WATER CONTROL BOARD

JAN 18 1972




Post Office Box 5189

Ashland, Virginia 23005

Phone (A/C 703) 798-5773

January 8, 1972



State Water Control Board  
P. O. Box 11143  
Richmond, Va. 23230

Attn: Mr. C. L. Jones

Dear Mr. Jones;

We are preparing a preliminary proposal submittal for a waste treatment facility to serve the community of Doswell, Va. and the Kings Dominion Amusement Park which is now under construction.

In this regard we would like to request from you the degree of treatment that will be required for this installation.

We are enclosing a data sheet and location map for your use in making your determinations.

The aforementioned amusement park is scheduled to open on April 1, 1975 and will require sewerage services approximately 6 months prior to opening. We would, therefore, appreciate your requirements and recommendations as soon as scheduling will permit.

If additional information is needed or elaboration required on the attached data please contact us at any time.

We appreciate your assistance in this matter.

Sincerely,

William F. Goodfellow, P. E.  
Associated Engineers

cc: Mr. Norman Phillips, S.H.D.


WFG/mfh

1/12/72  
C. L.

DOCKELL WASTE TREATMENT FACILITY

DATA SHEET

- A. Plant Location- Lat  $37^{\circ} 40' 31''$ , Long  $77^{\circ} 25' 41''$ , on the northwest bank of the confluence of the North Anna and Little Rivers. (See Attached Sketch).
- B. Owner of Facility- County of Henrico.
- C. Plant Design Discharge- 1. Initial Stage - 0.5 MGD  
2. Ultimate Stage - 2.0 MGD
- D. Receiving Stream- North Anna and Little Rivers (Tributaries to York River)
- E. Stream Particulars- 1. Drainage area at discharge point is 589 square miles (118 sq. mi. from Little River and 471 sq. mi. from North Anna River.  
2. Vepco's North Anna Dam, located 29.7 miles upstream, will release a minimum drought flow of 40 CFS. Drainage area between the dam and discharge point is 127 square miles.  
3. Jarrell's Truck Stop, located at U. S. Route 30 and I-95, is currently operating a waste treatment facility (sewage lagoon) which will be obviated by the County plant.
- F. Other Data- A water treatment facility of equal design capacities will be constructed concurrently with the waste treatment plant and will be located approximately 1200 feet upstream.



# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

SUBJECT: Choosing Flow and Temperature Values for Modeling the North Anna River for the Doswell STP Discharge

TO: File

FROM: Joyce L. Hoyle

DATE: May 23, 1978

COPIES:

The seven-day, ten-year low flow recorded at the gage on the North Anna River is 6.5 cfs (0.015 cfs/sq.mile), but this is augmented by 40 cfs from the dam. This makes the total flow above the discharge 46.5 cfs.\*

The closest USGS water quality gage is on the Pamunkey River near Hanover. The monthly average temperatures for the months of May through September are shown below for the period of record.

### AVERAGE MONTHLY TEMPERATURE (°C)

Station: Pamunkey River near Hanover (01673000)\*\*

<u>Year</u>	<u>May</u>	<u>June</u>	<u>July</u>	<u>August</u>	<u>September</u>
1975	19.5	25.0	25.5	25.5	22.5
1974	19.5	22.5	-	25.5	21.0
1973	19.5	23.0	25.5	27.0	24.5
1972	18.0	21.5	24.0	23.5	21.0
1971	17.5	22.5	25.5	25.0	21.0
1970	21.3	23.3	26.2	26.3	23.7
1969	19.0	23.0	25.0	24.0	-
1968	16.0	22.0	-	25.0	19.0

(-) Incomplete Data.

\*\* Source: Water Resources Data for Virginia (1968-1975).

\* See Page 56 of the York River Basin Plan.

Memorandum to File

Choosing Flow and Temperature Values for Modeling the North Anna River  
for the Doswell STP Discharge

Page 2

May 23, 1978

A glance at the table above will show that  $27^{\circ}\text{C}$  was the highest monthly average temperature. The highest instantaneous temperature recorded was  $28^{\circ}\text{C}$ .

There are six ambient monitoring stations on the North Anna River in Hanover County. Ambient monitoring only records instantaneous temperatures. The highest temperature recorded at any of these stations is  $29^{\circ}\text{C}$  at the Route 30 bridge on August 17, 1977. Since the temperature of  $29^{\circ}\text{C}$  was actually recorded in the North Anna River under conditions of fairly low flow, I suggest using  $29^{\circ}\text{C}$  for modeling.

SW

# MEMORANDUM

## State Water Control Board

2111 North Hamilton Street

P. O. Box 11143

Richmond, VA. 23230

*JB*  
*rey*

SUBJECT: Amendment of Doswell NPDES Permit VA0029521

TO: File (42-0525)

FROM: S. S. Waldo and R. R. Jenkins *Ray Jenkins*

DATE: June 19, 1978

COPIES: L. G. Lawson, J. J. Cibulka, W. D. Jones, Dale F. Jones,  
60-0033

By letter dated April 7, 1978, John E. Longmire, Hanover County Administrator, transmitted a permit amendment request for the Doswell Wastewater Treatment Plant. The permit amendment request reflected the discharge of treated wastewater from the proposed Bato plant. The amendment request was updated by a letter dated April 28, 1978 and completed by correspondence with transmittal dates of May 8, 1978 and May 26, 1978. Mr. Longmire requested that the Board consider a tiered permit to take into account increased assimilative capacity in the stream during the periods of high flow in the North Anna River (other permits incorporating this concept have been written in the State, although this is the first permit that incorporates an "instantaneous" correlation between river flow and discharge).

The staff has investigated the feasibility of a tiered permit concept for the Doswell permit. In that an allocation for Doswell is already included in an adopted 303(e) plan (York River Basin), the original intent of the investigation was to preserve all parameters used in the adopted allocation modeling. By retaining the original inputs, the generation of tiered levels of discharge does not constitute remodeling, but only a recalculation using the existing model. Subsequently, it was discovered that an obvious error had been made in the original allocation. The original modeling in 1973 resulted in an allowable discharge of 400 lbs/day at 2 MGD wastewater flow. But when Hanover County decided to build only a 1 MGD treatment plant, this 400 lbs/day was simply halved to obtain an allocation of 200 lbs/day. In addition, it was determined that the river temperature used in the modeling and the 7-day/10-year low flow used were incorrect. It was then decided that the errors would be corrected and appropriate revisions to the 303(e) plan proposed. These revisions were to change the stream temperature (29°C instead of 32.2°C) and to revise the flow (46.5 cfs\* instead of 42.4 cfs for the North Anna River at 7-day/10-year low flow). No other changes were made; i.e., rate coefficients selected at 20°C in the original modeling ( $K_1^* = 0.13$ ,  $K_2^* = 0.68$ ),  $UBOD^*/BOD_5^*$  ratio(1.3),

\*Terms: cfs = cubic feet per second  
 $K_1$  = deoxygenation rate  
 $K_2$  = reaeration rate  
UBOD = ultimate biochemical oxygen demand  
BOD<sub>5</sub> = 5-day biochemical oxygen demand

File No. 42-0525

Page 2

June 19, 1978

etc. remain the same. The resulting calculations were run precisely in accordance with the procedure previously used in the 303(e) allocation, with the exception of the temperature change and flow change mentioned above and discussed more fully below. Thus the basic modeling remains unchanged. All inputs to the modeling equation were those determined for the seven-day/ten-year low flows; the inputs were not adjusted at increased river flows. Fixing these factors keeps the calculations more conservative (i.e., increases the "safety factors").

The original modeling used a stream temperature of  $32.2^{\circ}\text{C}$ . This temperature was taken directly from the Water Quality Standard for a Class III stream (i.e.,  $90^{\circ}\text{F} = 32.2^{\circ}\text{C}$ ). This methodology of choosing a stream temperature was used only for a short time by the Board and since then the ambient temperature, as measured instream, has been used exclusively. For the North Anna River this temperature was determined to be  $29^{\circ}\text{C}$ , which is the maximum temperature observed.

The original modeling used a critical flow in the North Anna River of 42.4 cfs. An investigation of stream flow for the North Anna River has determined that, in fact, the critical flow is 46.5 cfs. This is based on a guaranteed release from Lake Anna of 40 cfs and a "stretch" flow in the drainage area between the lake and the Doswell gaging station of 6.5 cfs. The use of the corrected values for river temperature and flow more precisely reflect actual conditions in the stream.

In making the calculations a simplification was made by letting the input variable to the modeling equation be the ultimate biochemical oxygen demand (UBOD) of the discharge-river mix (hereafter referred to as  $L_0$ ). This procedure was preferred to the more typical procedure of inputting various wastewater flow and concentration values.

When the temperature was corrected to  $29^{\circ}\text{C}$ , an additional simplification was made in the modeling. The existing Doswell permit requires a minimum dissolved oxygen (DO) level of 6.5 mg/l. At  $32.2^{\circ}\text{C}$ , the background river DO is also 6.5 mg/l. Therefore, at any wastewater volume-river volume mix, the DO of the mix is 6.5 mg/l. At  $29^{\circ}\text{C}$ , however, the background stream DO is 6.84 mg/l and the effluent DO is still 6.5 mg/l. Effluent volume now influences the DO of the mix and, therefore, influences the results of the modeling calculations. The simplification in the calculations was to input an initial DO of the mix of 6.8 mg/l. This value results from the mass balance of 4.0 MGD (in accordance with Hanover's amendment application for ultimate flows) of wastewater with a DO of 6.5 mg/l and a river flow of 49 cfs with a DO of 6.84, and should represent the lowest initial DO under any conditions (Note: The flow of 49 cfs includes 46.5 cfs from the North Anna River and the 7-day/10-year low flow of 2.5 cfs from the Little River, which enters the North Anna immediately below the discharge.). Since the effluent volume is small in comparison to total flow, this simplification impacts the results only slightly.

File No. 42-0425

Page 3

June 19, 1978

As a result of setting all of the foregoing parameters constant at "worst case conditions", the calculations were performed with only one variable - the UBOD of the discharge-stream mix ( $L_o$ ). It was then observed that by having fixed all other input values,  $L_o$  did not change with increased river flow when the same DO value at the "sag" was calculated. Using an  $L_o$  so determined, a mass balance equation is used to calculate the allowable discharge concentration for various wastewater and stream flows. The inputs to the calculations included the Little River at a 7-day/10-year low flow of 2.5 cfs and the South Anna River 3.7 miles downstream of the discharge at a 7-day/10-year low flow of 12.1 cfs. The UBOD background of the rivers was 3.0 mg/l ( $BOD_5 = 3.0/1.3 = 2.3$ ) and all stream velocities were 0.5 fps. The calculations indicated that the sag point occurred below the confluence with the South Anna River. The critical dissolved oxygen deficit of 0.96 mg/l (10% of D.O. saturation at 29°C, 0.76 mg/l, plus 0.2 mg/l, anti-degradation application for this case) occurred at an  $L_o$  of 5.5 mg/l.

When used as described above, the calculations indicate that the Board's anti-degradation policy will be met as long as a UBOD ( $L_o$ ) of 5.5 mg/l ( $UBOD/BOD_5 = 1.3$ ; therefore,  $BOD_5 = 4.2$  mg/l) is maintained in the mix of the stream and wastewater flow. Using this knowledge, an equation was developed which can be used to determine an allowable  $BOD_5$  discharge concentration at various stream flows. This equation was derived from the basic mass balance equation:

$$L_{mix} = \frac{Q_s L_s + Q_w L_w}{Q_s + Q_w}$$

Where:

$L_{mix}$  =  $BOD_5$  of the stream-wastewater mix

$Q_s$  = stream flow

$Q_w$  = wastewater flow

$L_s$  = background  $BOD_5$  in stream

$L_w$  =  $BOD_5$  of wastewater

• Using known values and calculating for  $L_w$ :

$$4.2 = \frac{Q_s (2.3) + Q_w L_w}{Q_s + Q_w}$$

Re: Amendment of Doswell NPDES Permit VA0029521

File No. 42-0525

Page 4

June 19, 1978

or, in another form,

$$L_w = \frac{4.2 + 1.9Q_s}{Q_w} \quad \text{Equation (1)}$$

Use of this equation enables an operator or a regulatory agency to easily enter stream flow and wastewater flow to determine the allowable effluent BOD<sub>5</sub> ( $L_w$ ) which will maintain the State's water quality standards. At a wastewater flow of 2.5 MGD, which is the proposed start-up flow, and critical low flow of 49 cfs, the low flow allocation was determined to be 584 lbs/day. This low flow allocation will be one of the proposed changes to the 303(e) plan.

There is a requirement which is also controlling for this discharge. 40CFR133 limits domestic waste discharges to a concentration of 30 mg/l BOD<sub>5</sub> and total suspended solids (TSS). However, 40CFR133.103(b) (Secondary Treatment Definition: Industrial Waste) allows for an increase in the "secondary treatment" limitation of 30 mg/l for BOD and suspended solids in proportion to the industrial contribution to the total wastewater flow at the industrial wastewater concentration which would apply for an industrial point source discharge by that industry type. Since the Bato wastewater will be treated to levels of 50 mg/l BOD<sub>5</sub> and total suspended solids (which will be defined by the Board as "new source" discharge limitations for this industry), this concentration is used in the following mass balance equation to define an allowable discharge concentration for BOD<sub>5</sub> and total suspended solids:

$$\text{TSS or BOD}_5 (\text{mg/l}) = \frac{30Q_H + 50Q_B}{Q_H + Q_B} \quad \text{Equation (2)}$$

While the BOD<sub>5</sub> limitation is controlled by either Equation (1) or Equation (2), whichever is more stringent, Equation (2) is the only controlling equation for the total suspended solids discharge.

A maximum limitation has also been established for BOD<sub>5</sub> and total suspended solids quantity. This limitation is based on 1 MGD of Doswell wastewater at 30 mg/l BOD<sub>5</sub> and TSS and 3.0 MGD at Bato wastewater at 50 mg/l. The flow figures are in accordance with Hanover's amendment application. The appropriate quantity calculation gives a maximum allowable quantity discharge of 1500 lbs/day. This limit cannot be exceeded regardless of the value determined by Equations (1) or (2).



File No. 42-0525

Page 5

June 19, 1978

Before describing the actual proposed permit amendment, it is important to summarize the conservative factors which were used in the derivations of the above equations. These are listed below:

1. Segment flow (runoff, groundwater and small streams) was not included below the discharge point.
2. Stream velocity and other inputs to the calculation were set at critical low flow and were not changed with increased river flow.
3. A minimum initial mix DO of 6.8 mg/l was used instead of recalculating the mix at higher stream flows; recalculating would have the effect of slightly increasing the mix DO.
4. The rate of coefficients were not redefined below the confluence of the North and South Anna Rivers (deoxygenation coefficient would actually drop; reaeration coefficient would actually increase).

The investigators point out that these calculations assume a complete mix at the discharge. However, the point should also be made that this assumption is used in every "free flowing" modeling effort and is completely in accordance with prior modeling practices.

#### Permit Conditions

The proposed permit amendments were drafted in such a way as to maximize the use of Equations (1) and (2) above. This necessitated a unique permit in that BOD<sub>5</sub> and suspended solids limitations are not specifically placed in the permit. Each value must be calculated using Equations (1) or (2).

Because Equation (1) is geared towards an "instantaneous" correlation between river flow and discharge concentration, it was necessary to provide a shorter limitation period than a one month average, which is normal on most other permits. It was resolved that the BOD<sub>5</sub> and total suspended solids limitations will be reported as a weekly average of 7 calendar day values, and also that additional monitoring would be required to have an "instantaneous" correlation between BOD<sub>5</sub> and some other parameter (TOC\* or COD\*) to enable an operator to determine at any point in time with some degree of surety whether or not he is in compliance with the permit. The limitations included on the composite waste discharge (point source 001) are as follows:

\*Terms: TOC = Total organic carbon  
COD = Chemical oxygen demand

Re: Amendment of Doswell Permit VA0029521

File No. 42-0525

Page 6

June 19, 1978

The BOD<sub>5</sub> limitation is referenced as paragraphs 4(a) through (d) in Part I, paragraph A-1 of the attached proposed amendments. 4(a) is a modification of Equation (1) listed above, which requires a weekly average. 4(b) does the same for Equation (2) above. 4(c) states that the more stringent of (a) and (b) above shall be the effluent BOD<sub>5</sub> concentration, except when flows are at 7-day/10-year low flow or less, at which time the more stringent of the following shall apply:

1. The maximum quantity allowable shall be no greater than 584 lbs (this is the waste load allocation which is proposed to be included in the 303(e) plan).
2. The concentration established by 4(b) above (which is the "secondary treatment" limitation).

4(d) states that the effluent BOD<sub>5</sub> quantity discharge shall not exceed 1500 lbs/day at any time.

Paragraphs 5(a) and (b) are the limitations for total suspended solids and are based on Equation (2) above modified to show a weekly average. 5(b) also limits the maximum quantity discharge at 1500 lbs/day.

Paragraph 6 is included to provide "real time" control over the amount of waste discharged. Because a lag time of 5 days is inherent in the BOD<sub>5</sub> test, it was realized that it was necessary to have some instantaneous determination of effluent quality for the operator to use in determining his allowable discharge. It was determined that this could be done best by a plot of TOC vs. BOD<sub>5</sub>, which would be updated using corresponding 24-hour composite samples of TOC and BOD<sub>5</sub> daily. This plot would be composed of data from a rolling 30 consecutive day period so that when a new data point is added, the oldest data point would be removed. Since it is possible that a plot of TOC vs. BOD<sub>5</sub> might not give the best correlation for these particular wastewaters, a special requirement was included in the proposed amendment which requires the permittee to also run COD tests on the same frequency as TOC to determine if COD would be a better correlation. At the end of the first six months of operation, the results will be evaluated to determine which parameter (i.e., TOC or COD) gives the closer correlation.

It is also necessary to place monitoring requirements on the separate waste streams coming into the combined outfall so that waste quality can be determined on each. These monitoring requirements are included as paragraph A-2 for Bato and paragraph A-3 for Hanover. Additionally,

Re: Amendment of Doswell NPDES Permit VA0029521

File No. 42-0525

Page 7

June 19, 1978

it was necessary to place a total chlorine residual limitation on the effluent from Hanover which is included in Paragraph A-3. The Bato waste stream does not include any sanitary waste (it is separately transported to the Doswell plant), thus, no chlorination is required. The permit requires that a plot of TOC vs. BOD<sub>5</sub> will be developed for each of these waste streams so that an operator can determine immediately the approximate quality of either waste stream.

Because of the special nature of the effluent limitations for this plant, it was necessary to develop a new reporting form also. This form is attached to the memorandum. The form includes spaces for entering all parameters which will be necessary to calculate the BOD<sub>5</sub> and total suspended solids limitations and for reporting actual final discharge values of BOD<sub>5</sub>, total suspended solids, pH, and dissolved oxygen (and total chlorine residual for the Doswell waste stream). In addition, a report form for the TOC, COD, and BOD<sub>5</sub> data used to develop the correlation plot is also included as an attachment.

Because the BOD<sub>5</sub> and total suspended solids limitations are based on a calendar week average, it was necessary to address this fact in the development of the monitoring report form. Paragraph 7 of Part I, A-1, states that if any month ends in an incomplete calendar week, the report for that week shall be included in the following monthly reporting period. For that reason, the report form has spaces for five weeks on it realizing that during some months there will only be three calendar weeks filled out and in others there will be five. Beyond these special reporting requirements the monitoring report form contains all the information required and included in the standard DMR format currently used in other NPDES permits, including a space for bypass and overflow information and a signature block.

The remainder of the permit shall be made up of standard pages, therefore, no discussion of those conditions is included here.

Any questions concerning the development of this proposed permit should be directed to the writers or Wesley Jones.

/pc  
Attachments

**Attachment 10**

F. LAKE LEVEL CONTINGENCY PLAN


The intent of this condition is to allow specific reductions in the lake discharge flow when the lake water level drops below designated levels due to drought conditions, taking into account and minimizing any adverse effects of any release reduction requirements on downstream users.

1. Except as provided in 2. below, the permittee shall at all times provide a minimum instantaneous release from the Lake Anna impoundment of 40 cfs.
2. When the level in Lake Anna reaches 248 feet above mean sea level (msl), the permittee will begin reducing releases below the 40 cfs minimum in accordance with the following conditions:
  - a. Minimum instantaneous releases shall not drop below 20 cfs.
  - b. The Water Compliance Manager of DEQ's Piedmont Regional Office and the downstream users identified below will be given at least 72 hours notice by the permittee prior to the initiation of flow reductions:
    - ◆ Hanover County Public Utilities
    - ◆ Bear Island Paper Company
    - ◆ Engel Farms, Inc
    - ◆ Pamunkey Indian Tribal Government
  - c. Skimmer gate adjustments will be performed in accordance with Station Operating Procedures.
  - d. Releases shall be stepped down in increments of approximately 5 cfs with at least a 72-hour period following each incremental reduction and prior to any subsequent reduction.
  - e. During the period in which releases are reduced below 40 cfs, conditions in the North Anna River shall be monitored in accordance with the monitoring plan submitted by the permittee and approved by the DEQ prior to implementation of the Lake Level Contingency Plan.
  - f. Releases from the dam shall return to 40 cfs upon the Lake level returning to greater than 248 ft. msl. Increases of flow will occur in 5 cfs increments with a 24 hour wait period prior to the next gate adjustment.
  - g. If any downstream user identifies an adverse effect at any time during flow reductions and notifies the DEQ of the adverse effect, the Director shall make a timely investigation. If after notice to the permittee and the affected downstream users the Director finds an adverse effect from the flow reductions, the flows shall be increased in 5 cfs increments with a 24 hour wait period prior to the next gate adjustment, until the flow reaches 40 cfs or the Director finds that the adverse effect has been eliminated.
  - h. Adverse effect is defined as the inability to withdraw/discharge water for proper operation of facilities, or impairment of water quality.

## **Attachment 11**

WATER QUALITY MODELING  
NORTH ANNA AND PAMUNKEY RIVERS  
YORK RIVER BASIN, VIRGINIA

Prepared for:  
Bear Island Paper Company  
Ashland, Virginia



HDR Project Number 317-10-35

Prepared by:  
HDR Infrastructure, Inc.  
6400 Fairview Road  
Charlotte, North Carolina

January 1988

TABLE OF CONTENTS (continued)

	<u>Page</u>
7.0 1987 MODEL SIMULATIONS.....	83
7.1 General Approach.....	83
7.2 Oxygenation of Effluent.....	84
7.3 Deaeration Under Supersaturated Conditions.....	87
7.4 Model Simulation.....	89
8.0 PROPOSED NPDES CRITERIA.....	99
8.1 Allowable CBOD.....	99
8.2 Oxygen Addition.....	105
REFERENCES.....	111
APPENDICES	
A. NPDES Permit	
B. Field Sampling Plan and Quality Assurance/Quality Control Document	
C. River Channel Profiles	
D. Stream Gaging and Velocity Calculations	
E. Laboratory Water Quality Analytical Reports	
F. In-Situ Sediment Oxygen Demand in North Anna and Pamunkey Rivers	
G. Literature Review of Sediment Oxygen Demand in Rivers and Streams	
H. 7Q10 Low-Flow Information	
I. Computer Model Output	
J. Development of TKN Design Wasteload	
K. Historical Water Temperature and Flow	
L. Analysis of Biodegradable TKN Fraction	
M. Selected Papers on Post-Aeration of Effluent and Deaeration Under Supersaturated Conditions	



## ANALYSIS OF BIODEGRADABLE TKN FRACTION

Prepared for

Bear Island Paper Company and Hanover County, Virginia

### INTRODUCTION

The Bear Island Paper Company operates a TMP pulp and paper mill in Ashland, Virginia. Wastewater from the mill is treated on site and is discharged into a national pollutant discharge elimination system (NPDES) regulated outfall (NPDES #VA0029521) controlled by Hanover County, Virginia. The NPDES permit was renewed in October 1985, and, as part of that renewal, the effluent standard was modified.

The previous permit had not been regulated for either ammonia or total kjeldahl nitrogen (TKN). An effluent TKN limitation of 6 mg/l was implemented as part of the permit renewal. The TKN limitation was imposed to control oxygen utilization in the receiving stream. The TKN oxygen utilization was based on 4.5 mg of oxygen per mg TKN.

The use of the TKN limit in the final October 1985 NPDES permit was a last minute alteration of the draft (as a draft of the permit had previously been based on ammonia). The assumption made by Hanover County and Bear Island Paper Company (BIPCO) in accepting the TKN limit was that the only TKN in the effluent would be in the form of ammonia nitrogen. The long-term wastewater treatment plant data had indicated that a discharge of less than 6 mg/l ammonia could be achieved. Therefore, the 6 mg/l TKN limit was thought to be an acceptable limitation.

In the final NPDES permit issuance, the State had a provision for the substitution of the ammonia limit for the TKN limit. However, any such

substitution would require approval from the State Water Control Board (SWCB) staff.

Subsequent to the implementation of the revised permit, it has been found that the combined effluent consistently exceeds the 6 mg/l TKN limitation. However, the discharge has been in compliance with the 6 mg/l ammonia limitation.

HDR was retained in 1986 to evaluate this situation. A preliminary analysis was conducted which indicated that a significant portion of the TKN in the Bear Island wastewater was non-biodegradable and the use of a theoretical TKN oxygen utilization would not be correct. The program to determine oxygen utilization of the waste was conducted utilizing inhibited and noninhibited BOD analyses. The results of this program are presented in Table 1. This indicated that the TKN in the Bear Island wastewater did not exert the 4.5 mg/l oxygen demand.

Based on the results of the preliminary testing program, the Bear Island Paper Company, in conjunction with Hanover County, entered into a consent agreement with the State of Virginia. A primary objective of that consent agreement was to identify the biodegradable portion of the TKN in the BIPCO effluent.

The results of the biodegradation program are presented in this report.

#### BIODEGRADATION PROGRAM

The methodologies for conducting the biodegradation program followed the procedures which had been previously submitted to and approved by the SWCB. A copy of the procedure is presented in Appendix A. All samples were

TABLE 1  
SUMMARY OF TKN OXYGEN UTILIZATION  
BEAR ISLAND EFFLUENT

Sample Date	TKN (mg/l)	NH <sub>3</sub> -N (mg/l)	BOD <sub>20</sub> Inhibited (mg/l)	BOD <sub>20</sub> Uninhibited (mg/l)	TKN Oxygen Utilization $\frac{\text{mg O}_2}{\text{mg TKN}}$	Organic Nitrogen Oxygen Utilization $\frac{\text{mg O}_2}{\text{mg O-N}}$
May 9	10.92	0.17	31	40	0.82	0.75
May 14	6.97	0.21	24	29	0.72	0.58
May 19	12.35	3.30	73	73	0	0
May 22	1.29	0.07	49	51	1.55	1.30

collected by personnel from either BIPCO or Hanover County and all analyses were conducted by Environmental Laboratories, Inc. of Ashland, Virginia.

### BIODEGRADATION RESULTS

In order to determine the biodegradable portion of the TKN a series of flask tests were initiated. The first tests were set up with waste samples collected on July 14, 1987, (sulfonation being utilized) and the second set with samples collected on August 26, 1987, (TMP production with purchased Kraft). Tests were performed on both TMP with purchased Kraft and sulfonation wastewaters. Phase I consisted of sulfonation wastes and Phase II was comprised of the TMP with purchased Kraft.

The samples for analysis were prepared by combining the wastewater samples with dilution water and seed in accordance with the test procedure and were maintained in test flasks under an oxygen blanket. Samples from the TKN testing flasks were collected and analyzed every 10 days. A summary of the data from the individual flasks is presented in Appendix B.

The TKN biodegradability data for the tests are presented on Table 2. The results from the tests are plotted and are presented in Figures 1 thru 6. The analysis of the data indicates that the degradable portion on BIPCO wastewater and combined Doswell/BIPCO wastewater is very similar, i.e., 34 to 46% degradable TKN. Therefore, for the purposes of performing the water quality modeling, it is recommended that the analysis be based on 46% degradable and 54% nondegradable TKN.

TABLE 2  
TKN BIODEGRADABILITY

Phase	Sample	Initial TKN, mg/l	Final TKN, mg/l	% Degradable TKN	% Non-degradable TKN
I	BIPCO	4.76	3.17	33	67
	Doswell	5.82	1.15	80	20
	Combined	6.16	4.08	34	66
II	BIPCO	11.40	6.16	46	54
	Doswell	1.89	0.22	88	12
	Combined	9.25	5.76	38	62




Figure 1: Chronological Variation - Phase I BIPCO






Figure 2: Chronological Variation - Phase I Doswell




Figure 3: Chronological Variation - Phase I Combined






Figure 4: Chronological Variation - Phase II BIPCO






Figure 5: Chronological Variation - Phase II Doswell




Figure 6: Chronological Variation - Phase II Combined

## APPENDIX A

### Procedure for Analysis of Non-Biodegradable TKN

## PROCEDURE FOR ANALYSIS OF NON-BIODEGRADABLE TKN

### I. DILUTION WATER

Dilution water shall be prepared as described below:

Buffer solution prepared according to Standard Methods contains ammonium ion, which would add to the measured nitrogenous BOD. Instead of using that formulation, prepare buffer as follows:

- Add the following reagents to approximately 500 mg of distilled/deionized water and dissolve. Then make up to one liter in a volumetric flask.
- 15.7 g.  $K_2HPO_4$
- 24.1 g.  $Na_2HPO_4 \cdot 7H_2O$
- 11.1 g.  $KH_2PO_4$

This solution should have a pH of 7.2 as prepared.

- Dilution water should be prepared according to Standard Methods, but with substitution of the above buffer.

### II. SAMPLE PREPARATION

Prepare sample for analysis consisting of:

- A. 1000 ml mill final effluent.
- B. 500 ml dilution water.
- C. Add commercially available nitrifying seed to culture.

Note: All testing to be performed in duplicate and with a control consisting of glucose-glutamic acid and ammonium chloride.

### III. INITIAL ANALYSIS

Analyze mill final effluent for TKN,  $NO_2/NO_3-N$ , and  $NH_3-N$ .

Analyze dilution water for TKN,  $NO_2/NO_3-N$ , and  $NH_3-N$ .

Analyze combined sample for pH, TKN,  $NO_2/NO_3-N$ , and  $NH_3-N$ .


- IV. Place sample in 2000 ml flask (as shown in Attachment A), maintain flask at ambient laboratory temperature, maintain under an oxygen blanket for 40 days

- V. Prior to aeration, at days 2, 5, 10, 20, 30 and 40, remove 50 ml sample and check pH and dissolved oxygen. The pH will be maintained in the 6.5 to 8.5 range and the dissolved oxygen in excess of 2 mg/l. If, at day 2 or any time low pH and DO levels are found, these will be adjusted and more frequent sampling will be initiated. Do not return sample to flask.
- VI. Analyze sample at days 10, 20, 40, and conclusion for TKN, NO<sub>2</sub>/NO<sub>3</sub>-N, and NH<sub>3</sub>-N. The conclusion of the test will be tied into the conclusion of the ultimate BOD test.
- VII. Non-biodegradable TKN percentage is defined as:

$$TKN_R = \frac{TKN_i - TKN_f}{TKN_i}$$

where:

TKN<sub>R</sub> = non-biodegradable TKN (Percent)  
TKN<sub>i</sub> = initial TKN (mg/l)  
TKN<sub>f</sub> = final TKN (mg/l)



REFRACTORY TKN TESTING APPARATUS

## APPENDIX B

### TKN Biodegradation Test Data



PROJECT : 317-03-35  
ANALYSIS BY: ENVIRONMENTAL LABORATORIES  
PHASE II. 66 PERCENT KRAFT WASTEATER

SAMPLE:BIPCO

SAMPLE A

SAMPLE B

AVERAGE OF A & B

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.19	8.0	10.40	11.90	1.58
2	7.20	8.0			
5	7.63	8.0			
10	7.42	9.6	8.67	16.60	1.17
20	7.96	8.0	6.25	16.20	0.80
30					
40	7.76	12.0	6.82	23.40	0.55
50			8.54	28.60	0.23
60	8.04	8.5	7.23	25.90	0.32
70	7.93	7.2	6.22	24.30	0.36
80					
90	8.21	8.1	5.80		

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.15	9.4	12.40	14.40	1.78
2	7.19				
5	7.56	9.2			
10	7.37	11.5		14.90	1.04
20	7.83	9.6	7.82	17.30	0.77
30					
40	7.74	12.0	6.94	24.70	0.68
50		6.7	5.41	27.20	0.23
60	8.38	11.5	5.88	28.20	0.29
70	7.98		6.11	24.60	0.35
80					
90	8.20	8.3	6.51		

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.17		11.40	13.15	1.68
2	7.20	8.68			
5	7.60	8.60			
10	7.40	10.55	4.34	15.75	1.11
20	7.90	8.80	7.04	16.75	0.79
30					
40	7.75	12.00	6.88	24.05	0.62
50	0.00	3.35	6.98	27.90	0.23
60	8.21	10.00	6.56	27.05	0.31
70	7.96	3.60	6.17	24.45	0.36
80					
90	8.21	8.20	6.16		

SAMPLE:DOSWELL

SAMPLE A

SAMPLE B

AVERAGE OF A & B

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.39		1.63	29.40	0.77
2	7.43	10.0			
5	7.60	10.6			
10	7.53	8.6	1.14	28.60	1.80
20	8.11	7.4	0.64	27.90	0.93
30					
40	7.73	12.5	0.93	37.80	0.77
50			0.31	39.00	0.29
60	8.31	9.3	0.40	48.90	0.23
70	8.22	7.9	1.11	41.70	0.69
80					
90	8.21	8.2	0.34		

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.28	11.3	2.14	24.30	1.88
2	7.27				
5	7.49	12.0			
10	7.30	14.5	1.20	27.50	1.67
20	8.26	9.2	2.06	27.90	0.82
30					
40	8.30	13.0	0.95	39.00	0.56
50			0.32	37.10	0.32
60	8.11	6.3	0.70	38.60	0.35
70	8.07	7.6	0.49	40.80	0.58
80					
90	8.14	8.2	0.10		

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.34		1.89	26.85	1.33
2	7.35	10.65			
5	7.55	11.30			
10	7.42	11.55	1.17	28.05	1.74
20	8.19	8.28	1.35	27.90	0.88
30					
40	8.02	12.75	0.94	38.40	0.67
50			0.32	38.05	0.31
60	8.21	7.80	0.55	43.75	0.29
70	8.15	7.75	0.80	41.25	0.64
80					
90	8.18	8.20	0.22		

SAMPLE:COMBINED

SAMPLE A

SAMPLE B

AVERAGE OF A & B

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.18		9.57	21.20	2.12
2	7.19	9.4			
5	7.41	9.4			
10	7.25	10.8	8.46	18.70	3.90
20	7.77	7.6	8.61	17.50	2.17
30					
40	7.54	14.5	7.36	24.90	2.80
50			7.56	53.40	0.68
60	7.84	7.9	6.58	28.90	0.66
70	7.62	7.4	6.46	28.60	0.49
80					
90	8.01	7.9	5.58		

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.20	9.0	8.93	18.80	1.04
2	7.19				
5	7.41	8.5			
10	7.20	10.6	9.74	17.80	3.92
20	7.55	8.1	11.49	18.20	2.14
30					
40	7.45	10.5	7.38	27.20	0.94
50			7.53	56.90	0.49
60	7.77	8.5	7.41	28.40	0.38
70	7.85	7.6	4.43	29.40	5.94
80					
90	6.79	8.1	5.93		

TIME DAYS	pH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.19		9.25	20.00	1.58
2	7.19	9.20			
5	7.41	8.93			
10	7.23	10.70	9.10	18.25	3.91
20	7.66	7.85	10.05	17.85	2.16
30					
40	7.50	12.50	7.37	26.05	1.87
50			7.55	55.15	0.59
60	7.81	8.20	7.00	28.65	0.52
70	7.74	7.50	5.45	29.50	3.22
80					
90	7.40	8.00	5.76		

PROJECT: 517-03-35  
ANALYSES BY: IRONMENTAL LABORATORIES  
66 PERCENT SULFONATION WASTEWATER  
PHASE I.

SAMPLE:BIPCO

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.17	15.8	4.12	0.30	0.15
2	7.36	15.1	8.28		
5	7.12	15.1	10.10		
10	7.24	9.6		<0.02	0.93
20	7.41	7.3		<0.02	2.84
30	7.45	6.8			
40	7.28	10.8	6.46	0.94	0.83
50	7.24	12.7	4.29	3.41	0.20
60	7.30	13.0	3.51	4.48	0.42
70	8.36	8.5	3.98	4.31	0.22
80					
90	8.59	8.0	5.99	5.96	0.28
100			3.14	6.53	0.28
114	8.18	7.3	2.03	5.49	0.11
120					
130	8.17	10.1	4.51	6.76	0.09
140	8.26	11.8	4.12	4.47	
150	8.80	16.5	2.70	5.60	

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.18	9.20	5.40	0.19	0.15
2	7.30	14.60			
5	7.37	8.50	1.44	<0.02	0.43
10	7.38	8.40	8.54	0.07	1.68
20	7.31	6.80			
30	7.35	6.80			
40	7.28	12.00	6.56	0.85	0.93
50	7.28	14.90	5.83	1.42	0.31
60	7.25	15.10	5.16	2.36	0.28
70	8.47	9.40	6.00	2.50	0.22
80					
90	8.79	9.00	7.16	3.51	0.91
100			5.08	5.99	0.17
114	8.19	7.70	7.78	9.19	<0.02
120					
130	8.15	10.50	3.65	7.00	0.13
140	8.34	12.80	3.83	4.47	
150	8.92	16.00	3.64	5.21	

AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.18	12.50	4.76	0.25	0.15
2	7.63	14.85	4.14		
5	7.25	9.05	5.77		0.68
10	7.31	7.85	4.27	0.04	2.26
20	7.36	6.80			
30	7.40	11.40	6.51	0.90	0.83
40	7.27	13.80	5.06	2.42	0.26
50	7.27	14.05	4.34	3.42	0.35
60	7.28	14.05	4.99	3.41	0.22
70	8.42	8.95			
80					
90	8.69	8.50	6.43	4.74	0.55
100			4.11	6.26	0.28
114	8.19	7.50	4.91	7.34	0.06
120					
130	8.16	10.30	4.08	6.88	0.11
140	8.30	12.30	3.98	4.47	
150	8.86	16.25	3.17	5.41	

SAMPLE:DOSHILL

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.25	16.50	5.54	14.66	2.01
2	7.69	16.80			
5	7.56	16.80			
10	7.80	9.80	6.02	1.25	3.08
20	6.90	8.80	1.75	12.50	0.55
30	7.24	7.18			
40	7.40	12.70	1.09	14.40	0.25
50	7.33	14.40	1.12	20.95	0.29
60	7.30	14.50	<0.10	18.29	0.27
70	8.58	7.10	<0.10	22.40	0.23
80					
90	8.10	13.50	0.68	41.60	0.24
100			0.38	26.00	0.55
114	8.15	7.80	0.53	18.03	0.15
120					
130	7.66	10.30	0.52	24.00	0.08
140	8.22	12.00	0.81	15.20	
150	8.84	18.50	0.53	17.50	

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.22	6.80	6.09	12.73	1.95
2	7.14	10.40			
5	6.82	10.20	5.15	7.75	3.36
10	7.00	11.10	2.47	9.89	1.25
20	6.50	7.40			
30	6.63				
40	7.08	12.00	1.20	14.40	0.17
50					
60					
70					
80					
90					
100					
114					
120					
130					
140					
150					

AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.24	11.65	5.82	13.70	1.98
2	7.19	13.60			
5	7.30	9.90	5.59	4.50	3.22
10	6.70	9.95	2.11	11.20	0.90
20	7.04	7.29			
30	7.24	12.35	1.15	14.40	0.21
40					
50					
60					
70					
80					
90					
100					
114					
120					
130					
140					
150					

CONTAMINATED

SAMPLE:COMBINED

SAMPLE A

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.26	15.00	6.30	2.18	0.81
2	7.42	15.40			
5	7.28	13.40	4.60	0.52	1.18
10	7.36	10.10	7.49	1.02	2.24
20	7.29	8.30			
30	7.23	6.80			
40	7.24	11.00	5.49	0.20	0.36
50	7.33	11.90	4.84	4.29	
60	7.40	11.50	1.49	6.04	
70	8.57	7.90	5.04	6.22	
80					
90	9.04	8.40	7.25	8.48	0.20
100			6.77	14.32	0.46
114	8.20	9.70	7.04	9.99	0.23
120					
130	8.12	10.90	4.11	12.83	0.28
140	8.25	12.50	4.91	8.65	
150	9.11	13.50	7.11	NA	

SAMPLE B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.23	14.20	6.01	2.16	0.69
2	7.47	15.80			
5	7.26	9.80	6.12	0.46	1.52
10	7.27	10.20	7.39	0.81	1.23
20	7.08	6.73			
30	7.13	6.73			
40	7.26	13.50	6.02	3.79	0.14
50	7.36	13.30	5.26	4.56	
60	7.43	13.20	5.79	4.16	
70	8.46	9.60	5.79		
80					
90	8.43	9.50	7.50	5.33	0.41
100			5.20	7.73	0.19
114	8.17	7.70	4.34	<0.02	0.15
120					
130	8.19	10.70	4.04	9.50	0.15
140	8.33	12.00	3.25	6.29	
150	8.74	16.50	3.91	7.49	


AVERAGE OF A & B

TIME DAYS	PH	DO mg/l	TKN mg/l	NO2/NO3-N mg/l	NH3-N mg/l
0	7.25	14.60	6.16	2.17	0.75
2	7.45	14.60			
5	7.27	9.95	5.36	0.49	1.35
10	7.32	9.25	7.44	0.92	1.74
20	7.19	6.77			
30	7.18	6.77			
40	7.25	12.25	5.76	0.10	0.25
50	7.35	12.60	5.05	4.04	
60	7.42	12.35	5.30	5.20	
70	8.52	8.75	5.42	5.19	
80					
90	8.74	8.95	7.38	6.91	0.31
100			5.99	11.03	0.33
114	8.19	8.70	5.69	5.00	0.19
120					
130	8.16	10.80	4.08	11.17	0.22
140	8.34	12.25	4.08	7.47	0.00
150	8.93	15.00	5.51	3.75	0.00

## **Attachment 12**

Three schematics that address the proposed mill expansion at Bear Island are attached:


1. Overall water flow schematic reflecting the Bear Island mill expansion
2. Proposed upgrade of wastewater treatment facilities at Bear Island
3. Detail of proposed effluent oxygenation



**NOTE:** THE 1.0 MGD EFFLUENT FROM THE COUNTY WWTP CAN BE DISPOSED THROUGH ANY OF THE 3 ROUTES (OR COMBINATION THEREOF):

- A) TO DOSWELL ONE: 0.4 TO 1.0 MGD
- B) TO BIPCO: 0.2 TO 1.0 MGD
- C) TO THE RIVER THROUGH OUTFALLS 101-001: 0.0 TO 1.0 MGD  
IN CASE BOTH DOSWELL ONE AND BIPCO ARE NOT OPERATIONAL


PROJECT WATER WITHDRAWAL		
BEAR ISLAND PAPER COMPANY, L.P. ASHLAND, VIRGINIA		
SCALE NOT TO SCALE	APPROVED BY :	DRAWN BY: D.A.O.
DATE MAY 1994	DESIGNED BY :	REVISED
PROJECT NUMBER N100 01	DRAWING NO.	



**LEGEND**

- NEW LIQUID LINE
- NEW SLUDGE LINE
- EXISTING LIQUID LINE
- EXISTING SLUDGE LINE
- EXISTING FILTRATE LINE
- PROPOSED CONSTRUCTION
- PROPOSED EFFLUENT DIFFUSER

PROPOSED PLANT SCHEMATIC			
BEAR ISLAND PAPER COMPANY WASTEWATER TREATMENT PLANT			
DATE	REV	BY	CHK
DEC 28, 1989	1	W.P.	W.P.
AWARD INC.			
N 1015-01			



**FIGURE 2**  
**CONCEPTUAL LAYOUT OF OXYGENATION SYSTEM**  
NOT TO SCALE

### **Attachment 13**

Attachment 13 includes Attachments 13A and 13B. **Attachment 13A** develops the control equation for a mill expansion consisting only of a second, TMP paper line. As the mill now uses recycled paper, and therefore, the expansion would also use recycled paper (approximately 40% recycled newsprint), the control equation was reevaluated in regard to the larger water use associated with recycled paper. **Attachment 13B** discusses those revisions. As it turns out, the control equation remained the same, but the dissolved oxygen requirements changed.

**Attachment 13A**



## SECTION 7.0

### 1987 MODEL SIMULATIONS

Computer simulations were performed using various input conditions to define the capacity of the river to assimilate wastewater in compliance with the SWCB anti-degradation policy. All model simulations used the calibrated model presented in Section 5.0.

#### 7.1 General Approach

The modeling for the proposed mill expansion uses the same approach as previous models of the North Anna, except that this model uses the actual stream data to define model parameters and input conditions (Section 3.0). The model was used to evaluate discharge at the wasteload allocation defined in the York River Plan (690 lbs CBOD<sub>5</sub> per day). The allowable in-stream UCBOD of the wastewater was then used in the mass balance equation (of the wastewater-river mix) to define effluent limits, which can be expressed in terms of an effluent limitation control equation.

The modeling analysis and controls for the proposed mill expansion have been based on the ultimate and 5-day carbonaceous BOD. The 16th edition of Standard Methods for the Analysis of Water and Wastewater (Greenberg et al, 1985) has introduced a procedure for carbonaceous analysis as the method to differentiate CBOD<sub>5</sub> and nitrogenous oxygen demand.

For this modeling analysis, the South Anna River DO is given as a function of the temperature of the North Anna River, as developed from probability distributions of DO data collected by Hanover County since 1982. For example, for days when the North Anna temperature was 25°C, the 90th percentile DO in the South Anna River was 6.46 mg/l (Figure 6-5). The

measured 90th percentile South Anna DO values are presented as a function of North Anna temperature in Figure 7-1. (The DO is related to the North Anna temperature, since the North Anna temperature is the critical temperature for the modeling.) A relationship function which may be used to estimate the 90th percentile DO from a given North Anna temperature is

$$SA\ DO\ 90 = 12.97 - 0.4058 (NA\ TEMP) + 0.005734 (NA\ TEMP)^2 \quad (7-1)$$

where

$$\begin{aligned} SA\ DO\ 90 &= 90\text{th percentile South Anna DO (mg/l),} \\ NA\ TEMP &= \text{North Anna temperature (}^{\circ}\text{C).} \end{aligned}$$

From this function, the South Anna DO input condition may be obtained for any North Anna temperature.

A summary of model parameters and input conditions which have been used in the model simulations is presented in Table 7-1.

The model was used to determine the allowable CBOD<sub>5</sub> loadings and the required initial in-stream DO concentrations which would meet the SWCB anti-degradation policy. It was anticipated that supplemental effluent oxygenation would be required under certain conditions to attain the necessary in-stream DO mix.

## 7.2 Oxygenation of Effluent

Applying Henry's Law to a water column in the presence of an oxygen-containing gas, the equilibrium DO in the water is directly proportional to the partial pressure of oxygen in the overlying gas. This may be expressed as




FIGURE 7-1. THE 90TH PERCENTILE SOUTH ANNA DISSOLVED OXYGEN VS. NORTH ANNA TEMPERATURE.

TABLE 7-1  
MODEL PARAMETERS AND INPUT CONDITIONS

Model Parameters: Reaction Rates (20°C)

<u>Stream Reach</u>	<u>K<sub>1</sub>-20°C</u>	<u>K<sub>2</sub>-20°C</u>	<u>K<sub>N</sub>-20°C</u>	<u>SOD<sub>20°C</sub></u>
1	0.11	1.30	0.30	5.0
2	0.11	1.00	0.20	2.0
3	0.11	1.90	0.20	1.8
4	0.10	2.00	0.20	2.5
5	0.10	2.50	0.20	1.5

Model Input Conditions

Justification

TKN Doswell	10 mg/l	Section 6.4; Appendix J
Flow Doswell	4.5 MGD	Anticipated flow after expansion
Water Withdrawal	10.5 MGD	Section 6.3
Headwater CBOD <sub>u</sub>	4.2 mg/l	Average (Aug. 19, Oct. 13 & 15)
Headwater TKN	0.4 mg/l	Average (Aug. 19, Oct. 13 & 15)
Little River CBOD <sub>u</sub>	2.5 mg/l	Average (Oct. 13, Oct. 15)
Little River TKN	0.5 mg/l	Average (Oct. 13, Oct. 15)
South Anna CBOD <sub>u</sub>	3.6 mg/l	Average (Aug. 19, Oct. 13 & 15)
South Anna TKN	0.50 mg/l	Average (Aug. 19, Oct. 13 & 15)
South Anna DO	$12.97 - 0.4058 (\text{NA TEMP}) + 0.005734 (\text{NA TEMP})^2$ where NA temp = North Anna temperature (°C). (This is equation 7-1.)	

$$C_S = \frac{1}{H_e'} P_O$$

where

$C_S$  = saturated DO (mg/l),

$H_e'$  = Henry's Constant (atm-l/mg),

$P_O$  = partial pressure of oxygen (atm).

For example, for water at 20°C in the presence of atmospheric air,  $H_e' = 0.023$  atm-l/mg,  $P_O = 0.209$  atm, and  $C_S = 9.09$  mg/l.

At a given temperature, the equilibrium DO increases with increasing partial pressure of the oxygen in the overlying gas. This may be accomplished by (1) increasing the percentage of oxygen in the overlying gas, and/or (2) increasing the gage pressure of the oxygen-containing gas. For example, replacing atmospheric air ( $P_O = 0.209$  atm) with pure oxygen ( $P_O = 1.0$  atm) would result in a saturated DO of  $C_S = 43.47$  mg/l at 20°C and standard atmospheric pressure.

A number of papers pertaining to post-aeration are presented in Appendix M.

### 7.3 Deaeration Under Supersaturated Conditions

According to Thomann and Mueller (1987), the transfer of a chemical across the air-water interface at atmospheric pressure may be derived from

$$V \frac{dC}{dt} = k_1 A \left( \frac{C_g}{H_e} - fC \right) \quad (7-2)$$

where

$V$  = volume of water column ( $L^3$ ),

$C$  = chemical concentration in the water column ( $M/L^3$ ),

- $t$  = time (T),  
 $k_1$  = overall exchange coefficient (L/T),  
 $A$  = surface area ( $L^2$ ),  
 $C_g$  = chemical concentration in the overlying air ( $M/L^3$ ),  
 $H_e$  = Henry's constant,  
 $f$  = fraction of total chemical which is dissolved.

The equation shows that flux of a chemical may be from the air to the water (if  $C_g/H_e$  is greater than  $fC$ ) or from the water to the air (if  $fC$  is greater than  $C_g/H_e$ ). Application of the two-film theory results in the overall transfer efficiency being given as

$$\frac{1}{k_1} = \frac{1}{K_1} + \frac{1}{K_g H_e} \quad (7-3)$$

where

- $K_1$  = liquid film coefficient (L/T),  
 $K_g$  = gas film coefficient (L/T).

This theory may be applied to the transfer of oxygen across an air-water interface. In such case,  $C_g/H_e$  is the saturated DO concentration and  $f = 1$ . Since  $H_e$  is relatively high, the oxygen transfer rate is controlled by the liquid phase. The reaeration coefficient is given by

$$K_2 = \frac{k_1 A}{V} \quad (7-4)$$

where  $K_2$  is the atmospheric reaeration coefficient ( $T^{-1}$ ). Thus, for oxygen transfer, equation 7-2 may be written as

$$\frac{dC}{dt} = K_2 (C_s - C) \quad (7-5)$$

where  $C_s$  is the saturated DO concentration ( $M/L^3$ ). As with equation 7-2, the solution to equation 7-5 does not depend on the sign of the right-hand side. In terms of DO deficit, the solution is given by

$$D = D_0 \exp (-K_2 t) \quad (7-6)$$

where

$D = C_s - C = \text{oxygen deficit } (M/L^3),$

$D_0 = \text{initial oxygen deficit } (M/L^3)$

Since equation 7-2 is applicable to mass flow in either direction, it follows that equation 7-6 is appropriate for both reaeration and deaeration.

Similarly, equation 3-1 may be applied to supersaturated water, although there are some important assumptions involved. First, it must be assumed that the CBOD and NBOD decay processes are not affected by the existence of supersaturated conditions. Also, it must be assumed that SOD will not be affected by the additional oxygen. The use of equation 3-1 to evaluate supersaturated conditions is a common practice (Thomann, 1987).

A number of papers pertaining to post-aeration and deaeration under supersaturated conditions are presented in Appendix M.

#### 7.4 Model Simulations

The calibrated Streeter-Phelps model (as described in Section 5.0) indicates that a natural DO sag would exist in the North Anna River. Therefore, the upstream dissolved oxygen concentrations are adjusted to maintain the critical river DO at the sag location. The DO concentrations

required at NA-3.5 to maintain the critical background DO throughout the North Anna River are presented in Table 7-2 for each season. The modeling used to develop these required DO levels was based on critical temperatures, 7Q10 flow, and upstream CBOD and TKN values measured during the data acquisition phase of this study (Table 7-1).

#### 7.4.1 Model Simulations for Spring Season

For the months of April, May, and June, the critical temperature is 24°C and the critical background DO is 6.43 mg/l (Table 7-2). The model indicates that the minimum DO of 6.23 mg/l (6.43 mg/l minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD<sub>5</sub> mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 11.70 mg/l (Figure 7-2). For an upstream DO of 7.90 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 27 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge (5.4 MGD and 1,350 lbs CBOD<sub>5</sub> per day), a North Anna flow of 92.73 cfs, and an upstream DO of 7.90 mg/l; the minimum DO of 6.23 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation (Figure 7-3).

The model indicates that with the maximum combined discharge of the mill and the storage ponds (21.2 MGD and 5,300 lbs CBOD<sub>5</sub> per day), a North Anna flow of 218.73 cfs, and an upstream DO of 7.90



TABLE 7-2

## SUMMARY OF EFFLUENT OXYGENATION REQUIREMENTS AND ALLOWABLE DISCHARGES

Line		Spring	Summer	Fall	Winter
1	Critical Temperature (°C)	24	27	16	11
2	Critical DO (mg/l)	6.43	5.97	7.87	8.91
3	Initial DO to maintain critical DO throughout North Anna for no effluent at critical temperature and 7Q10 flow (mg/l) <sup>a</sup>	7.90	7.73	8.75	9.31
4	Minimum DO (mg/l) <sup>b</sup>	6.23	5.77	7.67	8.71
5	Initial in-stream DO required at 7Q10 flow and discharge of 690 lbs CBOD <sub>5</sub> per day to maintain minimum DO (Line 4) throughout the North Anna (mg/l) <sup>c</sup>	11.70	12.65	10.50	9.93
6	Effluent O <sub>2</sub> requirement at 7Q10 flow and discharge of 690 lbs per day, based on an upstream DO in the North Anna equal to Line 3 (mg/l) <sup>c</sup>	27	32	17	12
7	North Anna flow above which no O <sub>2</sub> is required (cfs): <sup>c</sup>				
7(a)	Discharge = 1,350 lbs CBOD <sub>5</sub> per day	92.73	97.73	86.73	79.73
7(b)	Discharge = 5,300 lbs CBOD <sub>5</sub> per day	218.73	222.73	195.73	175.73

<sup>a</sup> From modeling (Appendix I)

<sup>b</sup> Critical DO minus 0.2 mg/l.

<sup>c</sup> Sections 7.4.1 through 7.4.4.




FIGURE 7-2. DISSOLVED OXYGEN PROFILE FOR 7Q10 FLOW, TEMPERATURE OF 24°C INITIAL UCBOD OF 20.04 MG/L, AND INITIAL DISSOLVED OXYGEN OF 11.70 MG/L.




FIGURE 7-3. DISSOLVED OXYGEN PROFILE FOR FLOW OF 92.73 CFS, TEMPERATURE OF 24°C INITIAL UCBOD OF 14.48 MG/L, AND INITIAL DISSOLVED OXYGEN OF 7.90 MG/L.

mg/l; the minimum DO of 6.23 mg/l can be maintained without supplemental effluent oxygenation (Figure 7-4).

#### 7.4.2 Model Simulation For Summer Season

For the months of July, August, and September, the critical temperature is 27°C and the critical background DO is 5.97 mg/l (Table 7-2). The model indicates that the minimum DO of 5.77 mg/l (5.97 mg/l minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 12.65 mg/l. For an upstream DO of 7.73 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 32 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge, a North Anna flow of 97.7 cfs, and an upstream DO of 7.73 mg/l; the minimum DO of 5.77 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation.

The model indicates that with the maximum combined discharge of the mill and the storage ponds, a North Anna flow of 222.7 cfs, and an upstream DO of 7.73 mg/l; the minimum DO of 5.77 mg/l can be maintained without supplemental effluent oxygenation.

#### 7.4.3 Model Simulation For Fall Season

For the months of October, November, and December, the critical temperature is 16°C and the critical background DO is 7.87 mg/l (Table 7-2). The model indicates that the minimum DO of 7.67 mg/l (7.87 mg/l




FIGURE 7-4. DISSOLVED OXYGEN PROFILE FOR FLOW OF 218.7 CFS, TEMPERATURE OF 24°C INITIAL UCBOD OF 20.56 MG/L, AND INITIAL DISSOLVED OXYGEN OF 7.90 MG/L.

minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 10.50 mg/l. For an upstream DO of 8.75 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 17 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge, a North Anna flow of 86.7 cfs, and an upstream DO of 8.75 mg/l; the minimum DO of 7.67 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation.

The model indicates that with the maximum combined discharge of the mill and the storage ponds, a North Anna flow of 195.7 cfs, and an upstream DO of 8.75 mg/l; the minimum DO of 7.67 mg/l can be maintained without supplemental effluent oxygenation.

#### 7.4.4 Model Simulation For Winter Season

For the months of January, February, and March, the critical temperature is 11°C and the critical background DO is 8.91 mg/l (Table 7-2). At the critical temperature of 11°C, it was assumed that the NBOD deoxygenation coefficient ( $K_N$ ) is equal to zero. The model indicates that the minimum DO of 8.71 mg/l (8.91 mg/l minus 0.2 mg/l) can be maintained at 7Q10 flow in the North Anna River for an initial in-stream UCBOD mix of 20.04 mg/l (4.5 MGD and 690 lbs CBOD<sub>5</sub> per day), if the initial in-stream DO mix is 9.93 mg/l. For an upstream DO of 9.31 mg/l (Table 7-2), this requires effluent oxygenation to a concentration of 12 mg/l, based on a mass balance at the discharge point.

The model indicates that with the maximum mill discharge, a North Anna flow of 79.7 cfs, and an upstream DO of 9.31 mg/l; the minimum DO of 8.71 mg/l can be maintained in the North Anna River without supplemental effluent oxygenation.

The model indicates that for the maximum combined discharge of the mill and the storage ponds, a North Anna flow of 175.7 cfs, and an upstream DO of 9.31 mg/l, the minimum DO of 8.71 mg/l can be maintained without supplemental effluent oxygenation.

#### 7.4.5 Summary

The allowable CBOD<sub>5</sub> discharges and effluent oxygenation requirements are summarized in Table 7-3.

TABLE 7-3  
SUMMARY OF EFFLUENT OXYGENATION REQUIREMENTS

	Spring	Summer	Fall	Winter
Critical Temperature (°C)	24	27	16	11
Effluent O <sub>2</sub> requirement (mg/l)	27	32	17	12
North Anna flow above which no O <sub>2</sub> is required (cfs):				
a. Normal mill discharge	92.73	97.73	86.73	79.73
b. Normal mill discharge plus release from hydrograph-controlled release pond	218.73	222.73	195.73	175.73



## SECTION 8.0

### PROPOSED NPDES CRITERIA

The proposed NPDES criteria are based on maintaining the SWCB anti-degradation policy in the North Anna River. The results of the modeling indicate that the addition of oxygen to the effluent using pure oxygen is required when the river flow is less than 100 cfs and there is no discharge from the hydrograph-controlled release lagoon, and up to river flow of 235 cfs when there is a discharge from the hydrograph-controlled release lagoon. A cascade type aeration system, similar to the existing unit, will be used in all other discharge cases.

#### 8.1 Allowable CBOD

The current permit has a control equation which regulates the allowable effluent discharge in proportion to the river flow. At higher stream flows, the allowable discharge is increased. The control equation has been updated based on the results of the modeling (Table 7-2).

The control equation is based on solving a mass balance around the UCBOD mix in the river. The results of the modeling indicated a critical UCBOD mix in the river of 20.04 mg/l. The control equation will define allowable discharge CBOD<sub>5</sub> in lbs/day. The basic mass balance is:

$$\begin{aligned} \text{Input Load (North Anna - Withdrawal + Little River + Effluent)} = \\ \text{UCBOD mix in river} \end{aligned} \quad (8-1)$$

$$\frac{(Q_U - Q_W)(4.2) + (1.77)(2.5) + (6.98) S_0(8.34)}{Q_U - Q_W + 1.77 + 6.98} = 20.04$$

where

$Q_U$  = stream flow in North Anna River before withdrawal (cfs),

$Q_w$  = withdrawal from North Anna (cfs),

$S_o$  = UCBOD of effluent (mg/l).

The allowable CBOD<sub>5</sub> discharge in lb/day can be defined as

$$\text{Allowable CBOD}_5 = \frac{S_o}{F} (Q_D) \quad 8.34$$

where

$F$  = CBOD<sub>u</sub>/CBOD<sub>5</sub>,

$Q_D$  = effluent discharge flow (MGD).

This mass balance is solved for allowable CBOD<sub>5</sub>, based on monitoring of the North Anna River flow at the Doswell discharge gage. Hanover County would initiate continuous monitoring of the flow in the river, which could be accomplished by telemetry from a gaging station located immediately upstream (approximately within 100 ft) of the effluent discharge (Figure 2.2). A typical cross section of this gaging location during low-flow conditions is presented in Figure 8-1. A gaging station at this location would allow measurement of the actual flow in the river.

The proposed effluent criteria would be defined by the following control equation:

$$\text{Allowable CBOD}_5 = 18.97 Q_S + 204.77 \quad (8-2)$$

where  $Q_S$  = stream flow in North Anna River after withdrawal.

The derivation of this equation from the mass balance is presented in Table 8-1. This control equation would be valid under all conditions. This equation would apply for all temperatures up to a maximum CBOD<sub>5</sub> level of 5,300 lb/day. A graphical interpretation of equation 8-2 is presented in Figure 8-2.




FIGURE 8-1. TYPICAL CROSS SECTION OF PROPOSED GAGING STATION

TABLE 8-1  
DERIVATION OF CONTROL EQUATION

The mass balance of (In-stream CBOD<sub>u</sub> Mix = Input Flow) is solved:

$$\text{In-stream UCBOD Mix} = \frac{(Q_s)(\text{CBOD}_{u1}) + (Q_{LR})(\text{CBOD}_{u2}) + Q_D(S_0)}{Q_s + Q_{LR} + Q_D} \quad (1)$$

where

$$\text{Input Load} = (\text{North Anna} - \text{withdrawal} + \text{Little River} + \text{Effluent}) / (\text{Total Flow})$$

$$\text{In-stream UCBOD Mix} = 20.04 \text{ (from Section 7.4 model simulations)}$$

$$Q_s = \text{stream flow in North Anna after withdrawal (cfs)}$$

$$\text{CBOD}_{u1} = \text{ultimate CBOD in North Anna} = 4.2 \text{ mg/l} \\ \text{(from Table 7-1)}$$

$$\text{CBOD}_{u2} = \text{ultimate CBOD in Little River} = 2.5 \text{ mg/l} \\ \text{(from Table 7-1)}$$

$$Q_{LR} = 7Q_{10} \text{ stream flow in the Little River (cfs)}$$

$$Q_D = \text{effluent discharge flow} = 6.98 \text{ cfs}$$

$$S_0 = \text{effluent ultimate CBOD}$$

$$F = \text{CBOD}_u / \text{CBOD}_5 = 4.5 \text{ (from Table 4-5)}$$

$$\text{Conversions: } \text{mg/l} \times \text{MGD} \times 8.34 = \text{lbs/day}$$

$$\text{MGD} \times 1.547 = \text{cfs}$$

Solving:

$$20.04 = \frac{(Q_s)(4.2) + 1.77(2.5) + 6.98(S_0)}{Q_s + 1.77 + 6.98}$$

$$20.04 = \frac{4.2(Q_s) + 4.425 + 6.98(S_0)}{Q_s + 8.75}$$

---

(continued)

TABLE 8-1 (continued)  
DERIVATION OF CONTROL EQUATION

---

In terms of  $S_0$ :

$$S_0 = \frac{1}{6.98} (20.04(Q_s + 8.75) - 4.2 Q_s - 4.425) \quad (2)$$

The allowable 5-day CBOD, in terms of lb/day BOD<sub>5</sub>:

$$\begin{aligned} \text{Allowable BOD}_5 &= \frac{S_0}{F} (8.34) Q_D \\ &= \frac{S_0}{4.5} (8.34) \frac{6.98}{1.547} \end{aligned}$$

This can be substituted into equation 2 and results in:

$$\text{Allowable CBOD}_5 = \frac{8.34 (6.98)}{4.5 (6.98)(1.547)} (20.04 (Q_s + 8.75) - 4.2 Q_s - 4.425) \quad (3)$$

This equation can be further simplified to:

$$\text{Allowable CBOD}_5 = 18.97 Q_s + 204.77$$

These controls will comply with the SWCB anti-degradation policy and provide for the long-term water quality in the North Anna River.

---




FIGURE 8-2. PROPOSED EFFLUENT CRITERIA

## 8.2 Oxygen Addition

The result of the modeling indicate that oxygenation of the effluent using pure oxygen will be required under low flow conditions to maintain water quality in the North Anna River. The required effluent dissolved oxygen concentrations are presented in Table 8-2. This is based on the results of the modeling presented in Table 7-2. Table 8-3 presents the North Anna River flow conditions for the various seasons where oxygen addition will not be required.

The mill uses a hydrograph-controlled release pond to store effluent under low flow conditions. With this type of storage, there are three basic discharge scenarios which can occur. These are:

1. Under normal conditions, the mill will discharge an average flow of 4.5 MGD and a maximum flow of 5.4 MGD.
2. If there are low river flow conditions, a portion of the mill effluent flow will be diverted to the hydrograph-controlled release pond.
3. If the river flow increases, then the waste stored in the hydrograph-controlled release pond will be discharged based on equation 8-2.

When there is no waste stored in the hydrograph-controlled release lagoon, the maximum discharge will be 5.4 MGD at 30 mg/l CBOD<sub>5</sub> (1,350 pounds CBOD<sub>5</sub> per day); if there is waste stored in the hydrograph-controlled-release pond, a discharge of up to 5,300 pounds CBOD<sub>5</sub> per day can occur, based on the river flow (equation 8-2).

TABLE 8-2  
REQUIRED EFFLUENT DISSOLVED OXYGEN LEVEL

Season	Effluent Dissolved Oxygen <sup>a</sup> (mg/l)
Summer (July, August, September)	32
Fall (October, November, December)	17
Winter (January, February, March)	12
Spring (April, May, June)	27

<sup>a</sup> The effluent dissolved oxygen concentration is calculated through a mass balance where

DO inputs = DO mix in river

North Anna DO + Little River DO + effluent DO = DO mix in river

$$\frac{Q_s DO_A + 1.77 DO_B + 1.547 Q_D DO_D}{Q_s + 1.77 + 1.547 Q_D} = \text{DO mix in River}$$

where

DO mix in river - from Table 7-2 (mg/l)

Q<sub>s</sub> = stream flow in North Anna after withdrawal (cfs)

DO<sub>A</sub> = North Anna background DO, based on Table 7-2.

DO<sub>B</sub> = Little River DO (mg/l) = DO<sub>A</sub>

Q<sub>D</sub> = effluent discharge flow (MGD)

DO<sub>D</sub> = effluent DO (mg/l)

(continued)



TABLE 8-2 (continued)  
REQUIRED EFFLUENT DISSOLVED OXYGEN LEVEL

---

For example:

at 27°C       $DO_A = 7.73 \text{ mg/l}$  (from Table 7-2)  
                   $DO_B = 7.73 \text{ mg/l}$   
                   $Q_D = 4.5 \text{ MGD}$   
                   $Q_S = 41.91 - 16.28$  (7Q10 conditions)  
                  = 25.63 cfs

$DO_{\text{mix in river}} = 12.65 \text{ mg/l}$  (from Table 7-2)

$$DO_D = \frac{(DO_{\text{mix in river}})(Q_S + 1.77 + 1.547 Q_D) - Q_S DO_A - 1.77 DO_B}{1.547 Q_D}$$

$$= \frac{((12.65)(25.63) + 1.77 + 6.96)}{(1.547)(4.5)} - \frac{(25.63)(7.73)}{(1.547)(4.5)} - \frac{(1.77)(7.73)}{(1.547)(4.5)}$$

$$= 32 \text{ mg/l}$$


---

TABLE 8-3

SUMMARY OF RIVER FLOWS WHERE PURE OXYGEN  
ADDITION IS NOT REQUIRED

Season	Minimum River Flow (cfs)	
	Mill Waste Discharge (5.4 MGD Max.)	Mill Waste Plus Hydrograph- Controlled Pond Discharge (21.2 MGD Max.)
Summer (July, August, September)	100	231
Fall (October, November, December)	89	202
Winter (January, February, March)	81	181
Spring (April, May, June)	95	224

For simplicity, it is proposed to operate on a two-season basis, summer and winter, with the summer season being April through September, and the winter season being October through March. For the summer season, the effluent dissolved concentration will be 32 mg/l, and during the winter season it will be 17 mg/l. The oxygen addition will be required under all conditions when the river flow is less than 100 cfs. Oxygen addition will not be required at river flows over 100 cfs, unless there is the need to discharge from the hydrograph-controlled release pond. If there is any discharge from the hydrograph-controlled release pond, oxygen addition will be required up to a river flow of 235 cfs.

A summary of the proposed regulations is presented in Table 8-4. These controls will comply with the State Water Control Board anti-degradation policy and provide for the long-term water quality of the North Anna River.

TABLE 8-4  
PROPOSED DISCHARGE CRITERIA

Season	Effluent DO Using Pure Oxygen Post-Oxygenation (mg/l)	Minimum River Flow to Switch to Cascade Aeration (cfs)	
		Mill Waste Discharge (5.4 MGD Max.)	Mill Waste Plus Hydrograph- Controlled Pond Discharge
Summer (April - September)	32	100	235
Winter (October - March)	17	100	235

**Attachment 13B**

(Begin at Item 12.)

- Item 9: Figure 2 has been modified per your comments, with the future 1 MGD at the Doswell STP deleted, and with the oxygen supply valve position changed to the "closed" position, to reflect the correct operating scheme of the treatment system; and is included as Attachment 5.
- Item 10: Item 10 - The daily flow rate is utilized in the equation and the daily flow rate is used to set the oxygen addition. The sentence in question should read "A set of controls, based on daily discharge flow, allows supplemental effluent oxygenation to be suspended when the river flow exceeds 100 cfs, when the existing cascade aeration system can be used instead."
- Item 11: Item 11 - The note on Table 4 and Table 5 should be 6.5 mg/L and should read "NOTE: When switching to cascade aeration, effluent DO criteria is 6.5 mg/L". The narrative on Page 15 should read "At these minimum flow rates, the use of cascade aeration systems to oxygenate the effluent to a dissolved oxygen concentration of 6.5 mg/L is sufficient to maintain the required minimum DO conditions in the North Anna River."
- Item 12: You are correct in noting that the Effluent Oxygenation Controls discussed on Page 15, in Table 5, in Table 6, and on Page 19 include an additional 1.0 MGD from the Doswell STP, even though, as is also stated in the Engineering Report, that plant expansion will not occur during the lifetime of the VPDES permit. One reason is

that the design of the oxygenation system should take into account possible future expansion of Doswell, as it is anticipated that the oxygenation system will have an operating life longer than the five year term of this permit. The effect of operating under these conditions can best be observed by a comparison of the Effluent Oxygenation Controls with the Doswell expansion to the Effluent Oxygenation Controls without the Doswell expansion. Tables 5 and 6 from the Engineering Report, attached here for your convenience as Attachment 6, outlines the effluent oxygenation controls based on an average flow of 6.75 MGD and a maximum flow of 7.34 MGD (i.e., with the Doswell expansion). Tables 5a and 6a, also included in Attachment 6, outline the effluent oxygenation controls based on an average flow of 5.75 MGD and a maximum flow of 6.75 MGD (i.e., without the Doswell expansion).

4.311

Comparing the two operating schemes, the two operating schemes differ in the effluent oxygen required, and in the North Anna flow above which no supplemental oxygenation is required. The Doswell expansion causes the effluent oxygen requirement at 7Q10 flow to decrease slightly, from 29 mg/L to 27.19 mg/L in the summer and from 16 mg/L to 15.4 mg/L in the fall. Because the effluent DO concentrations in either case

is lower than the effluent DO concentration of 32 mg/L and 17 mg/L originally listed in the original VPDES permit application, the original permit DO concentrations of 32 mg/L and 17 mg/L were maintained originally to avoid additional permit modifications. The correct limits for the new permit should be 29 mg/L summer and 16 mg/L winter. The higher effluent DO concentrations result in a higher in-stream DO concentration, which in turn results in a higher minimum DO concentration in the river, thus ensuring compliance with the State Water Control Board's antidegradation policy requiring a DO sag of no more than 0.2 mg/L below the critical DO in the North Anna and Pamunkey Rivers.

The Doswell expansion causes the minimum N. Anna flow above which no oxygenation is required to increase, from 111 to 121 cfs in summer and from 97 to 105 cfs in the fall. If BIPCO chooses to operate under the oxygenation control scheme outlined in Table 5 while the Doswell expansion does not occur, then more oxygen will be added to the North Anna River than estimated to be necessary to maintain the minimum DO concentration throughout the North Anna, which again will help ensure compliance with the State Water Control Board's antidegradation policy. If desired by the SWCB, the



effluent oxygenation controls included in Table 5a can be utilized until the Doswell expansion occurs.

Several other items in this letter address the derivation of some of the parameters in Table 6. To avoid confusion, any questions in these areas will be answered only for the 6.75/7.34 MGD case presented in the Engineering Report. If the SWCB desires, comparable documentation for the 5.75/6.34 MGD case can be presented.

Item 13: The omitted footnote c in Table 6 states "River sections 7.4.1 through 7.4.4 ", which covers the sections of the North Anna that reflect the minimum DO conditions that Lines 5 and 7 in Table 6 are based on. Note that this footnote was included in the tables included in Attachment 6. These are the river sections included in Appendices B and C of the Engineering Report. The source of the information in Lines 5 and 7 is from the water quality model, via iterative runs to determine first the in-stream DO to maintain the minimum DO in the river (Line 5 of Table 6), then the North Anna flow above which no oxygenation is required (Line 7 of Table 6). Copies of the computer printouts showing the derivation of these values are attached as Attachment 7.

**Attachment 14**

Effluent Limitation Development for the Bear Island Expansion

## Mixing Zone Predictions for

## Doswell WWTP expansion

Effluent Flow = 6.34 MGD  
Stream 7Q10 = 29 MGD  
Stream 30Q10 = 32 MGD  
Stream 1Q10 = 27 MGD  
Stream slope = 0.00038 ft/ft  
Stream width = 75 ft  
Bottom scale = 2  
Channel scale = 1

---

### Mixing Zone Predictions @ 7Q10

Depth = 1.5445 ft  
Length = 5004.32 ft  
Velocity = .4722 ft/sec  
Residence Time = .1226 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 7Q10 may be used.

---

### Mixing Zone Predictions @ 30Q10

Depth = 1.6232 ft  
Length = 4794.79 ft  
Velocity = .4875 ft/sec  
Residence Time = .1138 days

#### Recommendation:

A complete mix assumption is appropriate for this situation and the entire 30Q10 may be used.

---

### Mixing Zone Predictions @ 1Q10

Depth = 1.4907 ft  
Length = 5159.18 ft  
Velocity = .4616 ft/sec  
Residence Time = 3.1045 hours

#### Recommendation:

A complete mix assumption is appropriate for this situation providing no more than 32.21% of the 1Q10 is used.

---

# FRESHWATER WATER QUALITY CRITERIA / WASTELOAD ALLOCATION ANALYSIS

Facility Name: Doswell WWTP expansion  
Receiving Stream: North Anna River

Permit No.: VA0029521

Version: OWP Guidance Memo 00-2011 (8/24/00)

Stream Information		Stream Flows		Mixing Information		Effluent Information	
Mean Hardness (as CaCO <sub>3</sub> ) =	19.4 mg/L	1Q10 (Annual) =	27 MGD	Annual - 1Q10 Mix =	32.21 %	Mean Hardness (as CaCO <sub>3</sub> ) =	582 mg/L
90% Temperature (Annual) =	26.2 deg C	7Q10 (Annual) =	29 MGD	- 7Q10 Mix =	100 %	90% Temp (Annual) =	30.6 deg C
90% Temperature (Wet season) =	deg C	3Q10 (Annual) =	32 MGD	- 3Q10 Mix =	100 %	90% Temp (Wet season) =	deg C
90% Maximum pH =	7.4 SU	1Q10 (Wet season) =	0 MGD	Wet Season - 1Q10 Mix =	%	90% Maximum pH =	7.9 SU
10% Maximum pH =	6.4 SU	3Q10 (Wet season) =	0 MGD	- 3Q10 Mix =	%	10% Maximum pH =	7.7 SU
Tier Designation (1 or 2) =	1	3Q05 =	33 MGD			Discharge Flow =	6.34 MGD
Public Water Supply (PWS) Y/N? =	n	Harmonic Mean =	81 MGD				
Trout Present Y/N? =	n	Annual Average =	MGD				
Early Life Stages Present Y/N? =	y						

Parameter (ug/l unless noted)	Background			Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
	Conc.	Acute	Chronic	HH (PWS)	HH	HH	Acute	Chronic	HH (PWS)	Acute	Chronic	HH (PWS)	Acute	Chronic	HH (PWS)	Acute	Chronic	HH
Acenaphthene	0	--	--	na	2.7E+03	na	--	--	na	1.7E+04	--	--	--	--	na	1.7E+04	--	na
Acrolein	0	--	--	na	7.9E+02	na	--	--	na	4.8E+03	--	--	--	--	na	4.8E+03	--	na
Acrylonitrile <sup>c</sup>	0	--	--	na	6.8E+00	na	--	--	na	9.1E+01	--	--	--	--	na	9.1E+01	--	na
Aldrin <sup>c</sup>	0	3.0E+00	--	na	1.4E-03	na	7.1E+00	--	na	1.9E-02	--	--	--	--	na	7.1E+00	--	na
Ammonia-N (mg/l) (Yearly)	0	1.85E+01	2.04E+00	na	--	na	4.4E+01	1.2E+01	na	--	--	--	--	4.4E+01	1.2E+01	na	--	na
Ammonia-N (mg/l) (High Flow)	0	1.01E+01	2.80E+00	na	--	na	1.0E+01	2.8E+00	na	--	--	--	--	1.0E+01	2.8E+00	na	--	na
Anthracene	0	--	--	na	1.1E+05	na	--	--	na	6.8E+05	--	--	--	--	na	6.8E+05	--	na
Antimony	0	--	--	na	4.3E+03	na	--	--	na	2.7E+04	--	--	--	--	na	2.7E+04	--	na
Arsenic	0	3.4E+02	1.5E+02	na	--	na	8.1E+02	8.4E+02	na	--	--	--	--	8.1E+02	8.4E+02	na	--	na
Barium	0	--	--	na	--	na	--	--	na	--	--	--	--	--	na	--	--	na
Benzene <sup>c</sup>	0	--	--	na	7.1E+02	na	--	--	na	9.8E+03	--	--	--	--	na	9.8E+03	--	na
Benzidine <sup>c</sup>	0	--	--	na	5.4E-03	na	--	--	na	7.4E-02	--	--	--	--	na	7.4E-02	--	na
Benzo (a) anthracene <sup>c</sup>	0	--	--	na	4.9E-01	na	--	--	na	6.8E+00	--	--	--	--	na	6.8E+00	--	na
Benzo (b) fluoranthene <sup>c</sup>	0	--	--	na	4.9E-01	na	--	--	na	6.8E+00	--	--	--	--	na	6.8E+00	--	na
Benzo (k) fluoranthene <sup>c</sup>	0	--	--	na	4.9E-01	na	--	--	na	6.8E+00	--	--	--	--	na	6.8E+00	--	na
Benzo (a) pyrene <sup>c</sup>	0	--	--	na	1.4E+01	na	--	--	na	8.7E+01	--	--	--	--	na	8.7E+01	--	na
Bis(2-Chloroethyl) Ether	0	--	--	na	1.7E+05	na	--	--	na	1.1E+06	--	--	--	--	na	1.1E+06	--	na
Bis(2-Chloroisopropyl) Ether	0	--	--	na	3.8E+03	na	--	--	na	5.0E+04	--	--	--	--	na	5.0E+04	--	na
Bromofom <sup>c</sup>	0	--	--	na	5.2E+03	na	--	--	na	3.2E+04	--	--	--	--	na	3.2E+04	--	na
Butylbenzylphthalate	0	1.1E+01	1.3E+00	na	--	na	2.5E+01	7.1E+00	na	--	--	--	--	2.5E+01	7.1E+00	na	--	na
Cadmium	0	--	--	na	4.4E+01	na	--	--	na	6.1E+02	--	--	--	--	na	6.1E+02	--	na
Carbon Tetrachloride <sup>c</sup>	0	2.4E+00	4.3E-03	na	2.3E-02	na	5.7E+00	2.4E-02	na	3.0E-01	--	--	--	5.7E+00	2.4E-02	na	--	na
Chlordane <sup>c</sup>	0	8.6E+05	2.3E+05	na	--	na	2.0E+06	1.3E+06	na	--	--	--	--	2.0E+06	1.3E+06	na	--	na
Chloride	0	1.9E+01	1.1E+01	na	--	na	4.5E+01	6.1E+01	na	--	--	--	--	4.5E+01	6.1E+01	na	--	na
TRC	0	--	--	na	2.1E+04	na	--	--	na	1.3E+05	--	--	--	--	na	1.3E+05	--	na
Chlorobenzene	0	--	--	na	--	na	--	--	na	--	--	--	--	--	na	--	--	na

Parameter (µg/l unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Chlorodibromomethane <sup>c</sup>	0	--	--	na	3.4E+02	--	--	na	4.7E+03	--	--	--	--	--	--	na
Chloroform <sup>c</sup>	0	--	--	na	2.9E+04	--	--	na	4.0E+05	--	--	--	--	--	--	na
2-Chloronaphthalene	0	--	--	na	4.3E+03	--	--	na	2.7E+04	--	--	--	--	--	--	na
2-Chlorophenol	0	--	--	na	4.0E+02	--	--	na	2.5E+03	--	--	--	--	--	--	na
Chlorpyrifos	0	8.3E-02	4.1E-02	na	--	2.0E-01	2.3E-01	na	--	--	--	--	--	2.0E-01	2.3E-01	na
Chromium III	0	1.2E+03	8.4E+01	na	--	2.8E+03	4.7E+02	na	--	--	--	--	--	2.8E+03	4.7E+02	na
Chromium VI	0	1.6E+01	1.1E+01	na	--	3.9E+01	6.1E+01	na	--	--	--	--	--	3.9E+01	6.1E+01	na
Chromium, Total	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Chrysene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Copper	0	3.2E+01	1.0E+01	na	--	7.5E+01	5.7E+01	na	--	--	--	--	--	7.5E+01	5.7E+01	na
Cyanide	0	2.2E+01	5.2E+00	na	2.2E+05	5.2E+01	2.9E+01	na	1.3E+06	--	--	--	--	5.2E+01	2.9E+01	na
DDD <sup>c</sup>	0	--	--	na	8.4E-03	--	--	na	1.2E-01	--	--	--	--	--	--	na
DDE <sup>c</sup>	0	--	--	na	5.9E-03	--	--	na	8.1E-02	--	--	--	--	--	--	na
DDT <sup>c</sup>	0	1.1E+00	1.0E-03	na	5.9E-03	2.6E+00	5.6E-03	na	8.1E-02	--	--	--	--	2.6E+00	5.6E-03	na
Demeton	0	--	1.0E-01	na	--	--	5.6E-01	na	--	--	--	--	--	--	5.6E-01	na
Dibenz(a,h)anthracene <sup>c</sup>	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Di-butyl phthalate	0	--	--	na	1.2E+04	--	--	na	7.4E+04	--	--	--	--	--	--	na
Dichloromethane	0	--	--	na	1.6E+04	--	--	na	2.2E+05	--	--	--	--	--	--	na
(Methylene Chloride) <sup>c</sup>	0	--	--	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
1,2-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.8E+04	--	--	--	--	--	--	na
1,3-Dichlorobenzene	0	--	--	na	2.6E+03	--	--	na	1.8E+04	--	--	--	--	--	--	na
1,4-Dichlorobenzene	0	--	--	na	2.7E-01	--	--	na	1.1E+01	--	--	--	--	--	--	na
3,3-Dichlorobenzidine <sup>c</sup>	0	--	--	na	4.6E+02	--	--	na	6.3E+03	--	--	--	--	--	--	na
Dichlorobromomethane <sup>c</sup>	0	--	--	na	9.9E+02	--	--	na	1.4E+04	--	--	--	--	--	--	na
1,2-Dichloroethane <sup>c</sup>	0	--	--	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
1,1-Dichloroethylene	0	--	--	na	1.4E+05	--	--	na	8.7E+05	--	--	--	--	--	--	na
1,2-trans-dichloroethylene	0	--	--	na	7.9E+02	--	--	na	4.9E+03	--	--	--	--	--	--	na
2,4-Dichlorophenol	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
2,4-Dichlorophenoxy	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
acetic acid (2,4-D)	0	--	--	na	3.9E+02	--	--	na	5.4E+03	--	--	--	--	--	--	na
1,3-Dichloropropene	0	--	--	na	1.7E+03	--	--	na	1.1E+04	--	--	--	--	--	--	na
Dieldrin <sup>c</sup>	0	2.4E-01	5.6E-02	na	1.4E-03	5.7E-01	3.1E-01	na	1.9E-02	--	--	--	--	5.7E-01	3.1E-01	na
Diethyl Phthalate	0	--	--	na	1.2E+05	--	--	na	7.4E+05	--	--	--	--	--	--	na
Di-2-Ethylhexyl Phthalate <sup>c</sup>	0	--	--	na	5.9E+01	--	--	na	8.1E+02	--	--	--	--	--	--	na
2,4-Dimethoxyphenol	0	--	--	na	2.3E+03	--	--	na	1.4E+04	--	--	--	--	--	--	na
Dimethyl Phthalate	0	--	--	na	2.9E+06	--	--	na	1.8E+07	--	--	--	--	--	--	na
Di-n-Butyl Phthalate	0	--	--	na	1.2E+04	--	--	na	7.4E+04	--	--	--	--	--	--	na
2,4-Dinitrophenol	0	--	--	na	1.4E+04	--	--	na	8.7E+04	--	--	--	--	--	--	na
2-Methyl-4,6-Dinitrophenol	0	--	--	na	7.6E+02	--	--	na	4.7E+03	--	--	--	--	--	--	na
2,4-Dinitrotoluene <sup>c</sup>	0	--	--	na	9.1E+01	--	--	na	1.3E+03	--	--	--	--	--	--	na
Dioxin (2,3,7,8-tetrachlorodibenzo-p-dioxin) (ppq)	0	--	--	na	1.2E+06	--	--	na	na	--	--	--	--	--	--	na
1,2-Diphenylhydrazine <sup>c</sup>	0	--	--	na	5.4E+00	--	--	na	7.4E+01	--	--	--	--	--	--	na
Alpha-Endosulfan	0	2.2E-01	5.6E-02	na	2.4E+02	5.2E-01	3.1E-01	na	1.5E+03	--	--	--	--	5.2E-01	3.1E-01	na
Beta-Endosulfan	0	2.2E-01	5.6E-02	na	2.4E+02	5.2E-01	3.1E-01	na	1.5E+03	--	--	--	--	5.2E-01	3.1E-01	na
Endosulfan Sulfate	0	--	--	na	2.4E+02	--	--	na	1.5E+03	--	--	--	--	--	--	na
Endrin	0	8.6E-02	3.6E-02	na	8.1E-01	2.0E-01	2.0E-01	na	5.0E+00	--	--	--	--	2.0E-01	2.0E-01	na
Endrin Aldehyde	0	--	--	na	8.1E-01	--	--	na	5.0E+00	--	--	--	--	--	--	na

Parameter (ug/L unless noted)	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)	HH	Acute	Chronic	HH (PWS)
Ethylbenzene	0	--	--	na	2.9E+04	--	--	na	1.8E+05	--	--	--	--	--	--	na
Fluoranthene	0	--	--	na	3.7E+02	--	--	na	2.3E+03	--	--	--	--	--	--	na
Fluorene	0	--	--	na	1.4E+04	--	--	na	8.7E+04	--	--	--	--	--	--	na
Foaming Agents	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Guthion	0	--	1.0E-02	na	--	--	5.6E-02	na	--	--	--	--	--	5.6E-02	--	na
Heptachlor <sup>c</sup>	0	5.2E-01	3.8E-03	na	2.1E-03	1.2E+00	2.1E-02	na	2.9E-02	--	--	--	--	1.2E+00	2.1E-02	na
Heptachlor Epoxide <sup>c</sup>	0	5.2E-01	3.8E-03	na	1.1E-03	1.2E+00	2.1E-02	na	1.5E-02	--	--	--	--	1.2E+00	2.1E-02	na
Hexachlorobenzene <sup>c</sup>	0	--	--	na	7.7E-03	--	--	na	1.1E-01	--	--	--	--	--	--	na
Hexachlorobutadiene <sup>c</sup>	0	--	--	na	5.0E+02	--	--	na	6.9E+03	--	--	--	--	--	--	na
Hexachlorocyclohexane	0	--	--	na	1.3E-01	--	--	na	1.8E+00	--	--	--	--	--	--	na
Alpha-BHC <sup>c</sup>	0	--	--	na	4.6E-01	--	--	na	6.3E+00	--	--	--	--	--	--	na
Beta-BHC <sup>c</sup>	0	--	--	na	6.3E-01	2.3E+00	--	na	8.7E+00	--	--	--	--	2.3E+00	--	na
Gamma-BHC <sup>c</sup> (Lindane)	0	9.5E-01	na	na	1.7E+04	--	--	na	1.1E+05	--	--	--	--	--	--	na
Hexachlorocyclopentadiene	0	--	--	na	8.9E+01	--	--	na	1.2E+03	--	--	--	--	--	--	na
Hexachloroethane <sup>c</sup>	0	--	2.0E+00	na	--	--	1.1E+01	na	--	--	--	--	--	--	1.1E+01	na
Hydrogen Sulfide	0	--	--	na	4.9E-01	--	--	na	6.8E+00	--	--	--	--	--	--	na
Indeno (1,2,3-cd) pyrene <sup>c</sup>	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Iron	0	--	--	na	2.6E+04	--	--	na	3.8E+05	--	--	--	--	--	--	na
Isophorone <sup>c</sup>	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Kepon	0	--	0.0E+00	na	--	--	0.0E+00	na	--	--	--	--	--	0.0E+00	--	na
Lead	0	3.8E+02	1.8E+01	na	--	9.0E-02	9.2E+01	na	--	--	--	--	--	9.0E-02	9.2E+01	na
Malathion	0	--	1.0E-01	na	--	--	5.8E-01	na	--	--	--	--	--	--	5.8E-01	na
Manganese	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Mercury	0	1.4E+00	7.7E-01	na	5.1E-02	3.3E+00	4.3E+00	na	3.2E-01	--	--	--	--	3.3E+00	4.3E+00	na
Methyl Bromide	0	--	--	na	4.0E+03	--	--	na	2.5E+04	--	--	--	--	--	--	na
Methoxychlor	0	--	3.0E-02	na	--	--	1.7E-01	na	--	--	--	--	--	--	1.7E-01	na
Mirex	0	--	0.0E+00	na	--	--	0.0E+00	na	--	--	--	--	--	--	0.0E+00	na
Monochlorobenzene	0	3.9E+02	2.3E+01	na	2.1E+04	--	--	na	1.3E+05	--	--	--	--	--	--	na
Nickel	0	--	--	na	4.6E+03	9.3E+02	1.3E+02	na	2.9E+04	--	--	--	--	9.3E+02	1.3E+02	na
Nitrate (as N)	0	--	--	na	--	--	--	na	--	--	--	--	--	--	--	na
Nitrobenzene	0	--	--	na	1.9E+03	--	--	na	1.2E+04	--	--	--	--	--	--	na
N-Nitrosodimethylamine <sup>c</sup>	0	--	--	na	8.1E+01	--	--	na	1.1E+03	--	--	--	--	--	--	na
N-Nitrosodiphenylamine <sup>c</sup>	0	--	--	na	1.6E+02	--	--	na	2.2E+03	--	--	--	--	--	--	na
N-Nitrosodi-n-propylamine <sup>c</sup>	0	--	--	na	1.4E+01	--	--	na	1.9E+02	--	--	--	--	--	--	na
Parathion	0	6.5E-02	1.3E-02	na	--	1.5E-01	7.2E-02	na	--	--	--	--	--	1.5E-01	7.2E-02	na
PCB-1016	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1221	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1232	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1242	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1248	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1254	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB-1260	0	--	1.4E-02	na	--	--	7.8E-02	na	--	--	--	--	--	--	7.8E-02	na
PCB Total <sup>c</sup>	0	--	--	na	1.7E+03	--	--	na	2.3E-02	--	--	--	--	--	--	na

Parameter (ug/l unless noted) <sup>c</sup>	Background Conc.	Water Quality Criteria			Wasteload Allocations			Antidegradation Baseline			Antidegradation Allocations			Most Limiting Allocations		
		Acute	Chronic	HH (PWS)	Acute	Chronic	HH (PWS)	Acute	Chronic	HH (PWS)	Acute	Chronic	HH (PWS)	Acute	Chronic	HH (PWS)
Pentachlorophenol <sup>c</sup>	0	6.0E+00	4.0E+00	na	8.2E+01	na	1.1E+03	--	--	--	--	--	--	1.4E+01	2.2E+01	1.1E+03
Phenol	0	--	--	na	4.6E+06	--	2.9E+07	--	--	--	--	--	--	--	--	2.9E+07
Pyrene	0	--	--	na	1.1E+04	--	6.8E+04	--	--	--	--	--	--	--	--	6.8E+04
Radionuclides (pCi/l except Beta/Photon)	0	--	--	na	--	--	--	--	--	--	--	--	--	--	--	--
Gross Alpha Activity Beta and Photon Activity (mrem/yr)	0	--	--	na	1.5E+01	--	9.3E+01	--	--	--	--	--	--	--	--	9.3E+01
Strontium-90	0	--	--	na	4.0E+00	--	2.5E+01	--	--	--	--	--	--	--	--	2.5E+01
Tritium	0	--	--	na	8.0E+00	--	5.0E+01	--	--	--	--	--	--	--	--	5.0E+01
Selenium	0	2.0E+01	5.0E+00	na	2.0E+04	--	1.2E+05	--	--	--	--	--	--	--	--	1.2E+05
Silver	0	1.6E+01	--	na	1.1E+04	--	6.8E+04	--	--	--	--	--	--	4.7E+01	2.8E+01	6.8E+04
Sulfate	0	--	--	na	--	--	na	--	--	--	--	--	--	3.9E+01	--	--
1,1,2,2-Tetrachloroethane <sup>c</sup>	0	--	--	na	1.1E+02	--	1.5E+03	--	--	--	--	--	--	--	--	1.5E+03
Tetrachloroethylene <sup>c</sup>	0	--	--	na	8.9E+01	--	1.2E+03	--	--	--	--	--	--	--	--	1.2E+03
Thallium	0	--	--	na	6.3E+00	--	3.9E+01	--	--	--	--	--	--	--	--	3.9E+01
Toluene	0	--	--	na	2.0E+05	--	1.2E+06	--	--	--	--	--	--	--	--	1.2E+06
Total dissolved solids	0	--	--	na	--	--	na	--	--	--	--	--	--	--	--	--
Toxaphene <sup>c</sup>	0	7.3E-01	2.0E-04	na	7.5E-03	na	1.0E-01	--	--	--	--	--	--	1.7E+00	1.1E-03	1.0E-01
Tributyltin	0	4.6E-01	6.3E-02	na	--	--	na	--	--	--	--	--	--	1.1E+00	3.5E-01	na
1,2,4-Trichlorobenzene	0	--	--	na	9.4E+02	--	5.8E+03	--	--	--	--	--	--	--	--	5.8E+03
1,1,2-Trichloroethane <sup>c</sup>	0	--	--	na	4.2E+02	--	na	--	--	--	--	--	--	--	--	5.8E+03
Trichloroethylene <sup>c</sup>	0	--	--	na	8.1E+02	--	1.1E+04	--	--	--	--	--	--	--	--	1.1E+04
2,4,6-Trichlorophenol <sup>c</sup>	0	--	--	na	6.5E+01	--	na	--	--	--	--	--	--	--	--	9.0E+02
2-(2,4,5-Trichlorophenoxy) propionic acid (Silvex)	0	--	--	na	--	--	na	--	--	--	--	--	--	--	--	--
Vinyl Chloride <sup>c</sup>	0	--	--	na	6.1E+01	--	na	--	--	--	--	--	--	--	--	8.4E+02
Zinc	0	2.5E+02	1.3E+02	na	6.9E+04	na	4.3E+05	--	--	--	--	--	--	6.0E+02	7.5E+02	na

Notes:

- All concentrations expressed as micrograms/liter (ug/l), unless noted otherwise
- Discharge flow is highest monthly average or Form 2C maximum for Industries and design flow for Municipals
- Metals measured as Dissolved, unless specified otherwise
- "C" indicates a carcinogenic parameter
- Regular WLAs are mass balances (minus background concentration) using the % of stream flow entered above under Mixing Information.  
Antidegradation WLAs are based upon a complete mix.  
Antideg. Baseline = (0.25(WQC - background conc.) + background conc.) for acute and chronic  
= (0.1(WQC - background conc.) + background conc.) for human health
- WLAs established at the following stream flows: 1Q10 for Acute, 30Q10 for Chronic Ammonia, 7Q10 for Other Chronic, 30Q5 for Non-carcinogens.  
Harmonic Mean for Carcinogens, and Annual Average for Dioxin. Mixing ratios may be substituted for stream flows where appropriate.

Metal	Target Value (SSTV)
Antimony	2.7E+04
Arsenic	3.2E+02
Barium	na
Cadmium	4.3E+00
Chromium III	2.8E+02
Chromium VI	1.5E+01
Copper	3.0E+01
Iron	na
Lead	5.5E+01
Manganese	na
Mercury	3.2E-01
Nickel	7.7E+01
Selenium	1.7E+01
Silver	1.6E-01
Zinc	2.4E+02

Note: do not use QL's lower than the minimum QL's provided in agency guidance

Facility = Doswell WWTP expansion  
Chemical = Ammonia  
Chronic averaging period = 30  
WLAa = 44  
WLAc = 12  
Q.L. = .2  
# samples/mo. = 30  
# samples/wk. = 8

Summary of Statistics:

# observations = 1  
Expected Value = 6  
Variance = 12.96  
C.V. = 0.6  
97th percentile daily values = 14.6005  
97th percentile 4 day average = 9.98274  
97th percentile 30 day average = 7.23631  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

6

Guidance Memorandum No. 00-2011 directs that an ammonia effluent concentration of 9 mg/L be used to evaluate the need for an ammonia limitation for a municipal discharge. Although this discharge consists predominantly of industrial wastewater, it is reasonable to check to see if the cited guidance would result in a limitation. In this case, the permit already limits TKN to 10 mg/L. Ammonia typically makes up 40% to 60% of the TKN in a municipal effluent. Ammonia makes up 46% of the TKN in the Bear Island wastewater (see "Outfall 001 – Supplement to Table I"). Using 60% as a worse case scenario, the ammonia concentration could be as high 6.0 mg/L, which is the concentration used in the above analysis ( $10 \times 0.6 = 6$ ). The above result that "no limit is required" establishes that the TKN limitation is also protective of the ammonia water quality standard. Note that the number of samples per month used in the above analysis matches the frequency of BOD monitoring.



Facility = Doswell WWTP expansion

Chemical = Chloride

Chronic averaging period = 4

WLAa = 2000000

WLAc = 1300000

Q.L. = 1

# samples/mo. = 1

# samples/wk. = 1

#### Summary of Statistics:

# observations = 1

Expected Value = 29000

Variance = 3027600

C.V. = 0.6

97th percentile daily values = 70569.1

97th percentile 4 day average = 48249.9

97th percentile 30 day average = 34975.5

# < Q.L. = 0

Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

29000

Facility = Doswell WWTP expansion  
Chemical = Total Residual Chlorine  
Chronic averaging period = 4  
WLAa = 45  
WLAc = 61

Q.L. = 0.1  
# samples/mo. = 1  
# samples/wk. = 1

#### Summary of Statistics:

# observations = 3  
Expected Value = 360  
Variance = 46656  
C.V. = 0.6  
97th percentile daily values = 876.030  
97th percentile 4 day average = 598.964  
97th percentile 30 day average = 434.179  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

#### **A limit is needed based on Acute Toxicity**

Maximum Daily Limit = 45  
Average Weekly Limit = 45  
Average Monthly Limit = 45

The data are:

190  
410  
480

Chlorine is not used for disinfection at the Doswell treatment plant and chlorine is not used in the Bear Island process. The above concentrations were determined in conjunction with the failed *Ceriodaphnia dubia* chronic bioassay test in March 2007 (see Attachment 8). These TRC concentrations are believed to be false positives due to possible interference by manganese or alkalinity. Because chlorine is not used at either site, limitations are not included in the draft permit. (It is not appropriate to "force" chlorine limitations with an input of value of 20,000 µg/L per Guidance Memorandum No. 00-2011 because chlorine is not added to the system at any point.)

Facility = Doswell WWTP expansion  
Chemical = Dissolved Copper  
Chronic averaging period = 4  
WLAa = 75  
WLAc = 57  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 6  
Variance = 12.96  
C.V. = 0.6  
97th percentile daily values = 14.6005  
97th percentile 4 day average = 9.98274  
97th percentile 30 day average = 7.23631  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

6

The dissolved copper data reported with the permit renewal application were 6 µg/L, <5 µg/L, and <5 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the copper data.

Facility = Doswell WWTP expansion  
Chemical = Cyanide  
Chronic averaging period = 4  
WLAa = 52  
WLAc = 29  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 2  
Expected Value = 10.5  
Variance = 39.69  
C.V. = 0.6  
97th percentile daily values = 25.5508  
97th percentile 4 day average = 17.4697  
97th percentile 30 day average = 12.6635  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

11  
10

The cyanide data reported with the permit renewal application were 11 µg/L, 10 µg/L, and <10 µg/L (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the cyanide data. Note in Attachment 6A that a cyanide study was conducted starting in March 2004 and ending in October 2005. The above data are consistent with the data collected during that study period. Although the data from the cyanide study are more than three years old, they are still representative and could have been included in the above analysis. The above analysis using only two data points is a more extreme analysis however, which indicates that limitations are not needed.

Facility = Doswell WWTP expansion  
Chemical = Dissolved Lead  
Chronic averaging period = 4  
WLAa = 900  
WLAc = 92  
Q.L. = 1  
# samples/mo. = 1  
# samples/wk. = 1

Summary of Statistics:

# observations = 1  
Expected Value = 30  
Variance = 324  
C.V. = 0.6  
97th percentile daily values = 73.0025  
97th percentile 4 day average = 49.9137  
97th percentile 30 day average = 36.1815  
# < Q.L. = 0  
Model used = BPJ Assumptions, type 2 data

**No Limit is required for this material**

The data are:

30

The dissolved lead data reported with the permit renewal application were (all in µg/L): <20, <20, 30, <20, <20, <20, <20, <20, and <20 (see Attachment 6A). In accordance with a memorandum dated January 29, 2003 from Allan Brockenbrough regarding mixed data sets that include censored data (values reported as less than a quantification limit (QL)) and uncensored data (>QL; i.e., a real number), the reasonable potential analysis is initially done using only the uncensored data. If limitations are not indicated, then the analysis is complete. That is the case with the lead data.

Facility = Doswell WWTP expansion

Chemical = Dissolved Zinc

Chronic averaging period = 4

WLAa = 600

WLAc = 750

Q.L. = 1

# samples/mo. = 1

# samples/wk. = 1

#### Summary of Statistics:

# observations = 11

Expected Value = 133.937

Variance = 1605.77

C.V. = 0.299185

97th percentile daily values = 222.573

97th percentile 4 day average = 175.236

97th percentile 30 day average = 147.698

# < Q.L. = 0

Model used = lognormal

**No Limit is required for this material**

The data are:

108

101

134

218

173

98

113

110

104

109

204